

-----NUMBER THIRTY ONE (31)-----

-----DEED OF RATIFICATION AND CONVERSION-----

-----TO PUBLIC INSTRUMENT OF QUITCLAIM DEED-----

-----CLEAN PARCEL ELEVEN (11)-----

---At San Juan, Puerto Rico, this sixth (6th) day of
May, Two Thousand Thirteen (2013).-----


-----BEFORE ME-----

---JORGE L. MENDIN, Attorney at Law and Notary
Public in and for Puerto Rico, residing at San
Juan, Puerto Rico and with offices at 60 José Martí
Street, Hato Rey, San Juan, Puerto Rico.-----

-----APPEAR-----

---AS PARTY OF THE FIRST PART: United States of
America, hereinafter "Grantor", acting by and
through the Department of the Navy (the "Navy"),
Real Estate Contracting Officer, under and pursuant
to the powers and authority contained in the
provisions of Section 2905(b)(4) of the Defense
Base Closure and Realignment Act of 1990, 10 U.S.C.
§ 2687 note, as amended, and the implementing
regulations of the Department of Defense (32 C.F.R.
Part 174), having an address of four thousand nine
hundred eleven (4911) South Broad Street,
Philadelphia, Pennsylvania herein represented by
Gregory C. Preston, also known as Gregory Charles
Preston, of legal age, married and resident of the
State of New Jersey, United States of America, who
is authorized to appear in this deed as real estate
contracting officer, by virtue of that Certificate
of Appointment signed by the Assistant Secretary of
the Navy (Installations and Environment) on August
eighteenth (18th), Two Thousand Six (2006).-----

msb
cfb



---AS PARTY OF THE SECOND PART: the Commonwealth of Puerto Rico, hereinafter "Grantee", acting by and through the Local Redevelopment Authority for Naval Station Roosevelt Roads, public corporation and government instrumentality of the Commonwealth of Puerto Rico, herein represented by its Executive Director, María de Lourdes Blázquez Arsuaga, of legal age, married and resident of Guaynabo, Puerto Rico, as authorized by the Resolution, signed on April thirty (30) two thousand thirteen (2013), by the Secretary of Economic Development and Commerce, Alberto Bacó Bagué, President of the Board of Directors, and certified by the Secretary of the Board of Directors, Francisco Acevedo, on May second (2nd) of the year two thousand thirteen (2013), under affidavit number 16,209.-----

MBB
AB



---I, the Notary, certify that I am personally acquainted with the persons appearing herein and by their statements I further certify as to their age, civil status, profession and residence. They assure me that they have and in my judgment they do have the necessary legal capacity to execute this instrument, and accordingly they do hereby.-----

-----STATE-----

---FIRST: The United States of America and the Commonwealth of Puerto Rico entered into a Quitclaim Deed dated May six (6), Two Thousand Thirteen (2013), executed by the United States of America, represented by Gregory C. Preston, Real Estate Contracting Officer and the Local Redevelopment Authority for Naval Station Roosevelt Roads represented by María de Lourdes Blázquez

Arsuaga, as its Executive Director, hereinafter "Quitclaim Deed".-----

---SECOND: The appearing parties state that the Quitclaim Deed pursuant to which the United States of America transferred to the Local Redevelopment Authority for Naval Station Roosevelt Roads the title of the following described property, hereinafter the "Property", is presently in effect:-----

---"Rural: Parcel of land identified as Sale Parcel Roman Numeral Two (II) B, situated in the Ward of Guayacan, Municipality of Ceiba, Puerto Rico, containing an area of three hundred eighty-three thousand one hundred sixty-seven point zero (383,167.0) square meters, equivalent to ninety-seven point four hundred eighty-eight (97.488) cuerdas, more or less, bounded on the North and West, by lands of the principal estate from which it is segregated, property of the United States of America; on the East and South, by the Caribbean Sea."-----

---The Property was segregated from property number 9,752 recorded at Page 76 of Volume 151 of Ceiba, Registry of the Property, Fajardo Section, and appears recorded at Page 139 of Volume 163 of Ceiba, property number 10,300.-----

---Due to changes affecting the properties adjacent to its boundaries the general surface description of the Property has changed and its new description is as follows:-----

-----CLEAN PARCEL ELEVEN (11)-----

---"Rural: Parcel of land identified as Clean Parcel Eleven (11) (formerly Sale Parcel Roman Numeral Two (II) B), situated in the Ward of Guayacan, Municipality of Ceiba, Puerto Rico, containing an area of three hundred eighty-three thousand one hundred sixty-seven point zero zero zero (383,167.000) square meters equivalent to ninety-seven point four hundred eighty-eight (97.488) cuerdas, more or less, bounded on the North by Conservation Zone 12, property of the Commonwealth of Puerto Rico, Department of Natural Resources, on the South by the Caribbean Sea, on the East by the Caribbean Sea and on the West by Conservation Zone 13, property

msb.
gfb



of the Commonwealth of Puerto Rico, Department of Natural Resources and Ensenada Honda."-----

---THIRD: The Grantor acquired title to the Property by virtue of Deed of Segregations and Description of Remnant Deed Number Five Hundred Seventy Six (576), executed on the eight (8th) day of October, Two Thousand Ten (2010), before Notary Public Raúl J. Vilá Selles.-----

---FOURTH: The Property is free of liens and encumbrances except those that may appear of record.-----

---FIFTH: The Grantor, as agreed in the Quitclaim Deed for and in consideration of the perpetual use of the Property, transfers to the Grantee and to its successors and assigns, subject to the reservations, exceptions, restrictions, conditions and covenants expressed and set forth in the Quitclaim Deed, all rights, title and interest in and to the Property.-----

---SIXTH: This conveyance is made subject to any and all existing rights-of-way, easements, covenants and agreements affecting the Property.---

---SEVENTH: It is understood and agreed that the Grantee, its assigns, and all parties shall comply with all applicable Federal, State, municipal, and local laws, rules, orders, ordinances, and regulations in the occupation, use, and operation of the Property.-----

---EIGHT: The Quitclaim consists of eleven (11) pages. Appended thereto are five (5) Exhibits that the appearing parties have agreed to attach to the first certified copy of this deed for purposes of

MSB.
RR



recordation.-----

---NINTH: The appearing parties have agreed to convert the Quitclaim Deed into a public instrument for the purpose of recording it in the corresponding section of the Registry of Property of Puerto Rico and hereby do so by delivering the Quitclaim Deed to me, the Notary, which I proceed to attach to the original of the Quitclaim Deed so as to make it an integral part of my protocol of public instruments for the current year.-----

---TENTH: In addition to the contents of this public deed, the appearing parties hereby ratify and confirm all of the terms and conditions of the Quitclaim Deed and acknowledge that the attached document which they have delivered to me contains all the terms, covenants and conditions of their agreement, as per the terms of the present deed.---

---ELEVENTH: The appearing parties hereby agree to the extent required by law applicable to the United States of America, to fully cooperate to remedy promptly any and all technical defects and irregularities of title that may constitute an impediment or bar to the due and proper recordation of this deed in the Registry of Property, free from defects, including, without limitation, the execution and filing for record of any supplementary or clarification deeds, affidavits, and other public and/or private documents. Any obligation created on the United States of America, is specifically made subject to the availability of appropriated funds to be used for such purposes. Nothing contained herein shall be interpreted to

MSB
JB



require obligations or payments by the United States of America that are in violation of the Anti-Deficiency Act, 31 U.S.C § 1341.-----

---TWELFTH: Only for purposes of recording the present deed at the Registry of the Property, the Property is valued at ONE THOUSAND DOLLARS (\$1,000.00).-----

---THIRTEENTH: The appearing parties hereby request the Registrar of the Property to record the Quitclaim Deed which has been acknowledged, ratified and converted to a public deed hereunder, together with the restrictive covenants therein stated.-----

-----ACCEPTANCE-----

---The appearing parties in accordance with the particulars of this Deed accept the same, in all its parts after, I, the Notary, gave them the necessary legal admonitions and warnings pertinent to this public instrument. Thus, the appearing parties state and execute this deed in my presence after having read the same, and place their initials on each and every page hereof and sign their name on the last page of this deed, before me, the Notary, that as to everything else hereinbefore stated, I the Notary, hereby ATTEST.--

MSB
off



M. S. Blazg
George Preston

[Signature]

QUITCLAIM DEED
Clean Parcel 11 (Sale Parcel IIB)

1 THIS INDENTURE ("Quitclaim Deed") is made the 6th day of May, 2013 between
2 **United States of America**, acting by and through the Secretary of the Navy, NAVFAC Base
3 Closure Program Management Office Southeast, Charleston, South Carolina, hereinafter referred
4 to as "GOVERNMENT," and **Local Redevelopment Authority for Naval Station Roosevelt**
5 **Roads**, a government instrumentality of the Commonwealth of Puerto Rico ("Commonwealth"),
6 created, operated, and existing under and by virtue of the laws of the Commonwealth, and
7 designated by the Commonwealth and the Office of Economic Adjustment on behalf of the
8 Secretary of Defense as the public agency to plan, promote, and implement the redevelopment
9 of the former Naval Station Roosevelt Roads, hereinafter referred to as "GRANTEE." It is based
10 upon the following facts:
11

12 **Recitals**
13

14 A. Pursuant to Section 8132 of the Department of Defense Appropriations Act for
15 Fiscal Year 2004 (Public Law No. 108-87; the "Appropriations Act"), the GOVERNMENT was
16 directed to close Naval Station Roosevelt Roads, Puerto Rico ("NSRR") no later than six (6)
17 months after the enactment of the Appropriations Act, and to do so pursuant to the procedures
18 and authorities contained in the Defense Base Closure and Realignment Act of 1990, as amended
19 (title XXIX of Public Law No. 101-510, 10 U.S.C. § 2687 note; the "Base Closure Act").
20

21 B. Pursuant to the power and authority provided by Section 2905(b)(4) of the Base
22 Closure Act and the implementing regulations of the Department of Defense (32 C.F.R. Part
23 174), the GOVERNMENT is authorized to convey surplus property at a closing installation to a
24 local redevelopment authority for economic development purposes.
25

26 C. On August 30, 2006, the Office of Economic Adjustment of the Department of
27 Defense recognized the GRANTEE, also known as the Portal del Futuro Authority and the
28 Roosevelt Roads Naval Base Lands and Facilities Redevelopment Authority, as the local
29 redevelopment authority for purposes of implementing the local redevelopment plan at NSRR.
30

31 D. GRANTEE, by application dated 17 December 2010, requested an "Economic
32 Development Conveyance" ("EDC") of a portion of the surplus property comprised of
33 approximately 1370.20 acres of the former Naval Station Roosevelt Roads, Ceiba, Puerto Rico.
34

35 E. The GRANTEE's EDC application was accepted by the GOVERNMENT on 16
36 September 2011.
37

38 F. The GOVERNMENT and the GRANTEE executed an Economic Development
39 Conveyance Memorandum of Agreement on December 20, 2011 ("Original Agreement")
40 detailing the specifics of the transfer of property under the Government-approved EDC,

Clean Parcel 11 Deed
Page 2.

1 including the consideration to be paid by the GRANTEE to the GOVERNMENT for such
2 transfer.

3
4 G. The Original Agreement did not address ownership of a parcel consisting of
5 approximately one thousand, five hundred and forty-two (1,542) acres at NSRR referred to as
6 "Parcel 1" and a parcel consisting of approximately four hundred and ninety-seven (497) acres at
7 NSRR referred to as "Parcel 2."

8
9 H. The GOVERNMENT and the GRANTEE executed an amendment to the Original
10 Agreement on December 11, 2012 ("Amendment No. 1") to address the transfer of Parcel 1 and
11 Parcel 2 to the GRANTEE (the Original Agreement, as amended by Amendment No. 1, is
12 referred to herein as the "EDC Agreement").

13
14 I. GRANTEE hereby offers consideration in the amount set forth in the EDC
15 Agreement, plus other good and valuable consideration, to it in hand paid by GRANTEE, the
16 receipt of which is hereby acknowledged; and GOVERNMENT has granted, bargained, sold,
17 and released and by these presents does grant, bargain, sell, and release unto the said
18 GRANTEE, its successors, and assigns, all right title and interest in and to that certain parcel of
19 real property at the former NSRR and identified as "Clean Parcel 11" by the NSRR Disposal
20 Map attached hereto and made a part hereof as **Exhibit "A."**

gop
WJB

21
22 NOW THEREFORE, by the acceptance of this Quitclaim Deed or any rights hereunder,
23 the GRANTEE, for itself, its successors and assigns, agrees that the transfer of all the property
24 transferred by this Quitclaim Deed is accepted subject to the following terms, restrictions,
25 reservations, covenants, and conditions set forth below, which shall run with the land, provided
26 that the property transferred hereby may be successively transferred only with the proviso that
27 any such subsequent transferee assumes all of the obligations imposed upon the GRANTEE by
28 the provisions of this Quitclaim Deed with respect to the property being transferred.

29
30 IN CONSIDERATION OF THE FOREGOING, of the terms and conditions set forth
31 below and of other good and valuable consideration (the receipt and adequacy of which, as
32 consideration, the parties hereto both acknowledge), the parties hereto, intending to be legally
33 bound hereby, have agreed to, and do hereby, effectuate the conveyance set forth below.

34
35 **Conveyance Language**

36
37 GOVERNMENT does hereby, subject to any easements and encumbrances of record
38 and subject to the reservations, exceptions, notices, covenants, conditions, and restrictions
39 expressly contained herein, grant, sell, convey, remise, release, and quitclaim unto GRANTEE,
40 its heirs, successors, and its assigns, without any warranty, express or implied, as to the quantity
41 or quality of GOVERNMENT's title (except such warranties as are specifically set forth herein,
42 required by 42 U.S.C. § 9620(h)(4), or otherwise required by law), all GOVERNMENT's right,
43 title, and interest in that certain real property, comprising 94.682 acres or 97.488 cuerdas, as per

Clean Parcel 11 Deed

Page 3.

1 plat or land plot plan prepared by Integra - Architects and Engineers, and recorded at the
2 Registry of Property with this same total area of cuerdas (collectively, "PROPERTY"),
3 including, but not limited to the underlying, estate, buildings, structures, and improvements
4 situated or installed thereon, commonly known as and referred to herein as Clean Parcel Eleven (CP-
5 11) (formerly Sale Parcel Roman Numeral Two (II) (B)), more fully described on the documents
6 attached to this Quitclaim Deed and incorporated herein as **Exhibit "B"**.

7
8 TOGETHER WITH all and singular the ways, waters, water-courses, driveways, rights,
9 hereditaments and appurtenances, whatsoever thereunto belonging, or in any wise appertaining,
10 and the reversions and remainders, rents, issues and profits thereof; and all the estate, right, title,
11 interest, property, claim and demand whatsoever of GOVERNMENT, in law, equity, or
12 otherwise howsoever, of, in, and to the same and every part thereof, and

13
14 TO HAVE AND TO HOLD the said lots or pieces of ground above described, the
15 hereditaments and premises hereby granted, or mentioned and intended so to be, with the
16 appurtenances, unto the said GRANTEE, its heirs, its successors, and its assigns, and subject to
17 the reservations, restrictions, and conditions set forth in this instrument, to and for the only
18 proper use and behalf of the said GRANTEE, its heirs, its successors, and its assigns forever.

gg
mjk

19
20 **Special Sections**

21
22 **I. Access Easements:** GRANTEE, upon acceptance of the PROPERTY, shall enjoy the
23 right and use of, and GRANTOR hereby assigns to GRANTEE, GRANTEE's interest in that
24 certain non-exclusive easement(s), constituted by public deed number five hundred, seventy-five
25 (575), executed on 8 October 2010 for the benefit of the GOVERNMENT, its successors, and
26 assigns, all as illustrated by **Exhibit "C"**.

27
28 **Environmental Notices for the Property**

29
30 **II. Notice of Environmental Condition:** Information concerning the environmental
31 condition of the PROPERTY is contained in the document known as the **Finding of Suitability**
32 **to Transfer** dated December 2007 (Sale Parcel II – Capehart), which is attached hereto and
33 made a part hereof as **Exhibit "D"** (the "FOST"), the receipt of which is hereby acknowledged
34 by the GRANTEE. An **Environmental Condition of Property (ECP)** report is referenced in
35 the FOST; the FOST and ECP reference environmental conditions on the PROPERTY. The
36 FOST sets forth the basis for the GOVERNMENT's determination that the PROPERTY is
37 suitable for transfer. Together, the ECP and FOST contain all pertinent information currently
38 known by GOVERNMENT as to the environmental condition of the PROPERTY. GRANTEE
39 hereby acknowledges that it has been provided copies of the ECP and FOST. The specific
40 environmental conditions described in the FOST and ECP, which are applicable to the
41 PROPERTY, are contained in this Quitclaim Deed.

Clean Parcel 11 Deed

Page 4.

1 **III. Property Covered by Covenant and Access Rights Made Pursuant to Section**
2 **120(h)(4)(D) of the Comprehensive Environmental Response, Compensation, and Liability**
3 **Act of 1980 (42 U.S.C. § 9620(h)(4)(D)):** For the property, the Grantor provides the following
4 covenants and retains the following access rights:

5 a. **Covenant Pursuant to Section 120(h)(4)(D)(i) of the Comprehensive**
6 **Environmental Response, Compensation, and Liability Act of 1980 (42 U.S.C. §**
7 **9620(h)(4)(D)(i)):** Pursuant to Section 120(h)(4)(D)(i) of the Comprehensive Environmental
8 Response, Compensation and Liability Act of 1980 (42 U.S.C. § 9620(h)(4)(D)(i)), the United
9 States warrants that any response action or corrective action found to be necessary after the date
10 of this deed for contamination existing on the PROPERTY prior to the date of this deed shall be
11 conducted by the United States.
12

13 b. **Access Rights Pursuant to Section 120(h)(4)(D)(ii) of the Comprehensive**
14 **Environmental Response, Compensation, and Liability Act of 1980 (42 U.S.C. §**
15 **9620(h)(4)(D)(ii)):** The United States retains and reserves a perpetual and assignable easement
16 and right of access on, over, and through the PROPERTY, to enter upon the PROPERTY in any
17 case in which an environmental response or corrective action is found to be necessary on the part
18 of the United States, without regard to whether such environmental response or corrective action
19 is on the PROPERTY or on adjoining or nearby lands. Such easement and right of access
20 includes, without limitation, the right to perform any environmental investigation, survey,
21 monitoring, sampling, testing, drilling, boring, coring, testpitting, installing monitoring or
22 pumping wells or other treatment facilities, response action, corrective action, or any other action
23 necessary for the United States to meet its responsibilities under applicable laws and as provided
24 for in this instrument. Such easement and right of access shall be binding on the GRANTEE and
25 its successors and assigns and shall run with the land.
26

27 In exercising such easement and right of access, the United States shall provide the GRANTEE
28 or its successors or assigns, as the case may be, with reasonable notice of its intent to enter upon
29 the PROPERTY and exercise its rights under this clause, which notice may be severely curtailed
30 or even eliminated in emergency situations. The United States shall use reasonable means to
31 avoid and to minimize interference with the GRANTEE's and the GRANTEE's successors' and
32 assigns' quiet enjoyment of the PROPERTY. At the completion of work, the work site shall be
33 reasonably restored. Such easement and right of access includes the right to obtain and use utility
34 services, including water, gas, electricity, sewer, and communications services available on the
35 PROPERTY at a reasonable charge to the United States. Excluding the reasonable charges for
36 such utility services, no fee, charge, or compensation will be due the GRANTEE, nor its
37 successor and assigns, for the exercise of the easement and right of access hereby retained and
38 reserved by the United States.
39

40 In exercising such easement and right of access, neither the GRANTEE nor its successors and
41 assigns, as the case may be, shall have any claim at law or equity against the United States or any
42 officer, employee, agent, contractor of any tier, or servant of the United States based on actions

gpp
MJB

Clean Parcel 11 Deed
Page 5.

1 taken by the United States or its officers, employees, agents, contractors of any tier, or servants
2 pursuant to and in accordance with this clause; Provided, however, that nothing in this paragraph
3 shall be considered as a waiver by the GRANTEE and its successors and assigns of any remedy
4 available to them under the Federal Tort Claims Act.

5
6 **IV. Grantee Notice Requirement Regarding Future Sale or Assignment:** In accordance
7 with that certain RCRA 7003 Administrative Order on Consent (EPA Docket No. RCRA-02-
8 2007-7301) (“Order”), and for as long as such Order is in effect, GRANTEE, on behalf of its
9 heirs, successors and assigns, covenants that it shall provide written notice to the
10 GOVERNMENT of any subsequent sale or assignment of the PROPERTY, or any portion
11 thereof, and provide contact information concerning the new owner or assignee. The following
12 is the point of contact for notice to the GOVERNMENT:

13
14 Director
15 NAVFAC BRAC Program Management Office SE
16 4130 Faber Place Drive
17 Suite 202
18 North Charleston, SC 29405

19
20 In the event GRANTEE, its successors or assigns (each hereinafter called a “Transferor”)
21 conveys the PROPERTY, or any portion thereof, the Transferor shall provide to the party
22 acquiring the PROPERTY, or any portion thereof, notice of this requirement.

23
24 **V. Lead Based Paint Hazard Disclosure and Acknowledgment:** The PROPERTY
25 contains improvements that, due to their age, are likely to have been painted with lead based
26 paint.

27
28 1. Lead from paint, paint chips, and dust can pose health hazards if not managed
29 properly. Pursuant to 40 C.F.R. Section 745.113, the following notice is provided: “Every
30 purchaser of any interest in residential real property on which a residential dwelling was built
31 prior to 1978 is notified that such property may present exposure to lead from lead-based paint
32 that may place young children at risk of developing lead poisoning. Lead poisoning in young
33 children may produce permanent neurological damage, including learning disabilities, reduced
34 intelligence quotient, behavioral problems, and impaired memory. Lead poisoning also poses a
35 particular risk to pregnant women. The seller of any interest in residential real property is
36 required to provide the buyer with any information on lead-based paint hazards from risk
37 assessments or inspections in the seller's possession and notify the buyer of any known lead-
38 based paint hazards. A risk assessment or inspection for possible lead-based paint hazards is
39 recommended prior to purchase.” The GRANTEE shall be responsible for managing all lead-
40 based paint and potential lead-based paint in compliance with all applicable Federal,
41 Commonwealth, and local laws and regulations.

JCP
ME

Clean Parcel 11 Deed

Page 6.

1
2 2. The GRANTEE hereby acknowledges the required disclosure of the presence of
3 any known LBP and/or LBP hazards in target housing constructed prior to 1978 in accordance
4 with the Residential Lead-Based Paint Hazard Reduction Act of 1992, 42 U.S.C. Section 4852d
5 (Title X). The GRANTOR agrees that it has provided to GRANTEE, and GRANTEE
6 acknowledges the receipt of, available records and reports pertaining to LBP and/or LBP hazards
7 and receipt of the Environmental Protection Agency (EPA) approved pamphlet: Renovate Right:
8 Important Lead Hazard Information for Families, Child Care Providers and Schools.
9 Furthermore, the GRANTEE acknowledges that it has read and understood the EPA pamphlet.

10
11 3. The GRANTEE covenants and agrees that, in any improvements on the
12 PROPERTY defined as target housing by Title X and constructed prior to 1978, LBP hazards
13 will be disclosed to potential occupants in accordance with Title X before use of such
14 improvements as a residential dwelling (as defined in Title X). Further, the GRANTEE
15 covenants and agrees that it shall, or it shall require future transferees of the PROPERTY to,
16 abate LBP hazards in any applicable target housing in accordance with the requirements of Title
17 X, to the extent applicable, before re-occupancy of the residential dwelling, in accordance with
18 applicable laws. "Target housing" means any housing constructed prior to 1978, except housing
19 for the elderly or persons with disabilities (unless any child who is less than six (6) years of age
20 resides, or is expected to reside, in such housing) or any zero-bedroom dwelling.

ggp
mfb

21
22 4. The GRANTEE acknowledges that the GRANTOR assumes no liability for costs
23 or any damages for personal injury, illness, disability, or death to the GRANTEE, or to any other
24 person, including members of the general public, arising from or incident to the purchase,
25 transportation, removal, handling, use, disposition, or other activity causing or leading to contact
26 of any kind whatsoever with LBP on the PROPERTY, arising after the conveyance of the
27 PROPERTY from the GRANTOR to the GRANTEE, whether the GRANTEE has properly
28 warned, or failed to properly warn, the persons injured.

29
30 5. Upon execution of this Quitclaim Deed, the GRANTEE covenants and agrees that
31 it shall, and it shall require future transferees of the PROPERTY to, be responsible at its own
32 cost and expense for the maintenance and management of LBP and LBP hazards located in the
33 improvements on the PROPERTY, and the GRANTEE shall comply with Title X and all
34 applicable Federal, Commonwealth, and local laws relating to LBP.

35
36 **VI. Asbestos Containing Materials Disclosure and Acknowledgment:** GRANTEE hereby
37 acknowledges that asbestos containing materials (ACM) remain in buildings on the PROPERTY
38 and agrees to manage any and all remaining ACM in accordance with applicable laws and
39 regulations.

40
41 1. GRANTOR covenants that it has provided to the GRANTEE all documentation in
42 its possession regarding the presence of any known ACM, and the GRANTEE acknowledges
43 receipt of documentation disclosing the presence of any known ACM in the buildings and

Clean Parcel 11 Deed

Page 7.

1 structures on the PROPERTY. The GRANTEE covenants that it will, and it will require future
2 transferees of the PROPERTY to, prohibit use or occupancy of buildings and structures, or
3 portions thereof, containing known friable and accessible, or damaged ACM prior to abatement
4 of the friable and accessible, or damaged ACM or demolition of the building or structure, to the
5 extent required by applicable law.
6

7 2. The GRANTEE covenants and agrees that it shall require, and it shall require
8 future transferees of the PROPERTY, in its use and occupancy of the PROPERTY, including but
9 not limited to demolition of buildings containing ACM, to comply with all applicable Federal,
10 Commonwealth and local laws relating to ACM. The GRANTEE acknowledges that the
11 GRANTOR assumes no liability for costs or any damages for personal injury, illness, disability,
12 or death to the GRANTEE, or to any other person, including members of the general public,
13 arising from or incident to the purchase, transportation, removal, handling, use, disposition, or
14 activity causing or leading to contact of any kind whatsoever with ACM in the improvements on
15 the PROPERTY, arising after the conveyance of the PROPERTY from the GRANTOR to the
16 GRANTEE, whether the GRANTEE has properly warned, or failed to properly warn the persons
17 injured.
18

19 3. The GRANTEE covenants and agrees that it shall, and it shall require future
20 transferees of the PROPERTY, upon demolition of the improvements located on the
21 PROPERTY, remove all ACM in accordance with the EPA National Emission Standard for
22 Hazardous Air Pollutants (NESHAP), 40 C.F.R. Section 61, Subpart M and applicable
23 Commonwealth laws and regulations.
24

25 **VII. Non-interference with Navigable Airspace:** The GRANTEE covenants for itself,
26 successors, and assigns, and every successor in interest to the PROPERTY herein described, or
27 any part thereof, that any construction or alteration is prohibited unless a determination of no
28 hazard to air navigation is issued by the Federal Aviation Administration in accordance with
29 Title 14, Code of Federal Regulation, Part 77, entitled "Objects Affecting Navigable Airspace",
30 or under the Authority of the Federal Aviation Act of 1958, as amended.
31

32 **VIII. Protection of Archeological Resources:** The GRANTEE shall monitor for
33 archeological artifacts during its construction activities and shall take appropriate action should
34 any artifacts be discovered in accordance with the Memorandum of Agreement between the
35 United States Navy and the Puerto Rico Historic Preservation Officer concerning the disposal of
36 Naval Activity Puerto Rico executed September 28, 2011.
37

38 **IX. Protection of Wetlands:** The GRANTEE is hereby notified that the PROPERTY may
39 contain wetlands. Wetland activities such as filling, draining or altering are regulated by Federal
40 laws. Section 404 of the Clean Water Act (CWA) establishes a program to regulate the
41 discharge of dredged or fill material into waters of the United States, including wetlands.
42 Activities in waters of the United States regulated under this program include fill for

Clean Parcel 11 Deed
Page 8.

1 development, water resource projects (such as dams and levees), infrastructure development
2 (such as highways and airports) and mining projects.

3
4 **General Provisions**

5
6 **X. Conveyance is "As Is – Where Is":** Except as expressly provided in this Quitclaim
7 Deed or as otherwise required by law, the PROPERTY is being conveyed "AS IS" and "WHERE
8 IS," without representation, warranty, or guaranty as to quality, quantity, character, condition,
9 size, kind, or fitness for a particular purpose. In this regard, GRANTEE acknowledges,
10 recognizes and accepts that the plat reflects that the general surface description of the
11 PROPERTY has changed due to changes affecting the properties adjacent to its boundaries. The
12 new legal description of the PROPERTY, after taking account of the changes affecting its
13 boundaries, is also described in **Exhibit "B"** hereto.

14
15 **XI. Covenant Regarding Non-Discrimination:** GRANTEE covenants for itself, its
16 successors, and assigns and every successor in interest to the PROPERTY, or any part thereof,
17 that GRANTEE and such heirs, successors, and assigns shall not discriminate upon the basis of
18 race, color, religion, disability, or national origin in the use, occupancy, sale, or lease of the
19 PROPERTY, or in their employment practices conducted thereon. This covenant shall not apply
20 however, to the lease or rental of a room or rooms within a family dwelling unit, nor shall it
21 apply with respect to PROPERTY used primarily for religious purposes. The United States of
22 America shall be deemed a beneficiary of this covenant without regard to whether it remains the
23 owner of any land or interest therein in the locality of the PROPERTY hereby conveyed and
24 shall have the sole right to enforce this covenant in any court of competent jurisdiction.

JCP
MSB

25
26 **XII. General Notice Provision:**

27
28 To facilitate such future cooperation, the following points of contact have been designated by the
29 GOVERNMENT, GRANTEE, United States Environmental Protection Agency (USEPA) and
30 Puerto Rico Environmental Quality Board (PREQB):

31
32 **GOVERNMENT:** Director
33 NAVFAC BRAC Program Management Office Southeast
34 4130 Faber Place Drive
35 Suite 202
36 North Charleston, SC 29405

37
38 **GRANTEE:** Executive Director
39 Local Redevelopment Authority for Naval Station Roosevelt Roads
40 400 Calaf St.
41 PMB #456
42 San Juan, PR 00918-1314
43

Clean Parcel 11 Deed

Page 9.

- 1 With a copy to: Kutak Rock LLP
- 2 1101 Connecticut Avenue, NW
- 3 Suite 1000
- 4 Washington, DC 20036
- 5 Attention: George Schlossberg, Esq.
- 6
- 7 USEPA: U.S. Environmental Protection Agency
- 8 Region 2
- 9 290 Broadway - 22nd Floor
- 10 New York, NY 10007-1866
- 11 Attention: Chief, RCRA Programs Branch
- 12
- 13 PREQB: Puerto Rico Environmental Quality Board
- 14 Oficina del Presidente - Piso 5 Ave.
- 15 Ponce de Leon #I308
- 16 Carr Estatal 8838
- 17 Sector El Cinco
- 18 Rio Piedras, PR 00926
- 19

XIII. Recording of Title:

21
22 The appearing parties do hereby acknowledge that although this Quitclaim Deed is a valid and
23 legally binding document, it may not fulfill the requirements established by the Mortgage and
24 Registry Property Act of 1979 for the recording of titles at the Registry of Property of Puerto
25 Rico (the "Registry"). Therefore, the appearing parties agree to jointly take all actions
26 reasonably necessary in accordance with and subject to the authorities and limitations prescribed
27 by applicable Federal and Commonwealth law to cause the recordable documents to be executed,
28 filed and registered in the Registry.

29
30 The appearing parties do hereby further acknowledge and recognize that in order for these
31 parcels to exist as separate properties and be developed as intended, it may be necessary for the
32 same to be segregated and the need for necessary easements to be created for the benefit of these
33 parcels may arise. In the event that such easements are granted by the GOVERNMENT, the
34 appearing parties acknowledge that the Recordable Documents must include such transactions
35 and in a timely manner and agree to jointly take all actions reasonably necessary in accordance
36 with and subject to the authorities and limitations prescribed by applicable Federal and
37 Commonwealth law to cause the recordable documents to be executed, filed and registered in the
38 Registry.

39
40 Notwithstanding the foregoing, it is the intent of the appearing parties that immediately upon
41 execution of this Quitclaim Deed, as it appears herein, all right, title and interest in the
42 PROPERTY shall have conveyed to the GRANTEE.

Clean Parcel 11 Deed

Page 10.

1 Any requirement for the obligation or payment of funds by the GOVERNMENT established by
2 any provision of this Quitclaim Deed shall be subject to the availability of appropriated funds,
3 and no provision herein shall be interpreted to require an obligation or payment in violation of
4 the Anti-Deficiency Act, 31 U.S.C. Section 1341.

5
6 **XIV. Counterparts:** This Quitclaim Deed may be executed in counterparts, each of which
7 shall be deemed an original, and such counterparts may be assembled to form a single document.

*gob
msb*

8
9

The remainder of this page is intentionally left blank

Execution

IN WITNESS WHEREOF, the undersigned, acting pursuant to the authority vested unto him as Real Estate Contracting Officer for the United States of America, has hereunto executed this Quitclaim Deed as of the day and year first written above.

UNITED STATES OF AMERICA

By: Navy BRAC PMO

By: 
Gregory C. Preston
Real Estate Contracting Officer

gcp

Affidavit No. 996 (copy 4)

Acknowledged and subscribed before me by Gregory C. Preston, of legal age, married, public servant and resident of Mount Laurel, New Jersey, in his capacity as Real Estate Contracting Officer of the NAVY BRAC PMO of the Department of the Defense of the United States of America, who I personally know.

In San Juan, Puerto Rico on this 6th day of May, 2013.



[Signatures Continue on Following Page]

Clean Parcel 11 Deed
Page 12.

IN WITNESS WHEREOF, the undersigned, acting pursuant to the authority vested unto her, as Executive Director, has hereunto executed and accepted this Quitclaim Deed as of the day and year first written above.

MLB

LOCAL REDEVELOPMENT AUTHORITY
NAVAL STATION ROOSEVELT ROADS

By: *MLB*
María L. Blázquez Arsuaga
Executive Director

Affidavit No. 997 (copy 4)

Acknowledged and subscribed to before me, by María L. Blázquez Arsuaga, of legal age, married, public servant and resident of Guaynabo, Puerto Rico in his capacity as Executive Director, who I personally know.

In San Juan, Puerto Rico this 6th day of May, 2013.



[Handwritten signature]

Exhibit "A"


NSRR DISPOSAL MAP

gco
hbb.

Handwritten signature

Exhibit A

04.30.13



LEGEND

- FOST Clean Parcel 1
- FOST Clean Parcel 2
- FOSL/LIFOC Parcels
- Parcel 3
- NA Puerto Rico

Exhibit "B"

**LEGAL DESCRIPTIONS OF PROPERTY CONVEYED
CLEAN PARCEL 11**

The surface measurement as per the plat or plot plan prepared by Integra – Architects and Engineers is as follows:

“Rural: Parcel of land identified as Clean Parcel Eleven (11) (formerly Sale Parcel Roman Numeral Two (II) B), situated in the Ward of Guayacan, Municipality of Ceiba, Puerto Rico, containing an area of three hundred eighty-three thousand one hundred sixty-seven point zero zero zero (383,167.000) square meters equivalent to ninety-seven point four hundred eighty-eight (97.488) cuerdas, more or less, bounded on the North by Conservation Zone 12, property of the Commonwealth of Puerto Rico, Department of Natural Resources, on the South by the Caribbean Sea, on the East by the Caribbean Sea and on the West by Conservation Zone 13, property of the Commonwealth of Puerto Rico, Department of Natural Resources and Ensenada Honda.”

The surface measurement as recorded at the Registry of the Property is as follows:

"Rural: Parcel of land identified as Sale Parcel Roman Numeral Two (II) B, situated in the Ward of Guayacan, Municipality of Ceiba, Puerto Rico, containing an area of three hundred eighty-three thousand one hundred sixty-seven point zero (383,167.0) square meters, equivalent to ninety-seven point four hundred eighty-eight (97.488) cuerdas, more or less, bounded on the North and West, by lands of the principal estate from which it is segregated, property of the United States of America; on the East and South, by the Caribbean Sea.”

The surface measurement as recorded at the Registry of Property but taking into account changes to the adjacent boundaries is as follows:

-----CLEAN PARCEL ELEVEN (11)-----

“Rural: Parcel of land identified as Sale Parcel Roman Numeral Two (II) B, situated in the Ward of Guayacan, Municipality of Ceiba, Puerto Rico, containing an area of three hundred eighty-three thousand one hundred sixty-seven point zero (383,167.0) square meters, equivalent to ninety-seven point four hundred eighty-eight (97.488) cuerdas, more or less, bounded on the North by Conservation Zone 12 (Commonwealth of Puerto Rico, Department of Natural Resources), on the South by the Caribbean Sea, on the East by the Caribbean Sea and on the West by Conservation Zone 13 (Commonwealth of Puerto Rico, Department of Natural Resources) and Ensenada Honda.”

Exhibit "C"

ACCESS EASEMENTS

gfb
mfb

----DEED NUMBER FIVE HUNDRED SEVENTY FIVE (575)---

----- DEED OF CONSTITUTION OF PATH EASEMENTS-----

---In San Juan, Puerto Rico, this eighth (8th)
day of October of the year two thousand ten
(2010).-----

----- BEFORE ME -----

---RAÚL J. VILÁ SELLES, Attorney-at-Law and Notary
Public in and for the Commonwealth of Puerto Rico,
with office and residence in San Juan, Puerto
Rico.-----

----- APPEARS -----

---AS SOLE PARTY: United States of America, acting
by and through the Department of the Navy, Base
Realignment and Closure Program Management Office
Southeast, under and pursuant to the powers and
authority contained in the provisions of Title Ten
(10), Section Two Thousand Eight Hundred Seventy-
Eight (2878), of the United States Code, and
regulations and orders promulgated thereunder,
having an address of forty-one thirty (4130) Faber
Place Drive, Suite Two Hundred Two (202) North
Charleston, South Carolina herein represented by
Gregory C. Preston, also known as Gregory Charles
Preston, of legal age, married and resident of the
State of New Jersey, United States of America, who
is authorized to appear in this deed as real
estate contracting officer, by virtue of that
Certificate of Appointment signed by B.J. Penn,
Assistant Secretary of the Navy (Installations and
Environment), on August eighteenth (18th), two
thousand six (2006).-----



---I, the Notary Public, do hereby certify and
attest that I personally know the appearing party

and his age, civil status, and residence, by his statements, he assures me to have, and in my judgment he does have, the legal capacity necessary for the execution of this deed, and for that purpose he freely-----

----- STATES-----

---FIRST: That the Airport, the Conservation Zones, Los Machos Three (3), and the Hospital parcels, appear recorded in the Registry of the Property, in favor of the United States of America, described in the English language as follows:-----

----- AIRPORT-----

---"Rural: Parcel of land identified as Airport situated in the Wards of Machos, Chupacallos and Quebrada Seca, Municipality of Ceiba, Puerto Rico, containing six million six hundred sixty-one thousand eight hundred and three point six (6,661,803.6) square meters equivalent to one thousand six hundred ninety-four point nine hundred forty-five (1694.945) cuerdas, more or less. Bounded on the North and West by the Municipality of Ceiba, and on the South and East by lands of the principal estate from which it is segregated."-----

----- CONSERVATION ZONES-----

---"Rural: Parcel of land identified as Conservation Zones situated in the Wards of Los Machos, Guayacán and Quebrada Seca, Municipality of Ceiba and the Ward of Daguao, Municipality of Naguabo, Puerto Rico, containing an area of twelve million eighty five thousand nine hundred and thirty point nine (12,085,930.9) square meters equivalent to three thousand and seventy-four point nine hundred and ninety (3074.990) cuerdas more or less, comprised of the following:-----

---Conservation Zone One (1)-----

---"Rural: Parcel of land identified as Conservation Zone One (1) situated in the Ward of Daguao, Municipality of Naguabo, Puerto Rico containing an area of three hundred seventy-three thousand five hundred and forty-four point six (373,544.6) square meters equivalent to ninety-five point zero four zero (95.040) cuerdas, more or less, bounded on the North and East by lands of the principal estate from which it is segregated; on the South, by Felix Robles and the Municipality of Naguabo, Puerto Rico, and on the West, by the Municipality of Naguabo, Puerto Rico."-----

---Conservation Zone Five (5)-----

---"Rural: Parcel of land identified as Conservation Zone Five (5) situated in the Wards of Guayacan and Quebrada Seca, Municipality of Ceiba, Puerto Rico and the Ward of Daguao, Municipality of Naguabo, Puerto Rico, containing an area of three million six hundred and thirty-nine thousand four hundred and eighty-five point zero (3,639,485.0) square meters, equivalent to nine hundred and twenty-five point nine hundred eighty-four (925.984) cuerdas, more or less, comprising the following:-----

---Portion A. Municipality of Ceiba; -----

---"Rural: Parcel of land identified as Conservation Zone Five (5) situated in the Wards of Guayacan and Quebrada Seca, Municipality of Ceiba, Puerto Rico, containing an area of two million two hundred and seventy thousand eight hundred and five point five (2,270,805.5) square meters, equivalent to five hundred seventy-seven point seven hundred fifty-five (577.755) cuerdas, more or less, bounded on the North, East and West by lands of the principal estate from which it is segregated and on the South by Bahia Algodones."---

---Portion B. Municipality of Naguabo;-----

---"Rural: Parcel of land identified as Conservation Zone Five (5) situated in the Ward of Daguao, Municipality of Naguabo, Puerto Rico, containing an area of one million three hundred sixty-eight thousand six hundred seventy-nine point five (1,368,679.5) square meters, equivalent to three hundred forty-eight point two hundred twenty-nine (348.229) cuerdas, more or less, bounded on the North, East and West by lands of the principal estate from which it is segregated and on the South, by Bahia Algodones."-----

---Conservation Zone Nine (9);-----

---"Rural: Parcel of land identified as Conservation Zone Nine (9) situated in the Ward of Guayacan, Municipality of Ceiba, Puerto Rico containing an area of ten thousand three hundred and twenty-three point one (10,323.1) square meters, equivalent to two point six hundred and twenty-six (2.626) cuerdas, more or less, bounded on the North, South and West by lands of the principal estate from which it is segregated; on the East by the Caribbean Sea."-----

---Conservation Zone Eleven (11);-----

---"Rural: Parcel of land identified as Conservation Zone Eleven (11) situated in the Ward of Guayacan, Municipality of Ceiba, Puerto Rico containing an area of four thousand seven hundred and sixty four point eight (4,764.8) square meters, equivalent to one point two hundred and twelve (1.212) cuerdas, more or less, bounded on

the North, South and West by lands of the principal estate from which it is segregated; on the East by the Caribbean Sea."-----

---Conservation Zone Twelve (12);-----

---"Rural: Parcel of land identified as Conservation Zone Twelve (12) situated in the Ward of Guayacan, Municipality of Ceiba, Puerto Rico, containing an area of seventy thousand two hundred and forty nine point nine (70,249.9) square meters, equivalent to seventeen point eight hundred and seventy three (17.873) cuerdas, more or less, bounded on the North and East by the Caribbean Sea and on the South and West by lands of the principal estate from which it is segregated."-----

---Conservation Zone Thirteen (13);-----

---"Rural: Parcel of land identified as Conservation Zone Thirteen (13) situated in the Ward of Guayacan, Municipality of Ceiba, Puerto Rico containing an area of one million five hundred and forty thousand and ten point nine (1,540,010.9) square meters, equivalent to three hundred and ninety-one point eight hundred and twenty-one (391.821) cuerdas, more or less, bounded on the North by lands of the principal estate from which it is segregated and Ensenada Honda, on the East by Ensenada Honda, on the South by lands of the principal estate from which it is segregated and by the Caribbean Sea, on the West by lands of the principal estate from which it is segregated."-----

---Conservation Zone Twenty-Six (26);-----

---"Rural: Parcel of land identified as Conservation Zone Twenty-Six (26) situated in the Ward of Guayacan, Municipality of Ceiba, Puerto Rico containing an area of one hundred and seventy-one thousand seven hundred and thirty-one point two (171,731.2) square meters, equivalent to forty-three point six hundred and ninety-three (43.693) cuerdas, more or less, bounded on the North, South and West by lands of the principal estate from which it is segregated; on the East by the Ensenada Honda."-----

---Conservation Zone Twenty-Eight (28);-----

---"Rural: Parcel of land identified as Conservation Zone Twenty-Eight (28) situated in the Ward of Guayacan, Municipality of Ceiba, Puerto Rico containing an area of six hundred and seven thousand three hundred and thirty point eight (607,330.8) square meters, equivalent to one hundred and fifty-four point five hundred and twenty-two (154.522) cuerdas, more or less, bounded on the North, East and West by lands of the principal estate from which it is segregated; on the South by the Ensenada Honda."-----

---Conservation Zone Los Machos Parcel One (1);---

---"Rural: Parcel of land identified as Los Machos Parcel One (1) situated in the Ward of Machos, Municipality of Ceiba, Puerto Rico containing an area of two hundred seventy-four thousand forty-two point two (274,042.2) square meters, equivalent to sixty-nine point seven hundred twenty-four (69,724) cuerdas, more or less, bounded on the North by the Majagua River, on the East by lands of the Commonwealth of Puerto Rico Department of Natural Resources, on the South by the lands of the principal estate from which it is segregated, and on the West by lands of Puerto Del Rey."-----

---Conservation Zone Thirty-Nine (39);-----

---"Rural: Parcel of land identified as Conservation Zone Thirty-Nine (39) situated in the Ward of Machos, Municipality of Ceiba, Puerto Rico containing an area of five million three hundred seventy-nine thousand nine hundred and nineteen point nine (5,379,919.9) square meters, equivalent to one thousand three hundred and sixty-eight point seven hundred and ninety-nine (1,368.799) cuerdas, more or less, bounded on the North by Media Mundo and by lands of the principal estate from which it is segregated, on the East by the Caribbean Sea and by lands of the principal estate from which it is segregated and on the South and West by lands of the principal estate from which it is segregated."-----

---Conservation Zone Fifty-Eight (58);-----

---"Rural: Parcel of land identified as Conservation Zone Fifty-Eight (58) situated in the Ward of Guayacan, Municipality of Ceiba, Puerto Rico containing an area of two thousand eighty-eight point six (2,088.6) square meters, equivalent to zero point five hundred and thirty-one (0.531) of a cuerda, more or less, bounded on the North, East and South by lands of the principal estate from which it is segregated; on the West by Ensenada Honda."-----

---Conservation Zone Sixty (60);-----

---"Rural: Parcel of land identified as Conservation Zone Sixty (60) situated in the Ward of Guayacan, Municipality of Ceiba, Puerto Rico containing an area of one thousand nine hundred and ninety-four point seven (1,994.7) square meters, equivalent to zero point five hundred and seven (0.507) of a cuerda, more or less, bounded on the North, East and West by lands of the principal estate from which it is segregated; on the South by the Caribbean Sea."-----

---Conservation Zone Sixty-Five (65);-----

---"Rural: Parcel of land identified as Conservation Zone Sixty-Five (65) situated in the Ward of Machos, Municipality of Ceiba, Puerto Rico containing an area of five thousand six hundred and twenty-four point four (5,624.4) square

meters, equivalent to one point four hundred and thirty-one (1.431) cuerdas, more or less, bounded on the North, East and West by lands of the principal estate from which it is segregated; on the South by the Caribbean Sea."-----

---Conservation Zone Sixty-Six (66);-----

---"Rural: Parcel of land identified as Conservation Zone Sixty-Six (66) situated in the Ward of Machos, Municipality of Ceiba, Puerto Rico containing an area of four thousand eight hundred and twenty point eight (4,820.8) square meters, equivalent to one point two hundred and twenty-seven (1.227) cuerdas, more or less, bounded on the North, East and South by lands of the principal estate from which it is segregated; on the West by the Caribbean Sea."-----

---LOS MACHOS THREE (3)-----

---"Rural: Parcel of land identified as Los Machos Parcel Three situated in the Ward of Machos, Municipality of Ceiba, Puerto Rico, containing five hundred sixty-nine thousand two hundred ninety-eight point three (569,298.3) square meters equivalent to one hundred forty-four point eight hundred forty-five (144.845) cuerdas, more or less. Bounded on the North and South by the lands of the principal estate from which it is segregated, on the East by the edge of water of Puerto Medio Mundo, and on the West by lands of the principal estate from which it is segregated."-----

-----HOSPITAL-----

---"Rural: Parcel of land identified as Hospital situated in the Ward of Machos, Municipality of Ceiba, Puerto Rico, containing an area of one hundred thirteen thousand seventy seven point zero (113,077.0) square meters equivalent to twenty-eight point seven hundred seventy (28.770) cuerdas, more or less, bounded on the North, East, South and West by lands of the principal estate from which it is segregated."-----

---All of the above described parcels were segregated from property number nine thousand seven hundred fifty-two (9,752), recorded at Page seventy-six (76), of volume one hundred fifty-one (151) of Ceiba, Registry of Property of Puerto Rico, Fajardo Section.-----

---As per the Registry of the Property, all of the above parcels are free from liens and encumbrances.-----

---SECOND: That the appearing party represents that it is also the owner and sole title holder of the following parcel of land, which is the remnant after the segregation of the Airport, the Conservation Zones, Los Machos Three (3), and the Hospital parcels. Said remnant is described in the English language as follows, hereinafter

"Remnant":-----

---"Rural: Parcel of land identified as Naval Activity Puerto Rico, formerly Naval Station Roosevelt Roads situated in the Wards of Chupacallos, Los Machos, Ensenada Honda, Guayacan and Quebrada Seca, Municipality of Ceiba and the Ward of Daguao, Municipality of Naguabo, Puerto Rico, containing an area of fourteen million one hundred and seventy seven thousand six hundred and thirty eight point two (14,177,638.2) square meters equivalent to three thousand six hundred and seven point one hundred and seventy-nine (3,607.179) cuerdas more or less, divided into two portions as follows:-----

---Portion A - Municipality of Ceiba - Rural: Parcel of land identified as Naval Activity Puerto Rico, formerly Naval Station Roosevelt Roads situated in the Wards of Chupacallos, Los Machos, Ensenada Honda, Guayacán and Quebrada Seca, Municipality of Ceiba, Puerto Rico, containing an area of twelve million one hundred twenty-eight thousand seven hundred and eighty-one point four (12,128,781.4) square meters equivalent to three thousand and eighty-five point eight hundred and ninety-three (3,085.893) cuerdas, more or less, bounded on the North, by the southerly bank of the Demajagua River and Puerto Del Rey Marina and lands of the United States of America; on the East, by the Caribbean Sea; on the South, by Ensenada Honda, Bahía Algodones and lands of the United States of America; on the West, by the Easterly line of the railroad Right of Way of the Fajardo Development Company.-----

---Portion B - Municipality of Naguabo - Rural: Parcel of land identified as Naval Activity Puerto Rico, formerly Naval Station Roosevelt Roads situated in the Ward of Daguao, Municipality of Naguabo, Puerto Rico containing an area of two million forty-eight thousand eight hundred and fifty-six point eight (2,048,856.8) square meters, equivalent to five hundred and twenty-one point two hundred and eighty-six (521.286) cuerdas, more or less, bounded on the North and East by lands of the United States of America; on the South, by Felix Robles and the Municipality of Naguabo, Puerto Rico; and on the West, by the Municipality of Naguabo, Puerto Rico.-----

---The remnant of property number nine thousand seven hundred fifty-two (9,752), recorded at Page seventy-six (76), of volume one hundred fifty-one (151) of Ceiba, Registry of Property of Puerto Rico, Fajardo Section,-----

---As per the Registry of the Property, the Remnant is free from Liens and encumbrances.-----

---THIRD: The Airport, the Conservation Zones, the Los Machos Three (3), the Hospital parcels and the Remnant resulted from deed of segregations and description of remnant, number five hundred seventy four (574), executed on eighth (8th) day of October, two thousand ten (2010), before Notary Public Raúl J. Vilá Sellés.-----

---FOURTH: The Government hereby reserves and constitutes a perpetual non-exclusive easement for the purpose of motor vehicle and pedestrian ingress and egress over upon and across the Airport parcel for the construction, repair, replacement, maintenance and operation of a two-lane roadway, for the use and benefit of the Conservation Zones parcel, Los Machos Three (3) parcel, the Hospital Parcel and the Remnant, their owners, successors, assigns, tenants, subtenants, licensees, suppliers and customers which easement is described as follows:-----

---"Strip of land located in the wards of Machos, Chupacallos and Quebrada Seca, Municipality of Ceiba, with a total area of thirty-two thousand five hundred ninety-six point two" (32,596.2) square meters, equivalent to eight point two hundred ninety-four (8.294) cuerdas, consisting of:-----

----- Segment Two (2) -----

---"Strip of land having an area of nineteen thousand six hundred fifteen point four (19,615.4) square meters, equivalent to four point nine

hundred ninety-one (4.991) cuerdas, with a length of one thousand three hundred four point zero (1,304.0) meters and a width of fifteen point zero zero (15.00) meters running from North to South."-----

----- Segment Four (4) -----

---"Strip of land having an area of twelve thousand nine hundred eighty point eight (12,980.8) square meters, equivalent to three point three hundred three (3.303) cuerdas, with a length of seven hundred sixty point zero (760.0) meters and a width of fifteen point zero (15.0) meters running from South to North."-----

---FIFTH: To be recorded at the Registry of the Property, the easement is valued at ONE THOUSAND DOLLARS (\$1,000.00).-----

---SIXTH: The appearing party also hereby reserves and constitutes a perpetual non-exclusive easement for the purpose of motor vehicle and pedestrian ingress and egress over, upon and across the Conservation Zones parcel for the construction, repair, replacement, maintenance and operation of various two-lane roadways, for the use and benefit of the Airport parcel, the Los Machos Three (3) parcel, the Hospital Parcel and the Remnant, their owners, successors, assigns, tenants, subtenants, licensees, suppliers and customers which easement is described as follows:-----

---"Strip of land located in the wards of Los Machos, Guayacán and Quebrada Seca, Municipality of Ceiba and the ward of Daguao, Municipality of Naguabo, with a total area of one hundred thirty-eight thousand and twelve point five (138,012.5) square meters, equivalent to thirty-five point one hundred and fourteen (35.114) cuerdas, consisting of:-----

----- Segment Three (3) -----

---"Strip of land having an area of twenty-six thousand four hundred ninety-four point four (26,494.4) square meters, equivalent to six point seven hundred forty-one (6.741) cuerdas, with a length of one thousand seven hundred sixty-six point zero (1766.0) meters and a width of fifteen (15) meters running from Southwest to Northeast, thence Southwest."-----

----- Segment Five (5) -----

---"Strip of land having an area of twenty-two thousand four hundred eleven point five (22,411.5) square meters, equivalent to five point seven hundred two (5.702) cuerdas, with a length of one thousand three hundred point zero (1,300.0) meters and a variable width running from Northwest to Southeast and thence Southwest."-----

----- Segment Eight (8) -----

---"Strip of land having an area of sixteen thousand nine hundred forty-nine point three (16,949.3) square meters, equivalent to four point three hundred twelve (4.312) cuerdas, with a length of one thousand one hundred twenty-nine point zero (1,129.0) meters and a width of fifteen (15) meters running from West to East, thence South to Northeast."-----

----- Segment Nine (9) -----

---"Strip of land having an area of forty-six thousand eight hundred twenty-six point two (46,826.2) square meters, equivalent to eleven point nine hundred fourteen (11.914) cuerdas, with a length of three thousand one hundred sixteen point zero (3116.0) meters and with a variable width running from North to South."-----

----- Segment Fourteen (14) -----

---"Strip of land having an area of nine thousand six hundred thirty-nine point two (9,639.2) square meters, equivalent to two point four hundred fifty-two (2.452) cuerdas, with a length of six hundred forty-two point zero (642.0) meters and a width of fifteen (15) meters running from East to West thence South."-----

----- Segment Eighteen (18) -----

---"Strip of land having an area of six thousand four hundred twenty-one point seven (6,421.7) square meters, equivalent to one point six hundred thirty-four (1.634) cuerdas, with a length of three hundred fifty-five point zero (355.0) meters and a width of eighteen (18) meters running from East to West."-----

----- Segment Twenty (20) -----

---"Strip of land having an area of six thousand four hundred forty-eight point four (6,448.4) square meters, equivalent to one point six hundred forty-one (1.641) cuerdas, with length of four hundred thirty point zero (430.0) meters and a width of fifteen (15) meters running from Southwest to Northeast."-----

----- Segment Twenty Two (22) -----

---"Strip of land having an area of two thousand eight hundred twenty-one point eight (2,821.8) square meters, equivalent to zero point seven

hundred eighteen (0.718) cuerda, with a length of one hundred eighty-eight point zero (188.0) meters and a width of fifteen (15) meters running from North to South."-----

---SEVENTH: To be recorded at the Registry of Property, the easement is valued at ONE THOUSAND DOLLARS (\$1,000.00).-----

---EIGHTH: The appearing party also hereby reserves and constitutes a perpetual non-exclusive easement for the purpose of motor vehicle and pedestrian ingress and egress over, upon and across Los Machos Three (3) parcel for the construction, repair, replacement, maintenance and operation of various two-lane roadways for the use and benefit of the Airport parcel, the Conservation Zones parcel, the Hospital Parcel and the Remnant, their owners, successors, assigns, tenants, subtenants, licensees, suppliers and customers which easement is described as follows:-

-----Segment One (1) I-----

---"Strip of land having an area of ten thousand four hundred twenty-five point five (10,425.5) square meters, equivalent to two point six hundred fifty-three (2.653) cuerdas, with a length of five hundred sixty-eight point zero (568.0) meters and a variable width running from South to North."-----

---NINTH: To be recorded at the Registry of the Property, the easement is valued at ONE THOUSAND DOLLARS (\$1,000.00).-----

---TENTH: The appearing party also hereby reserves and constitutes a perpetual non-exclusive easement for the purpose of motor vehicle and pedestrian ingress and egress over, upon and across the Remnant for the construction, repair, replacement, maintenance and operation of a two-lane roadways for the use and benefit of the Airport parcel, Los Machos Three (3) parcel, the Hospital Parcel and

the Conservation Zones parcel, their owners, successors, assigns, tenants, subtenants, licensees, suppliers and customers which easement is described as follows:-----

---"Strip of land located in the wards of Chupacallos, Los Machos, Ensenada Honda, Guayacán and Quebrada Seca, Municipality of Ceiba and ward of Daguae, Municipality of Naguabo, with a total area of three hundred fifty-three thousand three hundred and sixty-four point six (353,364.6) square meters, equivalent to eighty-nine point nine hundred fifty-three (89.953) cuerdas, consisting of:-----

----- Segment One (1) II-----

---"Strip of land having an area of ten thousand one hundred ninety-eight point three (10,198.3) square meters, equivalent to two point five hundred ninety-five (2.595) cuerdas, with a length of six hundred seventy-eight point five (678.5) meters and a width of fifteen point zero (15.0) meters running from South to North."-----

----- Segment Six (6) -----

---"Strip of land having an area of nine thousand two hundred twenty-six point eight (9,226.8) square meters, equivalent to two point three hundred forty-eight (2.348) cuerdas, a length of five hundred twelve point zero (512.0) meters and a width of eighteen (18) meters running from Northwest to Southeast."-----

----- Segment Seven (7) -----

---"Strip of land having an area of fifty thousand eight hundred ninety point one (50,890.1) square meters, equivalent to twelve point nine hundred forty-eight (12.948) cuerdas, with a length of three thousand two hundred fifty point zero (3250.0) meters and with a variable width running from West to East."-----

----- Segment Ten (10)-----

---"Strip of land having an area of fourteen thousand six hundred seventy-eight point two (14,678.2) square meters, equivalent to three point seven hundred thirty-five (3.735) cuerdas, with a length of eight hundred twenty-six point zero (826.0) meters and a variable width running from Southwest to Northeast."-----

----- Segment Eleven (11) -----

---"Strip of land having an area of eighty thousand five hundred seventy-two point nine (80,572.9) square meters, equivalent to twenty point five hundred forty-six (20.546) cuerdas, with a length of three thousand four hundred

seventeen point zero (3417.0) meters and a variable width running from North to South thence from Southwest to Northeast."-----

----- Segment Twelve (12) -----

---"Strip of land having an area of five thousand one hundred eighty three point eight (5,183.8) square meters, equivalent to one point three hundred nineteen (1.319) cuerdas, with a length of three hundred forty-six point zero (346.0) meters with a width of fifteen (15) meters running from East to West."-----

----- Segment Thirteen (13) -----

---"Strip of land having an area of thirty-six thousand six hundred ninety-three point nine (36,693.9) square meters, equivalent to nine point three hundred thirty-six (9.336) cuerdas, with a length of two thousand two hundred eighty-seven point zero (2287.0) meters and a variable width running from Northwest to Southeast."-----

----- Segment Fifteen (15) I-----

---"Strip of land having an area of seventeen thousand eight hundred two point five (17,802.5) square meters, equivalent to four point five hundred twenty-nine (4.529) cuerdas, with a length of one thousand twenty-four point zero (1,024.0) meters and a variable width running from Southeast to Northwest."-----

----- Segment Fifteen (15) II-----

---"Strip of land having an area of six thousand two hundred and eighty point seven (6,280.7) square meters, equivalent to one point five hundred ninety-eight (1.598) cuerdas, with a length of three hundred and forty-nine point zero (349.0) meters and a variable width running from Northwest to Southeast."-----

----- Segment Sixteen (16)-----

---"Strip of land having an area of thirty-three thousand two hundred thirty-three point four (33,233.4) square meters, equivalent to eight point four hundred fifty-five (8.455) cuerdas, with a length of two thousand two hundred fifteen point zero (2,215.0) meters and a width of fifteen (15) meters running from Northwest to Southeast."-----

----- Segment Seventeen (17)-----

---"Strip of land having an area of five thousand seventy-nine point two (5,079.2) square meters, equivalent to one point two hundred ninety-two (1.292) cuerdas, with a length of three hundred forty point zero (340.0) meters and a variable width running from North to South."-----

----- Segment Nineteen (19) -----

---"Strip of land having an area of thirty-two thousand six hundred six point nine (32,606.9) square meters, equivalent to eight point two hundred ninety-six (8.296) cuerdas, with a length of one thousand eight hundred twenty-three point zero (1,823.0) meters and a variable width running from East to West thence South."-----

----- Segment Twenty-One (21) -----

---"Strip of land having an area of twenty thousand five hundred eighty-two point six (20,582.6) square meters, equivalent to five point two hundred thirty-seven (5.237) cuerdas, with a length of one thousand three hundred seventy point zero (1370.0) meters and a width of fifteen (15) meters running from North to South."-----

----- Segment Twenty-Three (23) -----

---"Strip of land having an area of five thousand thirty-seven point zero (5,037.0) square meters, equivalent to one point two hundred eighty-two (1.282) cuerdas, with a length of three hundred thirty-six point zero (336.0) meters and a width of fifteen (15) meters running from Southwest to Northeast."-----

----- Segment Twenty-Four (24) -----

---"Strip of land having an area of ten thousand four hundred thirty-seven point three (10,437.3) square meters, equivalent to two point six hundred fifty-six (2.656) cuerdas, with a length of six hundred ninety-seven point zero (697.0) meters and a width of fifteen (15) meters running from Northeast to Southwest."-----

----- Segment Twenty-Five (25) -----

---"Strip of land having an area of two thousand ninety-nine point three (2,099.3) square meters, equivalent to zero point five hundred thirty-four (0.534) cuerda, with a length of one hundred forty point zero (140.0) meters and a width of fifteen (15) meters running from East to West."-----

----- Segment Twenty-Six (26) -----

---"Strip of land having an area of two thousand four hundred fifty point two (2,450.2) square meters, equivalent to zero point six hundred twenty-three (0.623) cuerda, with a length of two hundred forty-one point zero (241.0) meters and a variable width running from South to North."-----

----- Segment Twenty-Seven (27) -----

---"Strip of land having an area of ten thousand three hundred eleven point five (10,311.5) square meters, equivalent to two point six hundred twenty-four (2.624) cuerdas, with a length of six

hundred eighty-seven point zero (687.0) meters and a width of fifteen (15) meters running from South to North."-----

---ELEVENTH: To be recorded at the Registry of the Property, the easement is valued at ONE THOUSAND DOLLARS (\$1,000.00).-----

---TWELFTH: The appearing party also hereby reserves and constitutes a perpetual non-exclusive easement for the purpose of communication utilities over, upon and across the Remnant for the construction, repair, replacement, maintenance and operation of communication utilities for the use and benefit of the Airport parcel, Los Machos Three (3) parcel, the Conservation Zones parcel, and the Hospital parcel, their owners, successors, assigns, tenants, subtenants, licensees, suppliers and customers which easement is described as follows.-----

----- Segment Twenty-Eight (28) -----

---"Strip of land having an area of twenty-four thousand nine hundred fifty-six point eight (24,956.8) square meters, equivalent to six point three hundred fifty (6.350) cuerdas, with a length of seven hundred seventy-seven point zero (777.0) meters and a variable width running from North to South."-----

---THIRTEENTH: To be recorded at the Registry of Property, the easement is valued at ONE THOUSAND DOLLARS (\$1,000.00).-----

---FOURTEENTH: The appearing party requests from the Registry of the Property to record all of the above easements in its books.-----

---FIFTEENTH: All easements constituted by this deed are graphically depicted IN Exhibit "A", attached and made part of this deed.-----

---SIXTEENTH: The geometric descriptions of all the easement segments constituted in this deed,

are included, attached and made part of this deed,
as Exhibit 'B'.....

----- ACCEPTANCE-----

---The appearing party in accordance with the
particulars of this Deed accepts the same, in all
its parts after, I, the Notary, gave him the
necessary legal admonitions and warnings pertinent
to this public instrument. Thus, the appearing
party states and executes this deed in my presence
after having read the same, and places his
initials on each and every page hereof and signs
his name on the last page of this deed, before, me
the Notary, that as to everything else
hereinbefore stated, I, the Notary, hereby

gcb

ATTEST.....



Gregory E. Preston

[Handwritten mark]



EXHIBIT B

LEGAL DESCRIPTION FOR EASEMENT 1 I

Beginning at a survey control point in the Ward of Machos, said point being a brass disk set in concrete. Said point also known as 'MOUND' and having a northing of 813308.1492 and an easting of 933097.0283 noted as the Point of Beginning on the plat labeled "UNITED STATES GOVERNMENT PROPERTY FORMER NAVAL STATION ROOSEVELT ROADS EASEMENT 1 I". Thence N71°50'03"W 1107.34' to an iron rod set, the True Point of Beginning, having a northing of 813653.3852 and an easting of 932044.8782:

Thence S73°51'24"W 49.23' to an iron rod set;

Thence following a curve to an iron rod set with a long chord of 345.49', chord bearing of N03°53'25"W

Radius=880.61'

Arc=347.75'

Thence N82°34'38"W 25.39' to an iron rod set;

Thence N07°25'22"E 219.33' to an iron rod set;

Thence N13°24'22"E 243.35' to an iron rod set;

Thence N07°25'22"E 659.31' to an iron rod set;

Thence S05°28'47"W 408.52' to point not set;

Thence S81°38'12"E 49.28' to a point not set;

Thence S05°28'47"W 406.87' to point not set;

Thence S07°25'22"W 660.14' to point not set;

Thence S82°34'38"E 25.39' to a point not set;

Thence S07°25'22"W 461.34' to a point not set;

Thence N82°34'38"W 25.39' to a point not set;

Thence following a curve to an iron rod set, the True Point of Beginning with a long chord of 325.39', chord bearing of S03°51'45"E

Radius=831.39'

Arc=327.50'

Said easement containing 112,218.3 square feet or 2.576 acres, which equates to 10,425.5 square meters or 2.653cuerdas.

LEGAL DESCRIPTION FOR EASEMENT 1 II

Beginning at a survey control point in the Ward of Machos, said point being a brass disk set in concrete. Said point also known as 'MOUND' and having a northing of 813308.1492 and an easting of 933097.0283 noted as the Point of Beginning on the plat labeled "UNITED STATES GOVERNMENT PROPERTY FORMER NAVAL STATION ROOSEVELT ROADS EASEMENT I II". Thence N22°09'05"W 2361.27' to an iron rod set, the True Point of Beginning, having a northing of 815495.1376 and an easting of 932206.6955;

Thence N81°38'12"W 49.28' to a point not set;

Thence N05°28'47"E 1994.60' to point not set;

Thence following a curve to a point not set with a long chord of 165.85', chord bearing of N03°53'22"W

Radius=509.39'

Arc=166.59'

Thence N05°39'24"E 117.42' to a point not set;

Thence following a curve to a point not set with a long chord of 291.12', chord bearing of S09°37'27"E

Radius=558.61'

Arc=294.51'

Thence S05°28'47"W 1997.07' to iron rod set, the True Point of Beginning.

Said easement containing 109,772.7 square feet or 2.520 acres, which equates to 10,198.3 square meters or 2.595cuerdas.

LEGAL DESCRIPTION FOR EASEMENT 2

Beginning at a survey control point in the Ward of Machos, said point being a brass disk set in concrete. Said point also known as 'MOUND' and having a northing of 813,308.1492 and an easting of 933,097.0283 noted as the Point of Beginning on the plat labeled "UNITED STATES GOVERNMENT PROPERTY FORMER NAVAL STATION ROOSEVELT ROADS EASEMENT 2 AND 4". Thence S50°05'29"W 669.86' to an iron rod set, the True Point of Beginning, having a northing of 812,878.3902 and an easting of 932,583.1982:

Thence S40°00'38"E 475.27' to an iron rod set;

Thence following a curve to an iron rod set with a long chord of 175.59', chord bearing of S33°21'21"E

Radius=757.61'

Arc=175.98'

Thence following a curve to a point not set with a long chord of 236.66', chord bearing of S17°42'56"E

Radius=757.61'

Arc=237.63'

Thence S08°43'48"E 1218.66' to a point not set;

Thence following a curve to a point not set with a long chord of 280.30', chord bearing of S10°31'28"E

Radius=4475.39'

Arc=280.33'

Thence following a curve to a point not set with a long chord of 397.21', chord bearing of S63°21'56"E

Radius=255.39'

Arc=455.07'

Thence N65°35'16"E 450.10' to a point not set;

Thence S32°17'53"E 49.69' to an iron rod set;

Thence S65°35'16"W 456.92' to a point not set;

Thence following a curve to a point not set with a long chord of 473.76', chord bearing of N63°21'56"W

Radius=304.61'

Arc=542.77'

Thence following a curve to a point not set with a long chord of 283.38', chord bearing of N10°31'28"W

Radius=4524.61'

Arc=283.41'

Thence N08°43'48"W 1218.66' to a point not set;

Thence following a curve to a point not set with a long chord of 381.96', chord bearing of N24°22'13"W

Radius=708.39'

Arc=386.74'

Thence N40°00'38"W 475.27' to a point not set;

Thence following a curve to a point not set with a long chord of 100.10', chord bearing of N39°32'42"W

Radius=6159.61'

Arc=100.13'

Thence N39°04'45"W 504.41' to a point not set;

Thence following a curve to a point not set with a long chord of 695.26', chord bearing of N15°49'42"W

Radius=880.61'

Arc=366.97'

Thence N73°51'24"E 49.23' to an iron rod set;

Thence following a curve to an iron rod set with a long chord of 344.74', chord bearing of S27°06'48"E

Radius=831.39'

Arc=347.26'

Thence S39°04'45"E 504.41' to an iron rod set;

Thence following a curve to an iron rod set, the True Point of Beginning with a long chord of

99.30', chord bearing of S39°32'42"E

Radius=6110.39'

Arc=99.33'

Said parcel containing 211,137.3 square feet or 4.847 acres, which equates to 19,615.4 square meters or 4.991 cuerdas.

LEGAL DESCRIPTION FOR EASEMENT 3

Beginning at a survey control point in the Ward of Guayacan, said point being a brass disk set in concrete. Said point also known as 'DOG' and having a northing of 805443.8964 and an easting of 933110.4735 noted as the Point of Beginning on the plat labeled "UNITED STATES GOVERNMENT PROPERTY FORMER NAVAL STATION ROOSEVELT ROADS EASEMENT 3". Thence N38°43'22"W 2713.86' to an iron rod set, the True Point of Beginning, having a northing of 807561.2021 and an easting of 934808.1316:

Thence following a curve to an iron rod set with a long chord of 56.94', chord bearing of N32°31'39"E

Radius=690.39'

Arc=56.95'

Thence N30°09'51"E 2439.05' to an iron rod set;

Thence following a curve to an iron rod set with a long chord of 1728.76', chord bearing of N42°07'27"W

Radius=907.39'

Arc=2289.65'

Thence S65°35'16"W 900.31' to an iron rod set;

Thence N32°17'53"W 49.69' to a point not set;

Thence N65°35'16"E 907.13' to a point not set;

Thence following a curve to a point not set with a long chord of 1822.53', chord bearing of S42°07'27"E

Radius=956.61'

Arc=2413.85'

Thence S30°09'51"W 2439.05' to a point not set;

Thence following a curve to a point not set with a long chord of 139.87', chord bearing of S35°35'25"W

Radius=739.61'

Arc=140.08'

Thence N05°12'00"E 90.85' to an iron rod set, the True Point of Beginning

Said parcel containing 285,182.4 square feet or 6.547 acres, which equates to 26,494.4 square meters or 6.741 cuerdas.

LEGAL DESCRIPTION FOR EASEMENT 4

Beginning at a survey control point in the Ward of Guayacan, said point being a brass disk set in concrete. Said point also known as 'DOG' and having a northing of 805443.8964 and an easting of 933110.4735 noted as the Point of Beginning on the plat labeled "UNITED STATES GOVERNMENT PROPERTY FORMER NAVAL STATION ROOSEVELT ROADS EASEMENT 2 AND 4". Thence N62°37'08"E 1139.76' to a point not set, the True Point of Beginning, having a northing of 805,968.0807 and an easting of 934,122.5427:

Thence N00°54'31"E 804.84' to a point not set;

Thence following a curve to a point not set with a long chord of 352.02', chord bearing of N25°23'51"E

Radius=424.61'

Arc=362.97'

Thence N49°53'12"E 523.53' to a point not set;

Thence following a curve to an iron rod set with a long chord of 180.18', chord bearing of N42°23'19"E

Radius=690.39'

Arc=180.70'

Thence S05°12'00"W 90.85' to a point not set;

Thence following a curve to a point not set with a long chord of 114.39', chord bearing of S45°27'05"W

Radius=739.61'

Arc=114.51'

Thence S49°53'12"W 523.53' to a point not set;

Thence following a curve to a point not set with a long chord of 311.21', chord bearing of S25°23'51"W

Radius=375.39'

Arc=320.90'

Thence S00°54'31"W 804.84' to a point not set;

Thence following a curve to a point not set with a long chord of 228.76', chord bearing of S06°58'49"W

Radius=833.39'

Arc=229.49'

Thence S22°19'52"E 75.42' to a point not set;

Thence following a curve to a point not set with a long chord of 367.19', chord bearing of S50°02'12"E

Radius=1543.42'

Arc=368.06'

Thence following a curve to an iron rod set with a long chord of 122.25', chord bearing of N82°40'41"W

Radius=2024.61'

Arc=122.25'

Thence N84°24'28"W 234.63' to a point not set;

Thence following a curve to a point not set with a long chord of 108.82', chord bearing of N20°10'41"E

Radius=107.10'

Arc=114.15'

Thence N14°52'08"W 157.68' to a point not set;

Thence following a curve to a point not set, the True Point of Beginning with a long chord of 242.28', chord bearing of N06°58'49"W

Radius=882.61'

Arc=243.04'

Said parcel containing 139,723.1 square feet or 3.208 acres, which equates to 12,980.8 square meters or 3.303 cuerdas.

LEGAL DESCRIPTION FOR EASEMENT 5

Beginning at a survey control point in the Ward of Guayanai, said point being a brass disk set in concrete. Said point known as "DOG" and having a northing of 805443.8964 and an easting of 933110.4735 noted as the Point of Beginning on the plat labeled "UNITED STATES GOVERNMENT PROPERTY FORMER NAVAL STATION ROOSEVELT ROADS EASEMENT 5". Thence S63°03'51"E 937.62' to an iron rod set, the True Point of Beginning, having a northing of 805019.1597 and an easting of 933946.3774;

Thence N63°28'17"E 59.67' to a point not set;

Thence S18°11'14"E 118.94' to a point not set;

Thence following a curve to a point not set with a long chord of 966.77', chord bearing of S36°32'12"E

Radius=1535.48'

Arc=983.50'

Thence S54°53'10"E 1634.30' to an iron rod set;

Thence S35°06'50"W 59.04' to an iron rod set;

Thence S86°03'23"W 149.04' to an iron rod;

Thence S73°15'38"W 1435.54' to an iron rod set;

Thence N01°00'48"W 51.13' to a point not set;

Thence N73°15'38"E 1421.68' to a point not set;

Thence N35°06'50"E 63.51' to a point not set;

Thence N54°53'10"W 1479.86' to a point not set;

Thence following a curve to a point not set, with a long chord of 1003.94', chord bearing of N36°32'12"W

Radius=1594.52'

Arc=1021.31'

Thence N18°11'14"W 110.29' to a point not set, True Point of Beginning.

Said parcel containing 214,234.4 square feet or 5.538 acres, which equates to 22,411.5 square meters or 5.702 cuerdas.

LEGAL DESCRIPTION FOR EASEMENT 6

Beginning at a survey control point in the Ward of Guayacon, said point being a brass disk set in concrete. Said point known as "DOG" and having a northing of 805443.8964 and an easting of 933110.4735 noted as the Point of Beginning on the plat labeled "UNITED STATES GOVERNMENT PROPERTY FORMER NAVAL STATION ROOSEVELT ROADS EASEMENT 6". Thence S51°52'31"E 3608.69' to an iron rod set, the True Point of Beginning, having a northing of 803215.9800 and an easting of 935949.3161;

Thence S54°53'10"E 1682.19' to an iron rod set;

Thence S35°06'50"W 59.04' to a point not set;

Thence N54°53'10"W 1682.19' to an iron rod set;

Thence N35°06'50"E 59.04' to an iron rod set, True Point of Beginning.

Said parcel containing 99,316.4 square feet or 2.280 acres, which equates to 9,226.8 square meters or 2,348 cuerdas.

LEGAL DESCRIPTION FOR EASEMENT 7

Beginning at a survey control point in the Ward of Guayacan, said point being a brass disk set in concrete. Said point also known as 'DOG' and having a northing of 805443.8964 and an easting of 933110.4735 noted as the Point of Beginning on the plat labeled "UNITED STATES GOVERNMENT PROPERTY FORMER NAVAL STATION ROOSEVELT ROADS EASEMENT 7". Thence N84°48'49"E 678.98' to a iron rod set, the True Point of Beginning, having a northing of 805505.2720 and an easting of 933786.6709:

Thence following a curve to an iron rod set with a long chord of 233.97', chord bearing of S85°20'41"E

Radius=7154.61'

Arc=234.00'

Thence S84°24'28"E 370.31' to an iron rod set;

Thence following a curve to a point not set with a long chord of 406.50', chord bearing of S78°38'46"E

Radius=2024.61'

Arc=407.19'

Thence S72°53'04"E 1013.37' to a point not set;

Thence following a curve to a point not set with a long chord of 370.17', chord bearing of S72°16'21"E

Radius=17324.61'

Arc=370.15'

Thence S71°39'37"E 1034.77' to a point not set;

Thence following a curve to a point not set with a long chord of 179.23', chord bearing of S82°31'33"E

Radius=475.39'

Arc=108.30'

Thence N86°36'32"E 255.03' to a point not set;

Thence following a curve to a point not set with a long chord of 1380.42', chord bearing of S69°39'13"E

Radius=1714.61'

Arc=1420.72'

Thence S45°54'58"E 670.96' to a point not set;

Thence following a curve to a point not set with a long chord of 341.13', chord bearing of S51°10'05"E

Radius=1863.39'

Arc=341.62'

Thence following a curve to a point not set with a long chord of 365.16', chord bearing of S46°46'26"E

Radius=1089.61'

Arc=366.90'

Thence S37°07'39"E 155.80' to a point not set;

Thence following a curve to a point not set with a long chord of 644.81', chord bearing of S16°29'13"E

Radius=914.61'

Arc=658.97'

Thence S04°09'13"W 115.96' to a point not set;

Thence following a curve to a point not set with a long chord of 380.82', chord bearing of S39°35'22"E

Radius=275.39'

Arc=420.50'

Thence following a curve to a point not set with a long chord of 96.52', chord bearing of S89°50'47"E

Radius=425.39'

Arc=96.72'
 Thence N83°38'23"E 113.50' to a point not set;
 Thence following a curve to a point not set with a long chord of 325.11', chord bearing of
 N81°34'11"E
 Radius=4500.39'
 Arc=325.18'
 Thence following a curve to a point not set with a long chord of 327.37', chord bearing of
 S81°57'14"E
 Radius=514.61'
 Arc=333.15'
 Thence following a curve to a point not set with a long chord of 437.63', chord bearing of
 S50°05'07"E
 Radius=949.61'
 Arc=441.60'
 Thence S36°45'47"E 111.79' to a point not set;
 Thence S63°24'52"E 381.66' to a point not set;
 Thence following a curve to a point not set with a long chord of 230.00', chord bearing of
 S81°15'13"E
 Radius=375.39'
 Arc=233.76'
 Thence N80°54'26"E 167.83' to an iron rod set;
 Thence S09°05'34"E 49.22' to an iron rod set;
 Thence S80°54'26"W 167.83' to a point not set;
 Thence following a curve to a point not set with a long chord of 260.16, chord bearing of
 N81°15'13"W
 Radius=424.61'
 Arc=264.41'
 Thence N63°24'52"W 234.68' to a point not set;
 Thence S53°14'13"W 71.16' to an iron rod set;
 Thence N36°45'47"W 265.23' to an iron rod set;
 Thence following a curve to an iron rod set with a long chord of 414.93, chord bearing of
 N50°05'07"W
 Radius=900.39'
 Arc=418.71'
 Thence following a curve to an iron rod set with a long chord of 296.05, chord bearing of
 N81°57'14"W
 Radius=465.39'
 Arc=301.29'
 Thence following a curve to an iron rod set with a long chord of 328.67, chord bearing of
 S81°34'11"W
 Radius=4549.61'
 Arc=328.74'
 Thence S83°38'23"W 113.50' to a point not set;
 Thence following a curve to a point not set with a long chord of 258.88, chord bearing of
 N80°31'59"W
 Radius=474.61'
 Arc=262.21'
 Thence following a curve to a point not set with a long chord of 109.91, chord bearing of
 N72°07'44"W
 Radius=425.39'
 Arc=110.22'
 Thence N79°33'06"W 66.90' to a point not set;
 Thence N08°57'37"E 71.30' to a point not set;
 Thence following a curve to a point not set with a long chord of 173.64, chord bearing of
 N06°33'25"E
 Radius=2070.39'

Arc=173.69'
 Thence N04°09'13"E 130.84' to a point not set;
 Thence following a curve to a point not set with a long chord of 610.11, chord bearing of
 N16°29'13"W
 Radius=865.39'
 Arc=623.50'
 Thence N37°07'39"W 155.80' to a point not set;
 Thence following a curve to a point not set with a long chord of 348.67, chord bearing of
 N46°46'26"W
 Radius=1040.39'
 Arc=350.32'
 Thence following a curve to a point not set with a long chord of 350.15, chord bearing of
 N51°10'05"W
 Radius=1912.61'
 Arc=350.64'
 Thence N45°54'58"W 670.96' to a point not set;
 Thence following a curve to a point not set with a long chord of 1340.80, chord bearing of
 N69°39'13"W
 Radius=1665.39'
 Arc=1379.93'
 Thence S86°36'32"W 255.03' to a point not set;
 Thence following a curve to a point not set with a long chord of 197.78, chord bearing of
 N82°31'33"W
 Radius=524.61'
 Arc=198.97'
 Thence N71°39'37"W 1034.77' to a point not set;
 Thence following a curve to a point not set with a long chord of 369.10, chord bearing of
 N72°16'21"W
 Radius=17275.39'
 Arc=369.10'
 Thence N72°53'04"W 1013.37' to an iron rod set;
 Thence following a curve to a point not set with a long chord of 396.62, chord bearing of
 N78°38'46"W
 Radius=1975.39'
 Arc=397.29'
 Thence N84°24'28"W 370.31' to a point not set;
 Thence following a curve to a point not set with a long chord of 148.75, chord bearing of
 N85°00'27"W
 Radius=7105.39'
 Arc=148.75'
 Thence S18°11'14"E 425.70' to a point not set;
 Thence S63°28'17"W 59.67' to a point not set;
 Thence N18°11'14"W 511.68' to an iron rod set, the True Point of Beginning.

Said parcel containing 547774.2 square feet or 12.575 acres, which equates to 50890.1 square
 meters or 12.948 cuerdsn.

LEGAL DESCRIPTION FOR EASEMENT 8

Beginning at a survey control point in the Ward of Guaynacan, said point being a brass disk set in concrete. Said point also known as 'CAMP' and having a northing of 800851.3059 and an easting of 941574.6311 noted as the Point of Beginning on the plat labeled "UNITED STATES GOVERNMENT PROPERTY FORMER NAVAL STATION ROOSEVELT ROADS, EASEMENT 8". Thence N48°18'42"E 1016.77' to an iron rod set, the True Point of Beginning, having a northing of 801527.5403 and an easting of 942333.9276:

Thence N80°54'26"E 434.18' to a point not set;

Thence following a curve to a point not set with a long chord of 463.10', chord bearing of N88°02'26"E

Radius=1864.61'

Arc=464.29'

Thence following a curve to a point not set with a long chord of 362.68', chord bearing of S73°28'41"E

Radius=921.61'

Arc=365.07'

Thence S62°07'48"E 205.39' to a point not set;

Thence following a curve to a point not set with a long chord of 267.28', chord bearing of S59°53'37"E

Radius=3424.61'

Arc=267.34'

Thence S57°39'26"E 142.96' to a point not set;

Thence following a curve to a point not set with a long chord of 168.92', chord bearing of N72°25'43"E

Radius=110.39'

Arc=192.34'

Thence N22°30'51"E 341.86' to a point not set;

Thence following a curve to a point not set with a long chord of 140.48', chord bearing of N27°43'01"E

Radius=774.61'

Arc=140.67'

Thence N32°55'10"E 115.54' to a point not set;

Thence following a curve to a point not set with a long chord of 88.65', chord bearing of N19°14'16"E

Radius=187.39'

Arc=89.49'

Thence N05°33'22"E 84.71' to a point not set;

Thence following a curve to a point not set with a long chord of 213.72', chord bearing of N43°17'24"E

Radius=174.61'

Arc=229.99'

Thence N81°01'25"E 75.96' to a point not set;

Thence following a curve to a point not set with a long chord of 389.23', chord bearing of S83°49'31"E

Radius=744.61'

Arc=393.81'

Thence S68°40'26"E 72.89' to a point not set;

Thence following a curve to an iron rod set with a long chord of 117.78', chord bearing of S48°57'51"E

Radius=174.61'

Arc=120.13'

Thence S60°44'45"W 49.22' to an iron rod set;

Thence following a curve to a point not set with a long chord of 84.58', chord bearing of N48°57'51"W

Radius=125.39'

Arc=86.27'

Thence N68°40'26"W 72.89' to a point not set;

Thence following a curve to a point not set with a long chord of 363.50', chord bearing of N83°49'31"W

Radius=695.39'

Arc=367.78'

Thence S81°01'25"W 75.96' to a point not set;

Thence following a curve to a point not set with a long chord of 153.48, chord bearing of S43°17'24"W

Radius=125.39'

Arc=165.16'

Thence S05°33'22"W 84.71' to a point not set;

Thence following a curve to a point not set with a long chord of 111.93, chord bearing of S19°14'16"W

Radius=236.61'

Arc=113.00'

Thence S32°55'10"W 115.54' to a point not set;

Thence following a curve to a point not set with a long chord of 131.55, chord bearing of S27°43'01"W

Radius=725.39'

Arc=131.73'

Thence S22°30'51"W 341.86' to a point not set;

Thence following a curve to an iron rod set with a long chord of 244.23, chord bearing of S72°25'43"W

Radius=159.61'

Arc=278.09'

Thence N57°39'26"W 142.96' to an iron rod set;

Thence following a curve to an iron rod set with a long chord of 263.44, chord bearing of N59°53'37"W

Radius=3375.39'

Arc=263.50'

Thence N62°07'48"W 205.39' to an iron rod set;

Thence following a curve to an iron rod set with a long chord of 343.32, chord bearing of N73°28'41"W

Radius=872.39'

Arc=345.57'

Thence following a curve to an iron rod set with a long chord of 450.87, chord bearing of S88°02'26"W

Radius=1815.39'

Arc=452.04'

Thence S80°54'26"W 434.18' to an iron rod set;

Thence N09°05'34"W 49.22' to an iron rod set, the True Point of Beginning,

Said parcel containing 182,440.5 square feet or 4.188 acres, which equates to 16,949.3 square meters or 4.312 cuerdas.

LEGAL DESCRIPTION FOR EASEMENT 9

Beginning at a survey control point in the Ward of Machos, said point being a brass disk set in concrete. Said point also known as 'MEDIO' and having a northing of 811980.2405 and an easting of 943163.0741 noted as the Point of Beginning on the plat labeled "UNITED STATES GOVERNMENT PROPERTY FORMER NAVAL STATION ROOSEVELT ROADS EASEMENT 9". Thence S42°23'29"W 2323.47' to an iron rod set, the True Point of Beginning, having a northing of 810264.2284 and an easting of 941596.6070:

Thence S32°59'45"W 82.86' to a point not set;
Thence following a curve to a point not set with a long chord of 134.73', chord bearing of S07°18'20"W

Radius=155.39'

Arc=139.35'

Thence S18°23'05"E 614.93' to a point not set;
Thence following a curve to a point not set with a long chord of 519.04', chord bearing of S07°11'21"E

Radius=1336.61'

Arc=522.35'

Thence following a curve to a point not set with a long chord of 409.95', chord bearing of S20°10'31"E

Radius=500.39'

Arc=422.38'

Thence S44°21'26"E 316.11' to a point not set;
Thence following a curve to a point not set with a long chord of 279.89', chord bearing of S48°38'12"E

Radius=1875.39'

Arc=280.15'

Thence S52°54'58"E 262.43' to a point not set;
Thence following a curve to a point not set with a long chord of 327.97', chord bearing of S44°00'48"E

Radius=1059.61'

Arc=329.29'

Thence S35°06'38"E 708.86' to a point not set;
Thence following a curve to a point not set with a long chord of 373.98', chord bearing of S29°35'03"E

Radius=1941.61'

Arc=374.56'

Thence S24°03'27"E 204.94' to a point not set;
Thence following a curve to a point not set with a long chord of 176.57', chord bearing of S22°00'17"E

Radius=2464.61'

Arc=176.61'

Thence S19°57'06"E 375.36' to a point not set;
Thence following a curve to a point not set with a long chord of 163.91', chord bearing of S47°48'32"E

Radius=175.39'

Arc=170.55'

Thence following a curve to a point not set with a long chord of 222.47', chord bearing of S51°29'26"E

Radius=271.61'

Arc=229.21'

Thence S27°18'54"E 248.18' to a point not set;
Thence following a curve to a point not set with a long chord of 418.53', chord bearing of S01°54'00"E

Radius=487.61'
 Arc=432.58'
 Thence following a curve to a point not set with a long chord of 722.70', chord bearing of
 S06°02'21"E
 Radius=732.60'
 Arc=755.77'
 Thence S35°35'35"E 38.54' to a point not set;
 Thence following a curve to a point not set with a long chord of 161.65', chord bearing of
 S40°29'50"E
 Radius=945.39'
 Arc=161.85'
 Thence following a curve to a point not set with a long chord of 194.35', chord bearing of
 S23°14'25"E
 Radius=257.61'
 Arc=199.28'
 Thence S01°04'45"E 554.93' to a point not set;
 Thence following a curve to a point not set with a long chord of 199.53', chord bearing of
 S20°08'47"E
 Radius=305.39'
 Arc=203.26'
 Thence S39°12'50"E 315.83' to a point not set;
 Thence following a curve to a point not set with a long chord of 200.61', chord bearing of
 S02°53'13"W
 Radius=149.61'
 Arc=219.87'
 Thence S44°59'16"W 27.23' to a point not set;
 Thence following a curve to a point not set with a long chord of 343.49', chord bearing of
 S65°05'37"W
 Radius=499.61'
 Arc=350.64'
 Thence S85°11'57"W 104.52' to a point not set;
 Thence following a curve to a point not set with a long chord of 229.39', chord bearing of
 S44°21'35"W
 Radius=175.39'
 Arc=250.03'
 Thence S03°31'12"W 236.43' to a point not set;
 Thence following a curve to a point not set with a long chord of 170.76', chord bearing of
 S14°08'35"E
 Radius=281.39'
 Arc=173.49'
 Thence S31°48'22"E 236.41' to a point not set;
 Thence following a curve to a point not set with a long chord of 114.50', chord bearing of
 S34°40'16"E
 Radius=1145.39'
 Arc=114.55'
 Thence S37°32'10"E 355.00' to a point not set;
 Thence S32°55'10"W 35.18' to a point not set;
 Thence following a curve to a point not set with a long chord of 55.09', chord bearing of
 S30°52'53"W
 Radius=774.61'
 Arc=55.10'
 Thence N08°32'02"W 72.51' to a point not set;
 Thence N37°32'10"W 323.62' to a point not set;
 Thence following a curve to a point not set with a long chord of 119.42', chord bearing of
 N34°40'16"W
 Radius=1194.61'

Arc=119.47
 Thence N31°48'22"W 236.41' to a point not set;
 Thence following a curve to a point not set with a long chord of 200.63', chord bearing of
 N14°08'35"W
 Radius=330.61'
 Arc=203.84
 Thence N03°31'12"E 236.43' to a point not set;
 Thence following a curve to a point not set with a long chord of 293.76', chord bearing of
 N44°21'35"E
 Radius=224.61'
 Arc=320.20
 Thence N85°11'57"E 104.52' to a point not set;
 Thence following a curve to a point not set with a long chord of 309.65', chord bearing of
 N65°05'37"E
 Radius=450.39'
 Arc=316.09
 Thence N44°59'16"E 27.23' to a point not set;
 Thence following a curve to a point not set with a long chord of 134.61', chord bearing of
 N02°53'13"E
 Radius=100.39'
 Arc=147.53
 Thence N39°12'50"W 315.83' to a point not set;
 Thence following a curve to a point not set with a long chord of 231.69', chord bearing of
 N20°08'47"W
 Radius=354.61'
 Arc=236.02
 Thence N10°04'45"W 554.93' to a point not set;
 Thence following a curve to a point not set with a long chord of 157.22', chord bearing of
 N23°14'25"W
 Radius=208.39'
 Arc=161.21
 Thence following a curve to a point not set with a long chord of 170.06', chord bearing of
 N40°29'50"W
 Radius=994.61'
 Arc=170.27
 Thence N35°35'35"W 38.54' to a point not set;
 Thence following a curve to a point not set with a long chord of 771.26', chord bearing of
 N06°02'21"W
 Radius=781.82'
 Arc=806.55
 Thence following a curve to a point not set with a long chord of 376.29', chord bearing of
 N01°54'00"W
 Radius=438.39'
 Arc=388.92
 Thence N27°18'54"W 248.18' to a point not set;
 Thence following a curve to a point not set with a long chord of 182.15', chord bearing of
 N51°29'26"W
 Radius=222.39'
 Arc=187.67
 Thence following a curve to a point not set with a long chord of 209.91', chord bearing of
 N47°48'32"W
 Radius=224.61'
 Arc=218.41
 Thence N19°57'06"W 375.36' to a point not set;
 Thence following a curve to a point not set with a long chord of 173.04', chord bearing of
 N22°00'17"W

Radius=2415.39'
Arc=173.08'
Thence N24°03'27"W 204.94' to a point not set;
Thence following a curve to a point not set with a long chord of 364.50', chord bearing of
N29°35'03"W
Radius=1892.39'
Arc=365.07'
Thence N35°06'38"W 708.86' to a point not set;
Thence following a curve to a point not set with a long chord of 312.73', chord bearing of
N44°00'48"W
Radius=1010.39'
Arc=314.00'
Thence N52°54'58"W 262.43' to a point not set;
Thence following a curve to a point not set with a long chord of 287.24', chord bearing of
N48°38'12"W
Radius=1924.61'
Arc=287.51'
Thence N44°21'26"W 316.11' to a point not set;
Thence following a curve to a point not set with a long chord of 450.28', chord bearing of
N20°10'31"W
Radius=549.61'
Arc=463.93'
Thence following a curve to a point not set with a long chord of 499.92', chord bearing of
N07°11'21"W
Radius=1287.39'
Arc=503.12'
Thence N18°23'05"W 614.93' to a point not set;
Thence following a curve to a point not set with a long chord of 177.40', chord bearing of
N07°18'20"E
Radius=204.61'
Arc=183.49'
Thence N32°59'45"E 74.06' to a point not set;
Thence S67°08'10"E 50.00' to a point not set, the True Point of Beginning.

Said parcel containing 504,031.5 square feet or 11.571 acres, which equates to 46,826.2 square meters or 11.914 cuerdas.

LEGAL DESCRIPTION
EASEMENT 10

Beginning at a survey control point in the Ward of Guayacan, said point being a brass disk set in concrete. Said point also known as 'DOCK' and having a northing of 801006.9442 and an easting of 938162.6251 noted as the Point of Beginning on the plat labeled "UNITED STATES GOVERNMENT PROPERTY FORMER NAVAL STATION ROOSEVELT ROADS EASEMENT 10". Thence N82°18'33"W 6368.65' to an iron rod set, the True Point of Beginning, having a northing of 801859.2585 and an easting of 931851.2678:

Thence N21°17'11"W 70.94' to a point not set;
Thence following a curve to a point not set with a long chord of 544.78', chord bearing of N62°20'51"E

Radius = 1438.79'

Arc = 548.09'

Thence N73°15'38"E 791.28' to a point not set;
Thence S16°44'22"E 9.18' to a point not set;
Thence N73°15'38"E 1381.12' to a point not set;
Thence S01°00'48"E 51.13' to an iron rod set;
Thence S73°15'38"W 1367.26' to an iron rod set;
Thence S16°44'22"E 9.18' to an iron rod set;
Thence S73°15'38"W 791.28' to an iron rod set;
Thence following a curve to an iron rod set, the True Point of Beginning with a long chord of 539.87', chord bearing of S61°54'26"W

Radius = 1371.21'

Arc = 543.42'

Said parcel containing 157,993.8 square feet or 3.627 acres, which equates to 14,678.2 square meters or 3.735 cuerdas.

LEGAL DESCRIPTION EASEMENT 11

Beginning at a survey control point in the Ward of Quayacan, said point being a brass disk set in concrete. Said point also known as 'DELICIAS' and having a northing of 799143.8537 and an easting of 927504.4901 noted as the Point of Beginning on the plat labeled "UNITED STATES GOVERNMENT PROPERTY FORMER NAVAL STATION ROOSEVELT ROADS EASEMENT 11". Thence S83°29'58"W 1270.45' to an iron rod set, the True Point of Beginning, having a northing of 799000.0249 and an easting of 926242.2090:

Thence following a curve to a point not set with a long chord of 206.40', chord bearing of S44°37'24"E

Radius=799.52'

Arc=206.98'

Thence S37°12'25"E 184.72' to a point not set;

Thence following a curve to a point not set with a long chord of 310.18', chord bearing of S16°02'25"E

Radius=429.52'

Arc=317.35'

Thence S05°07'35"W 113.24' to a point not set;

Thence following a curve to a point not set with a long chord of 295.16', chord bearing of S13°33'58"E

Radius=460.48'

Arc=300.46'

Thence S32°15'31"E 300.98' to a point not set;

Thence following a curve to a point not set with a long chord of 368.15', chord bearing of S16°53'22"E

Radius=694.52'

Arc=372.60'

Thence S01°31'13"E 874.38' to a point not set;

Thence following a curve to a point not set with a long chord of 478.71', chord bearing of S11°36'57"E

Radius=1365.48'

Arc=481.20'

Thence following a curve to a point not set with a long chord of 450.35', chord bearing of S85°44'10"E

Radius=250.48'

Arc=559.79'

Thence N30°14'21"E 582.72' to a point not set;

Thence N59°45'39"W 19.69' to a point not set;

Thence N30°14'21"E 467.43' to a point not set;

Thence following a curve to a point not set with a long chord of 1610.03', chord bearing of N32°20'28"E

Radius=21949.21'

Arc=1610.45'

Thence N34°26'35"E 721.41' to a point not set;

Thence following a curve to a point not set with a long chord of 1138.26', chord bearing of N39°17'54"E

Radius=6724.21'

Arc=1139.63'

Thence following a curve to a point not set with a long chord of 684.73', chord bearing of N54°49'22"E

Radius=1849.21'

Arc=688.70'

Thence N65°29'32"E 226.98' to a point not set;

Thence S24°30'28"E 15.42' to a point not set;

Thence following a curve to a point not set with a long chord of 577.17', chord bearing of
N42°44'26"E
Radius=746.21'
Arc=592.63'

Thence N19°59'21"E 655.01' to a point not set;
Thence following a curve to a point not set with a long chord of 779.77', chord bearing of
N35°42'42"E
Radius=1438.79'
Arc=789.65'

Thence S21°17'11"E 70.94' to an iron rod set;
Thence following a curve to a point not set with a long chord of 722.84', chord bearing of
S35°16'17"W
Radius=1371.21'
Arc=731.48'

Thence S19°59'21"W 651.23' to a point not set;
Thence following a curve to a point not set with a long chord of 629.45', chord bearing of
S42°44'26"W
Radius=813.79'
Arc=646.30'

Thence S24°30'28"E 15.42' to a point not set;
Thence S65°29'32"W 226.98' to a point not set;
Thence following a curve to a point not set with a long chord of 648.29', chord bearing of
S54°49'22"W
Radius=1750.79'
Arc=652.05'

Thence following a curve to a point not set with a long chord of 1121.60', chord bearing of
S39°17'54"W
Radius=6625.79'
Arc=1122.95'

Thence S34°26'35"W 721.41' to a point not set;
Thence following a curve to a point not set with a long chord of 1602.81', chord bearing of
S32°20'28"W
Radius=21850.79'
Arc=1603.23'

Thence S30°14'21"W 467.43' to a point not set;
Thence N59°45'39"W 19.69' to a point not set;
Thence S30°14'21"W 582.72' to a point not set;
Thence following a curve to an iron rod set with a long chord of 556.51', chord bearing of
N85°44'10"W
Radius=309.52'
Arc=691.74'

Thence following a curve to an iron rod set with a long chord of 499.41', chord bearing of
N11°36'57"W
Radius=1424.52'
Arc=502.01'

Thence N01°31'13"W 874.38' to an iron rod set;
Thence following a curve to an iron rod set with a long chord of 336.85', chord bearing of
N16°53'22"W
Radius=635.48'
Arc=340.93'

Thence N32°15'31"W 300.98' to an iron rod set;
Thence following a curve to an iron rod set with a long chord of 333.00', chord bearing of
N13°33'58"W
Radius=519.52'
Arc=338.98'

Thence N05°07'35"E 113.24' to an iron rod set;

Thence following a curve to an iron rod set with a long chord of 267.55', chord bearing of N16°02'25"W

Radius=370.48'

Arc=273.73'

Thence N37°12'25"W 184.72' to an iron rod set;

Thence following a curve to an iron rod set with a long chord of 203.46', chord bearing of N45°06'13"W

Radius=740.48'

Arc=204.10'

Thence N49°48'48"E 60.44' to an iron rod set, the True Point of Beginning.

Said parcel containing 869,213.9 square feet or 19.954 acres, which equates to 80,572.9 square meters or 20.546 cuerdas.

LEGAL DESCRIPTION FOR EASEMENT 12

Beginning at a survey control point in the Ward of Guaynecan, said point being a brass disk set in concrete. Said point also known as 'DELICIAS' and having a northing of 799143.8537 and an easting of 927504.4901 noted as the Point of Beginning on the plat labeled "UNITED STATES GOVERNMENT PROPERTY FORMER NAVAL STATION ROOSEVELT ROADS EASEMENT 12". Thence N86°08'59"E 2916.67' to an iron rod set, the True Point of Beginning, having a northing of 799339.7094 and an easting of 930414.5800:

Thence following a curve to an iron rod set; with a long chord of 394.07', a chord bearing of S88°16'14"E,

Radius= 694.61'

Arc=399.55'

Thence S18°12'29"W 49.22' to a point not set;

Thence following a curve to a point not set; with a long chord of 366.14', a chord bearing of N88°16'14"W,

Radius= 645.39'

Arc=371.24'

Thence S75°15'02"W 302.30' to a point not set;

Thence following a curve to a point not set; with a long chord of 433.01', a chord bearing of N79°52'10"W,

Radius= 514.61'

Arc=446.92'

Thence N54°59'22"W 22.37' to a point not set;

Thence following a curve to a point not set; with a long chord of 49.37', a chord bearing of N39°39'44"E,

Radius= 6625.79'

Arc=49.37'

Thence S54°59'22"E 18.37' to a point not set;

Thence following a curve to a point not set; with a long chord of 391.60', a chord bearing of S79°52'10"E,

Radius= 465.39'

Arc=404.18'

Thence N75°15'02"E 302.30' to an iron rod set, the True Point of Beginning.

Said parcel containing 55,798.0 square feet or 1.281 acres, which equates to 5,183.8 square meters or 1.319 cuerdas.

LEGAL DESCRIPTION FOR EASEMENT 13

Beginning at a survey control point in the Ward of Guayacan, said point being a brass disk set in concrete. Said point also known as 'DELVIS' and having a northing of 796646.7678 and an easting of 927749.8902 noted as the Point of Beginning on the plat labeled "UNITED STATES GOVERNMENT PROPERTY FORMER NAVAL STATION ROOSEVELT ROADS EASEMENT 13". Thence S78°52'34"E 168.01' to an iron rod set, the True Point of Beginning, having a northing of 796614.3537 and an easting of 927914.7410:

Thence N30°14'21"E 51.03' to a point not set;

Thence S75°02'51"E 919.53' to a point not set;

Thence following a curve to a point not set; with a long chord of 462.99', a chord bearing of S29°33'20"E,

Radius= 324.61'

Arc=515.47'

Thence S15°56'11"W 360.72' to a point not set;

Thence following a curve to a point not set; with a long chord of 418.08', a chord bearing of S01°33'03"W,

Radius= 841.39'

Arc=422.51'

Thence S12°50'05"E 705.02' to a point not set;

Thence following a curve to a point not set; with a long chord of 237.97', a chord bearing of S10°24'27"E,

Radius= 2809.61'

Arc=238.04'

Thence S07°58'50"E 664.13' to a point not set;

Thence following a curve to a point not set; with a long chord of 161.35', a chord bearing of S12°03'18"E,

Radius= 1135.39'

Arc=161.48'

Thence S16°07'47"E 406.15' to a point not set;

Thence following a curve to a point not set; with a long chord of 121.76', a chord bearing of S21°04'50"E,

Radius= 705.39'

Arc=121.91'

Thence S26°01'54"E 754.37' to a point not set;

Thence N63°58'06"E 29.53' to a point not set;

Thence following a curve to an iron rod set; with a long chord of 243.72', a chord bearing of S17°46'50"E,

Radius= 849.14'

Arc=244.57'

Thence S09°31'46"E 282.37' to an iron rod set;

Thence following a curve to an iron rod set; with a long chord of 294.29', a chord bearing of S40°30'35"E,

Radius= 285.86'

Arc=309.13'

Thence S18°30'36"W 29.53' to a point not set;

Thence S71°29'24"E 79.41' to a point not set;

Thence following a curve to a point not set; with a long chord of 143.96', a chord bearing of S83°20'41"E,

Radius= 350.39'

Arc=144.99'

Thence N84°48'02"E 272.81' to an iron rod set;

Thence following a curve to an iron rod set; with a long chord of 241.06', a chord bearing of
 S70°36'19"E,
 Radius= 289.61'
 Arc=248.63'

Thence following a curve to an iron rod set; with a long chord of 530.38', a chord bearing of
 N84°01'47"E,
 Radius= 346.39'
 Arc=604.07'

Thence S55°55'45"E 49.22' to a iron rod set;
 Thence following a curve to a point not set; with a long chord of 605.74', a chord bearing of
 S84°01'47"W,
 Radius= 395.61'
 Arc=689.90'

Thence following a curve to a point not set; with a long chord of 200.09', a chord bearing of
 N70°36'19"W,
 Radius= 240.39'
 Arc=206.37'

Thence S84°48'02"W 272.81' to a point not set;
 Thence following a curve to a point not set; with a long chord of 164.18', a chord bearing of
 N83°20'41"W,
 Radius= 399.61'
 Arc=165.36'

Thence N71°29'24"W 79.41' to a point not set;
 Thence following a curve to a point not set; with a long chord of 375.36', a chord bearing of
 N40°30'35"W,
 Radius= 364.61'
 Arc=394.30'

Thence N09°31'46"W 282.37' to a point not set;
 Thence following a curve to a point not set; with a long chord of 221.12', a chord bearing of
 N17°46'50"W,
 Radius= 770.39'
 Arc=221.88'

Thence N26°01'54"W 754.37' to a point not set;
 Thence following a curve to a point not set; with a long chord of 130.25', a chord bearing of
 N21°04'50"W,
 Radius= 754.61'
 Arc=130.41'

Thence N16°07'47"W 406.15' to a point not set;
 Thence following a curve to a point not set; with a long chord of 168.34', a chord bearing of
 N12°03'18"W,
 Radius= 1184.61'
 Arc=168.49'

Thence N07°58'50"W 664.13' to a point not set;
 Thence following a curve to a point not set; with a long chord of 233.80', a chord bearing of
 N10°24'27"W,
 Radius= 2760.39'
 Arc=233.87'

Thence N12°50'05"W 705.02' to a point not set;
 Thence following a curve to a point not set; with a long chord of 442.54', a chord bearing of
 N01°33'03"E,
 Radius= 890.61'
 Arc=447.22'

Thence N15°56'11"E 360.72' to a point not set;

Thence following a curve to a point not set; with a long chord of 392.79', a chord bearing of N29°33'20"W,

Radius= 275.39'

Arc=437.31'

Thence N75°02'51"W 932.99' to an iron rod set, the True Point of Beginning.

Said parcel containing 394,968.0 square feet or 9.067 acres, which equates to 36,693.9 square meters or 9.336 cuerdas.

LEGAL DESCRIPTION FOR EASEMENT 14

Beginning at a survey control point in the Ward of Guaynacan, said point being a brass disk set in concrete. Said point also known as 'DELVIS' and having a northing of 796646.7678 and an easting of 927749.8902 noted as the Point of Beginning on the plat labeled "UNITED STATES GOVERNMENT PROPERTY FORMER NAVAL STATION ROOSEVELT ROADS EASEMENT 14". Thence S47°16'47"E 6610.93' to an iron rod set, the True Point of Beginning, having a northing of 792161.7895 and an easting of 932606.7849:

Thence S48°34'14"W 49.22' to an iron rod set;
Thence following a curve to a point not set; with a long chord of 327.40', a chord bearing of N51°48'41"W,

Radius= 908.39'

Arc=329.19'

Thence N62°11'35"W 204.46' to a point not set;
Thence following a curve to a point not set; with a long chord of 285.17', a chord bearing of N87°30'50"W,

Radius= 333.39'

Arc=294.67'

Thence S67°09'55"W 249.07' to a point not set;
Thence following a curve to a point not set; with a long chord of 273.38', a chord bearing of S50°35'54"W,

Radius= 479.39'

Arc=277.23'

Thence S34°01'53"W 112.96' to a point not set;
Thence following a curve to a point not set; with a long chord of 157.69', a chord bearing of S03°58'06"W,

Radius= 157.39'

Arc=165.17'

Thence S26°05'42"E 141.99' to a point not set;
Thence following a curve to an iron rod set; with a long chord of 275.30', a chord bearing of S03°59'17"W,

Radius= 274.61'

Arc=288.37'

Thence N55°55'45"W 49.22' to an iron rod set;
Thence following a curve to a point not set; with a long chord of 225.95', a chord bearing of N03°59'17"E,

Radius= 225.39'

Arc=236.68'

Thence N26°05'42"W 141.99' to a point not set;
Thence following a curve to a point not set; with a long chord of 207.00', a chord bearing of N03°58'06"E,

Radius= 206.61'

Arc=216.82'

Thence N34°01'53"E 112.96' to a point not set;
Thence following a curve to a point not set; with a long chord of 301.45', a chord bearing of N50°35'54"E,

Radius= 528.61'

Arc=305.69'

Thence N67°09'55"E 249.07' to a point not set;
Thence following a curve to a point not set; with a long chord of 327.27', a chord bearing of S87°30'50"E,

Radius= 382.61'

Arc=338.17'

Thence S62°11'35"E 204.46' to a point not set;

Thence following a curve to an iron rod set; the True Point of Beginning with a long chord of
345.14', a chord bearing of S51°48'41"E,
Radius=957.61'
Arc=347.03'

Said parcel containing 103,755.2 square feet or 2.382 acres, which equates to 9,639.2 square
meters or 2.452 cuerds.

LEGAL DESCRIPTION FOR EASEMENT 15 I.

Beginning at a survey control point in the Ward of Machos, said point being a brass disk set in concrete. Said point also known as 'CAMP' and having a northing of 800851.3059 and an easting of 941574.6311 noted as the Point of Beginning on the plat labeled "EASEMENT 15 I". Thence S58°15'43"W 1415.33' to an iron rod set, the True Point of Beginning, having a northing of 800106.7923 and an easting of 940370.9503:

Thence S53°34'53"E 189.86' to an iron rod set;

Thence S50°43'25"E 313.99' to an iron rod set;

Thence following a curve to an iron rod set with a long chord of 278.22', chord bearing of S52°59'29"E

Radius=3515.39'

Arc=278.30'

Thence S34°44'26"W 49.22' to a point not set;

Thence following a curve to a point not set with a long chord of 282.12', chord bearing of N52°59'29"W

Radius=3564.61'

Arc=282.19'

Thence N50°43'25"W 313.99' to a point not set;

Thence N56°37'00"W 186.32' to a point not set;

Thence N54°53'10"W 2578.10' to an iron rod set;

Thence N35°07'20"E 59.04' to an iron rod set;

Thence S54°53'10"E 2578.09' to an iron rod set, the True Point of Beginning.

Said parcel containing 191,623.6 square feet or 4.399 acres, which equates to 17,802.5 square meters or 4.529 cuerdas.

LEGAL DESCRIPTION FOR EASEMENT 15 II

Beginning at a survey control point in the Ward of Machos, said point being a brass disk set in concrete. Said point also known as 'CAMP' and having a northing of 800851.3059 and an easting of 941574.6311 noted as the Point of Beginning on the plat labeled "UNITED STATES GOVERNMENT PROPERTY FORMER NAVAL STATION ROOSEVELT ROADS EASEMENT 15 II". Thence N71°48'01"W 4473.04' to an iron rod set, the True Point of Beginning, having a northing of 802248.3777 and an easting of 937325.3615:

Thence S54°53'10"E 1145.08' to an iron rod set;
Thence S35°07'20"W 59.04' to an iron rod set;
Thence N54°53'10"W 1145.07' to a point not set;
Thence N35°06'50"E 59.04' to an iron rod set, True Point of Beginning

Said parcel containing 67,605.1 square feet or 1.552 acres, which equates to 6,208.7 square meters or 1.598 cuerdas.

LEGAL DESCRIPTION FOR EASEMENT 16

Beginning at a survey control point in the Ward of Machos, said point being a brass disk set in concrete. Said point also known as 'CAMP' and having a northing of 800851.3059 and an easting of 941574.6311 noted as the Point of Beginning on the plat labeled "UNITED STATES GOVERNMENT PROPERTY FORMER NAVAL STATION ROOSEVELT ROADS EASEMENT 16". Thence S25°34'47"W 1356.43' to a PK nail set, the True Point of Beginning, having a northing of 799627.8270 and an easting of 940988.9671:

Thence S55°15'34"E 1622.79' to a point not set;

Thence following a curve to a point not set with a long chord of 317.94', chord bearing of S44°08'39"E

Radius=824.61'

Arc=319.94'

Thence following a curve to a point not set with a long chord of 471.02', chord bearing of S44°53'41"E

Radius=1145.39'

Arc=474.41'

Thence S56°45'37"E 453.21' to a point not set;

Thence following a curve to a point not set with a long chord of 885.86', chord bearing of S25°20'19"E

Radius=849.61'

Arc=931.87'

Thence S06°04'59"W 307.16' to a point not set;

Thence following a curve to a point not set with a long chord of 263.68', chord bearing of S47°25'16"W

Radius=199.61'

Arc=288.03'

Thence S88°45'33"W 199.61' to a point not set;

Thence following a curve to a point not set with a long chord of 512.24', chord bearing of S54°06'07"W

Radius=450.39'

Arc=544.87'

Thence S19°26'41"W 326.67' to a point not set;

Thence following a curve to a point not set with a long chord of 80.15', chord bearing of S20°22'22"W

Radius=2474.61'

Arc=80.15'

Thence S21°18'03"W 174.42' to a point not set;

Thence following a curve to a point not set with a long chord of 181.43', chord bearing of N15°47'57"W

Radius=150.39'

Arc=194.76'

Thence S52°53'57"E 1350.91' to an iron rod set;

Thence S37°06'03"W 49.22' to an iron rod set;

Thence N52°53'57"W 1350.91' to a point not set;

Thence following a curve to a point not set with a long chord of 240.81', chord bearing of N15°47'57"W

Radius=199.61'

Arc=258.50'

Thence N21°18'03"E 174.42' to a point not set;

Thence following a curve to a point not set with a long chord of 78.56', chord bearing of N20°22'22"E

Radius=2425.39'

Arc=78.56'

Thence N19°26'41"E 326.67' to a point not set;
Thence following a curve to a point not set with a long chord of 568.22', chord bearing of
N54°06'07"E
Radius=499.61'
Arc=604.41'
Thence N88°45'33"E 199.61' to a point not set;
Thence following a curve to a point not set with a long chord of 198.67', chord bearing of
N47°25'16"E
Radius=150.39'
Arc=217.01'
Thence N06°04'59"E 307.16' to a point not set;
Thence following a curve to a point not set with a long chord of 834.54, chord bearing of
N25°20'19"W
Radius=800.39'
Arc=877.89'
Thence N56°45'37"W 453.21' to a point not set;
Thence following a curve to a point not set with a long chord of 491.26, chord bearing of
N44°53'41"W
Radius=1194.61'
Arc=494.79'
Thence following a curve to a point not set with a long chord of 298.96, chord bearing of
N44°08'39"W
Radius=775.39'
Arc=300.84'
Thence N55°15'34"W 1622.79' to a point not set;
Thence N34°44'26"E 49.22' to a PK nail set, True Point of Beginning.

Said parcel containing 357719.9 square feet or 8.212 acres, which equates to 33233.4 square meters or 8.455 cuerdas.

LEGAL DESCRIPTION EASEMENT 17

Beginning at a survey control point in the Ward of Guayacon, said point being a brass disk set in concrete. Said point also known as 'EMBEACH' and having a northing of 798535.1118 and an easting of 943260.8239 noted as the Point of Beginning on the plat labeled "UNITED STATES GOVERNMENT PROPERTY FORMER NAVAL STATION ROOSEVELT ROADS EASEMENT 17". Thence S70°34'51"W 1062.22' to an iron rod set, the True Point of Beginning, having a northing of 798181.9491 and an easting of 942259.0304:

Thence S20°24'39"W 163.17' to an iron rod set;

Thence S35°11'24"W 90.57' to an iron rod set;

Thence S44°07'15"W 227.64' to a point not set;

Thence N45°48'06"W 38.83' to a point not set;

Thence N44°11'54"E 120.58' to a point not set;

Thence following a curve to a point not set with a long chord of 1000.12', chord bearing of N05°31'50"E

Radius=655.39'

Arc=1137.67'

Thence S55°15'34"E 344.36' to a point not set;

Thence S34°44'26"W 40.66' to a point not set;

Thence following a curve to a point not set, the True Point of Beginning with a long chord of 491.31', chord bearing of S05°35'53"E

Radius=704.61'

Arc=501.85'

Said parcel containing 54,671.6 square feet or 1.255 acres, which equates to 5,079.2 square meters or 1.292 cuerdas.

LEGAL DESCRIPTION FOR EASEMENT 18

Beginning at a survey control point in the Ward of Guayacan, said point being a brass disk set in concrete. Said point also known as 'DELICIAS' and having a northing of 799143.8537 and an easting of 927504.4901 noted as the Point of Beginning on the plat labeled "UNITED STATES GOVERNMENT PROPERTY FORMER NAVAL STATION ROOSEVELT ROADS EASEMENT 18". Thence S82°02'45"W 1321.16' to an iron rod set, the True Point of Beginning, having a northing of 798961.0287 and an easting of 926196.0422;

Thence following a curve to a point not set with a long chord of 58.03', chord bearing of N55°14'45"W

Radius=740.48'

Arc=58.05°

Thence following a curve to a point not set with a long chord of 749.97', chord bearing of N68°57'48"W

Radius=1885.48'

Arc=755.01°

Thence N80°26'05"W 333.41' to a point not set;

Thence N02°53'40"E 59.44' to an iron rod set;

Thence S80°26'05"E 340.32' to a point not set;

Thence following a curve to a point not set with a long chord of 773.46', chord bearing of S68°57'48"E

Radius=1944.52'

Arc=778.65°

Thence following a curve to a point not set with a long chord of 76.05', chord bearing of S54°45'56"E

Radius=799.52'

Arc=76.08°

Thence S49°48'46"W 60.43' to an iron rod set, the True Point of Beginning.

Said parcel containing 69,121.9 square feet or 1.587 acres, which equates to 6,421.7 square meters or 1.634 cuerdas.

LEGAL DESCRIPTION FOR EASEMENT 19

Beginning at a survey control point in the Ward of Guayacan, said point being a brass disk set in concrete. Said point also known as 'DELICIAS' and having a northing of 799143.8537 and an easting of 927504.4901 noted as the Point of Beginning on the plat labeled "UNITED STATES GOVERNMENT PROPERTY FORMER NAVAL STATION ROOSEVELT ROADS EASEMENT 19". Thence N84°23'00"W 2393.39' to an iron rod set, the True Point of Beginning, having a northing of 799378.0976 and an easting of 925122.5952;

Thence S02°53'40"W 59.44' to a point not set;
Thence N80°26'05"W 1000.44' to a point not set;
Thence following a curve to a point not set with a long chord of 524.92', chord bearing of N86°52'24"W

Radius=2340.48'
Arc=526.02'

Thence S86°41'17"W 956.85' to a point not set;
Thence S03°18'43"E 19.69' to a point not set;
Thence following a curve to a point not set with a long chord of 328.45', chord bearing of S73°39'53"W

Radius=728.79'
Arc=331.29'

Thence N29°21'27"W 19.69' to a point not set;
Thence S60°38'33"W 1014.42' to a point not set;
Thence following a curve to a point not set with a long chord of 440.23', chord bearing of S77°37'38"W

Radius=753.52'
Arc=446.74'

Thence N85°23'18"W 105.09' to a point not set;
Thence S06°29'05"W 565.74' to a point not set;
Thence following a curve to a point not set with a long chord of 240.83', chord bearing of S12°29'15"E

Radius=370.39'
Arc=245.29'

Thence S31°27'34"E 205.67' to a point not set;
Thence following a curve to an iron rod set with a long chord of 512.82', chord bearing of S25°12'28"E

Radius=2354.61'
Arc=513.83'

Thence S71°02'38"W 49.22' to an iron rod set;
Thence following a curve to an iron rod set with a long chord of 502.10', chord bearing of N25°12'28"W

Radius=2305.39'
Arc=503.09'

Thence N31°27'34"W 205.67' to an iron rod set;
Thence following a curve to a point not set with a long chord of 272.84', chord bearing of N12°29'15"E

Radius=419.61'
Arc=277.89'

Thence N06°29'05"E 488.65' to a point not set;
Thence N11°14'04"E 135.38' to a point not set;
Thence S85°23'18"E 141.19' to a point not set;
Thence following a curve to a point not set with a long chord of 405.74', chord bearing of N77°37'38"E

Radius=694.48'
Arc=411.74'

Thence N60°38'33"E 1014.42' to a point not set;

Thence N29°21'27"W 19.69' to a point not set;
Thence following a curve to a point not set with a long chord of 372.80', chord bearing of
N73°39'55"E

Radius=827.21'

Arc=376.03'

Thence S03°18'43"E 19.69' to a point not set;

Thence N86°41'17"E 956.85' to an iron rod set;

Thence following a curve to an iron rod set with a long chord of 538.16', chord bearing of
S86°52'24"E

Radius=2399.52'

Arc=539.29'

Thence S80°26'05"E 993.54' to an iron rod set, the True Point of Beginning.

Said parcel containing 350,976.2 square feet or 8.057 acres, which equates to 32,606.9 square
meters or 8.296 cuerdas.

LEGAL DESCRIPTION FOR EASEMENT 20

Beginning at a survey control point in the Ward of Daguao, said point being a brass disk set in concrete. Said point also known as 'MANATI' and having a northing of 791059.1339 and an easting of 921490.5759 noted as the Point of Beginning on the plat labeled "UNITED STATES GOVERNMENT PROPERTY FORMER NAVAL STATION ROOSEVELT ROADS EASEMENT 20". Thence N12°12'56"W 5380.02' to an iron rod set, the True Point of Beginning, having a northing of 796317.3385 and an easting of 920352.2213;

Thence N07°23'37"W 50.22' to a point not set;

Thence following a curve to a point not set with a long chord of 262.52', chord bearing of N60°27'55"E

Radius=735.39'

Arc=263.93'

Thence N50°11'00"E 631.48' to a point not set;

Thence following a curve to an iron rod set with a long chord of 443.02', chord bearing of N15°36'49"E

Radius=390.39'

Arc=471.09'

Thence N71°02'38"E 49.22' to an iron rod set;

Thence following a curve to a point not set with a long chord of 498.88', chord bearing of S15°36'49"W

Radius=439.61'

Arc=530.48'

Thence S50°11'00"W 631.48' to an iron rod set;

Thence following a curve to an iron rod set, the True Point of Beginning, with a long chord of 290.24', chord bearing of S60°50'32"W

Radius=784.61'

Arc=291.92'

Said parcel containing 69,409.9 square feet or 1.593 acres, which equates to 6,448.4 square meters or 1.641 cuerdas.

LEGAL DESCRIPTION EASEMENT 21

Beginning at a survey control point in the Ward of Daguao, said point being a brass disk set in concrete. Said point also known as 'BAKER' and having a northing of 794549.6798 and an easting of 921077.9933 noted as the Point of Beginning on the plat labeled "UNITED STATES GOVERNMENT PROPERTY FORMER NAVAL STATION ROOSEVELT ROADS EASEMENT 21". Thence N13°53'46"W 1966.63' to an iron rod set, the True Point of Beginning, having a northing of 796458.7488 and an easting of 920605.6833;

Thence following a curve to a point not set with a long chord of 332.65', chord bearing of S21°45'22"W
Radius=349.39'
Arc=346.70'

Thence S06°40'17"E 707.30' to a point not set;

Thence following a curve to a point not set with a long chord of 228.51', chord bearing of S10°09'33"W
Radius=394.61'
Arc=231.83'

Thence S26°59'23"W 1182.66' to a point not set;

Thence following a curve to a point not set with a long chord of 62.33', chord bearing of S11°34'06"E
Radius=50.00'
Arc=67.30'

Thence following a curve to a point not set with a long chord of 239.96', chord bearing of S25°11'36"E
Radius=284.61'
Arc=247.71'

Thence S00°15'36"E 233.14' to a point not set;

Thence following a curve to a point not set with a long chord of 115.51', chord bearing of S27°41'13"E
Radius=125.39'
Arc=120.05'

Thence S55°06'51"E 162.71' to a point not set;

Thence following a curve to a point not set with a long chord of 156.28', chord bearing of S23°37'40"E
Radius=149.61'
Arc=164.43'

Thence S07°51'31"W 152.93' to a point not set;

Thence following a curve to a point not set with a long chord of 86.37', chord bearing of S27°05'18"E
Radius=75.39'
Arc=91.97'

Thence S62°02'07"E 305.68' to a point not set;

Thence following a curve to a point not set with a long chord of 349.05', chord bearing of S75°57'24"E
Radius=725.39'
Arc=352.51'

Thence S89°52'42"E 180.05' to a point not set;

Thence S01°18'44"E 49.24' to a point not set;

Thence N89°52'42"W 181.28' to a point not set;

Thence following a curve to a point not set with a long chord of 372.73', chord bearing of N75°57'24"W
Radius=774.61'
Arc=376.42'

Thence N62°02'07"W 305.68' to a point not set;

Thence following a curve to a point not set with a long chord of 142.76', chord bearing of N27°05'18"W
Radius=124.61'
Arc=152.01'

Thence N07°51'31"E 152.93' to a point not set;

Thence following a curve to a point not set with a long chord of 104.87', chord bearing of N23°37'40"W
Radius=110.39'
Arc=110.34'

Thence N55°06'51"W 162.71' to a point not set;
Thence following a curve to a point not set with a long chord of 160.86', chord bearing of N27°41'13"W
Radius=174.61'
Arc=167.17'

Thence N00°15'36"W 233.14' to a point not set;
Thence following a curve to a point not set with a long chord of 198.46', chord bearing of N25°11'36"W
Radius=235.39'
Arc=204.87'

Thence following a curve to a point not set with a long chord of 123.69', chord bearing of N11°34'06"W
Radius=99.22'
Arc=133.54'

Thence N26°39'23"E 1182.66' to a point not set;
Thence following a curve to a point not set with a long chord of 200.01', chord bearing of N10°09'33"E
Radius=345.39'
Arc=202.91'

Thence N06°40'17"W 707.30' to a point not set;
Thence following a curve to a point not set with a long chord of 228.97', chord bearing of N10°01'10"E
Radius=398.61'
Arc=232.24'

Thence following a curve to an iron rod set, the True Point of Beginning, with a long chord of 159.60',
chord bearing of N56°01'16"E
Radius=784.61'
Arc=159.88'

Said parcel containing 221,548.7 square feet or 5.086 acres, which equates to 20,582.6 square meters or 5.237 cuerdas.

LEGAL DESCRIPTION FOR EASEMENT 22

Beginning at a survey control point in the Ward of Guayaqan, said point being a brass disk set in concrete. Said point also known as 'DELVIS' and having a northing of 796646.7678 and an easting of 927749.8902 noted as the Point of Beginning on the plat labeled "UNITED STATES GOVERNMENT PROPERTY FORMER NAVAL STATION ROOSEVELT ROADS EASEMENT 22". Thence S10°14'36"E 5702.81' to an iron rod set, the True Point of Beginning, having a northing of 791034.8502 and an easting of 928764.0234:

Thence S37°21'10"E 56.21' to a point not set;

Thence following a curve to a point not set; with a long chord of 93.66', a chord bearing of S32°30' 14"W,

Radius= 399.61'

Arc=93.87'

Thence S39°14'01"W 203.42' to a point not set;

Thence S31°07'00"W 298.77' to a point not set;

Thence N82°23'22"W 53.67' to a point not set;

Thence N31°07'00"E 323.67' to a point not set;

Thence N39°14'01"E 206.91' to a point not set;

Thence following a curve to an iron rod set; the True Point of Beginning with a long chord of 107.32', a chord bearing of N30°25'29"E,

Radius= 350.39'

Arc=107.74'

Said parcel containing 30,374.0 square feet or 0.697 of an acre, which equates to 2,821.8 square meters or 0.718 of a cuerda.

LEGAL DESCRIPTION EASEMENT 23

Beginning at a survey control point in the Ward of Guayacan, said point being a brass disk set in concrete. Said point also known as 'DELVIS' and having a northing of 796646.7678 and an easting of 927749.8902 noted as the Point of Beginning on the plat labeled "UNITED STATES GOVERNMENT PROPERTY FORMER NAVAL STATION ROOSEVELT ROADS EASEMENT 23". Thence N50°37'43"E 1415.10' to an iron rod set, the True Point of Beginning, having a northing of 797544.4326 and an easting of 928843.8370:

Thence N55°35'04"W 49.22' to a point not set;

Thence N34°24'56"E 784.00' to a point not set;

Thence following a curve to an iron rod set with a long chord of 14.71', chord bearing of N10°38'54"W

Radius=10.39'

Arc=16.34°

Thence N55°42'43"W 262.55' to an iron rod set;

Thence N34°26'35"E 49.22' to a point not set;

Thence S55°42'43"E 262.42' to a point not set;

Thence following a curve to a point not set with a long chord of 84.40', chord bearing of S10°38'54"E

Radius=59.61'

Arc=93.77°

Thence S34°24'56"W 784.00' to an iron rod set, the True Point of Beginning.

Said parcel containing 54,217.7 square feet or 1.245 acres, which equates to 5,037.0 square meters or 1.282 cuerdas.

LEGAL DESCRIPTION FOR EASEMENT 24

Beginning at a survey control point in the Ward of Guayacán, said point being a brass disk set in concrete. Said point also known as 'DELVIS' and having a northing of 796646.7678 and an easting of 927749.8902 noted as the Point of Beginning on the plat labeled "UNITED STATES GOVERNMENT PROPERTY FORMER NAVAL STATION ROOSEVELT ROADS BASEMENT 24". Thence S25°06'47"E 5671.51' to an iron rod set, (the True Point of Beginning, having a northing of 791511.3792 and an easting of 930156.9139):

Thence S18°30'36"W 166.08' to a point not set;

Thence N71°29'24"W 87.49' to a point not set;

Thence following a curve to a point not set; with a long chord of 395.01', a chord bearing of N49°38'14"W,

Radius= 530.61'

Arc=404.75'

Thence S64°52'27"W 372.81' to a point not set;

Thence following a curve to a point not set; with a long chord of 132.18', a chord bearing of N70°06'25"W,

Radius= 724.61'

Arc=132.36'

Thence S75°20'24"W 301.47' to a point not set;

Thence following a curve to a point not set; with a long chord of 167.79', a chord bearing of S88°16'52"W,

Radius= 374.61'

Arc=169.22'

Thence N78°46'40"W 162.48' to a point not set;

Thence following a curve to a point not set; with a long chord of 157.98', a chord bearing of S37°18'43"E,

Radius= 374.39'

Arc=159.18'

Thence S49°29'31"E 57.39' to a point not set;

Thence following a curve to a point not set; with a long chord of 155.14', a chord bearing of S18°15'41"E,

Radius= 149.61'

Arc=163.10'

Thence following a curve to a point not set; with a long chord of 89.12', a chord bearing of S19°22'19"W,

Radius= 399.61'

Arc=89.31'

Thence N37°21'10"W 56.21' to a point not set;

Thence following a curve to a point not set; with a long chord of 52.83', a chord bearing of N17°17'33"E,

Radius= 350.39'

Arc=52.88'

Thence following a curve to a point not set; with a long chord of 104.10', a chord bearing of N18°15'41"W,

Radius= 100.39'

Arc=109.44'

Thence N49°29'31"W 57.39' to a point not set;

Thence following a curve to a point not set; with a long chord of 193.18', a chord bearing of N36°18'43"W,

Radius= 423.61'

Arc=194.89'

Thence N23°07'54"W 41.33' to a point not set;

Thence N11°13'20"E 32.22' to a point not set;

Thence S78°46'40"E 234.00' to a point not set;

Thence following a curve to a point not set; with a long chord of 145.74', a chord bearing of N88°16'52"E,

Radius= 325.39'

Arc=146.99'

Thence N75°20'24"E 301.47' to a point not set;

Thence following a curve to a point not set; with a long chord of 123.20', a chord bearing of N70°06'25"E,

Radius= 675.39'

Arc=123.37'

Thence N64°52'27"E 422.09' to a point not set;

Thence following a curve to a point not set; with a long chord of 401.51', a chord bearing of S46°50'34"E,

Radius= 481.39'

Arc=414.16'

Thence S71°29'24"E 38.27' to a point not set;

Thence N18°30'36"E 116.78' to a point not set;

Thence S71°29'24"E 41.15' to a point not set;

Thence following a curve to an iron rod set, the True Point of Beginning with a long chord of 8.07', a chord bearing of S72°04'08"E,

Radius= 399.61'

Arc=8.07'

Said parcel containing 112,345.5 square feet or 2.579 acres, which equates to 10,437.3 square meters or 2.656 cuerdas.

LEGAL DESCRIPTION EASEMENT 25

Beginning at a survey control point in the Ward of Quebrada Seca, said point being a brass disk set in concrete. Said point also known as 'DELICIAS' and having a northing of 799143.8537 and an easting of 927504.4901 noted as the Point of Beginning on the plat labeled "UNITED STATES GOVERNMENT PROPERTY FORMER NAVAL STATION ROOSEVELT ROADS EASEMENT 25". Thence S65°46'40"W 1154.24' to an iron rod set, the True Point of Beginning, having a northing of 798670.2992 and an easting of 926451.8698:

Thence following a curve to a point not set with a long chord of 58.23', chord bearing of S32°42'00"E

Radius=370.48'

Arc=58.29'

Thence following a curve to a point not set with a long chord of 422.66', chord bearing of S69°24'05"W

Radius=320.39'

Arc=461.54'

Thence N71°15'39"W 15.42' to an iron rod set;

Thence N21°18'51"W 43.57' to a point not set;

Thence following a curve to a point not set with a long chord of 418.41', chord bearing of N66°36'34"E

Radius=369.61'

Arc=444.76'

Thence S37°12'25"E 17.52' to an iron rod set the True Point of Beginning.

Said parcel containing 22,596.3 square feet or 0.519 of an acre, which equates to 2,099.3 square meters or 0.534 of a cuerda.

LEGAL DESCRIPTION FOR EASEMENT 26

Beginning at a survey control point in the Ward of Daguao, said point being a brass disk set in concrete. Said point known as "COLINA" and having a northing of 797036.8324 and an easting of 916304.6005 noted as the Point of Beginning on the plat labeled "UNITED STATES GOVERNMENT PROPERTY FORMER NAVAL STATION ROOSEVELT ROADS EASEMENT 26". Thence N67°51'33"E 4952.64' to POINT #26-3A, an iron rod set, the True Point of Beginning, having a northing of 798903.4095 and an easting of 920892.0277:

Thence N07°56'34"E 730.47' to a point not set;
Thence S83°59'00"E 26.33' to a point not set;
Thence S06°01'00"W 450.00' to a point not set;
Thence N83°59'00"W 15.00' to a point not set;
Thence S06°01'00"W 341.39' to a point not set;
Thence N85°23'18"W 41.58' to a point not set;
Thence N11°14'04"E 62.61' to a POINT # 26-3A, an iron rod set the True Point of beginning.

Said parcel containing 26,373.1 square feet or 0.605 of an acre, which equates to 2450.2 square meters or 0.623 of a cuerda.

LEGAL DESCRIPTION EASEMENT 27

Beginning at a survey control point in the Ward of Guayacan, said point being a brass disk set in concrete. Said point also known as 'DELICIAS' and having a northing of 799143.8537 and an easting of 927504.4901 noted as the Point of Beginning on the plat labeled "UNITED STATES GOVERNMENT PROPERTY FORMER NAVAL STATION ROOSEVELT ROADS EASEMENT 27". Thence N67°33'29"E 3925.91' to an iron rod set, the True Point of Beginning, having a northing of 800642.5529 and an easting of 931133.0789;

Thence N74°40'21"W 111.12' to a point not set;

Thence following a curve to a point not set with a long chord of 408.37', chord bearing of N65°04'28"W

Radius=1224.61'

Arc=410.28'

Thence N55°28'36"W 108.63' to a point not set;

Thence following a curve to a point not set with a long chord of 239.53', chord bearing of N32°33'46"W

Radius=307.61'

Arc=246.04'

Thence N09°38'56"W 228.13' to a point not set;

Thence N04°39'23"W 217.78' to a point not set;

Thence following a curve to a point not set with a long chord of 226.29', chord bearing of N18°40'54"E

Radius=285.61'

Arc=232.67'

Thence N42°01'11"E 105.61' to a point not set;

Thence following a curve to a point not set with a long chord of 161.10', chord bearing of N18°55'46"E

Radius=205.39'

Arc=165.55'

Thence N04°09'40"W 140.27' to a point not set;

Thence following a curve to a point not set with a long chord of 166.96', chord bearing of N14°16'29"W

Radius=475.39'

Arc=167.83'

Thence following a curve to a point not set with a long chord of 49.52', chord bearing of N04°54'08"W

Radius=74.22'

Arc=50.48'

Thence N14°35'03"E 89.02' to a point not set;

Thence following a curve to a point not set with a long chord of 61.93', chord bearing of N67°13'22"E

Radius=263.00'

Arc=62.07'

Thence S14°35'03"W 126.60' to a point not set;

Thence following a curve to a point not set with a long chord of 16.68', chord bearing of S04°54'08"E

Radius=25.00'

Arc=17.00'

Thence following a curve to a point not set with a long chord of 184.25', chord bearing of S14°16'29"E

Radius=524.61'

Arc=185.21'

Thence S04°09'40"E 140.27' to a point not set;

Thence following a curve to a point not set with a long chord of 199.71', chord bearing of S18°55'46"W

Radius=254.61'

Arc=205.22'

Thence S42°01'11"W 105.61' to a point not set;

Thence following a curve to a point not set with a long chord of 187.29', chord bearing of S18°40'54"W

Radius=236.39'

Arc=192.58'

Thence S04°39'23"E 215.64' to a point not set;

Thence S09°38'56"E 225.98' to a point not set;

Thence following a curve to a point not set with a long chord of 201.21', chord bearing of S32°33'46"E

Radius=258.39'

Arc=206.67'

Thence S55°28'36"E 108.63' to a point not set;

Thence following a curve to a point not set with a long chord of 391.95', chord bearing of S65°04'28"E

Radius=1175.39'

Arc=393.79'

Thence S74°40'21"E 116.04' to a point not set;

Thence S19°59'21"W 12.83' to a point not set;

Thence following a curve to an iron rod set, the True Point of Beginning with a long chord of 36.64', chord bearing of S21°23'45"W

Radius=746.21'

Arc=36.64'

Said parcel containing 110,992.1 square feet or 2.548 acres, which equates to 10,311.5 square meters or 2.624 cuerdas.

LEGAL DESCRIPTION EASEMENT 28

Beginning at a survey control point in the Ward of Guaynaboa, said point being a brass disk set in concrete, Said point also known as 'DOG' and having a northing of 805443.8964 and an easting of 933110.4735 noted as the Point of Beginning on the plat labeled "UNITED STATES GOVERNMENT PROPERTY FORMER NAVAL STATION ROOSEVELT ROADS EASEMENT 28". Thence S80°32'06"W 1455.73' to an iron rod set, the True Point of Beginning, having a northing of 805204.5081 and an easting of 931674.5620:

Thence S02°46'27"E 399.73' to an iron rod set;
Thence S23°35'04"W 247.75' to an iron rod set;
Thence S19°01'22"W 388.54' to a MAG nail set;
Thence S29°57'10"W 290.23' to an iron rod set;
Thence S32°49'53"W 712.89' to an iron rod set;
Thence S32°37'31"W 558.73' to a point not set;
Thence following a curve to a point not set with a long chord of 107.57', chord bearing of N63°04'19"W
Radius=263.00'
Arc=108.33'
Thence N32°37'31"E 1500.73' to a point not set;
Thence N21°31'21"E 641.58' to a point not set;
Thence N02°46'27"W 368.63' to an iron rod set;
Thence N71°08'07"E 114.48' to an iron rod set, the True Point of Beginning.

Said parcel containing 268,631.5 square feet or 6.170 acres, which equates to 24,956.8 square meters or 6.350 cuerdas.

Exhibit "D"

**FINDING OF SUITABILITY TO TRANSFER
FOR SALE PARCEL II - CAPEHART**

gff
mjb

FINDING OF SUITABILITY TO TRANSFER

SALE PARCEL II - CAPEHART

**NAVAL ACTIVITY PUERTO RICO
CEIBA, PUERTO RICO**



*gcp
mab*

Prepared by:

**Department of the Navy
Base Realignment and Closure
Program Management Office Southeast
4130 Faber Place Drive, Suite 202
North Charleston, South Carolina 29405**

December 2007

**FINDING OF SUITABILITY TO TRANSFER
SALE PARCEL II - CAPEHART
NAVAL ACTIVITY PUERTO RICO**

TABLE OF CONTENTS

| <u>SECTION</u> | <u>PAGE</u> |
|---|-------------|
| 1.0 PURPOSE..... | 1 |
| 2.0 DESCRIPTION OF PROPERTY..... | 1 |
| 3.0 PAST USE AND PROPOSED REUSE | 2 |
| 4.0 ENVIRONMENTAL FINDINGS | 3 |
| A. Hazardous Substance Contamination | 3 |
| B. Petroleum Contamination | 3 |
| C. Condition of Property Classification | 4 |
| D. Other Environmental Aspects | 4 |
| 5.0 REQUIREMENTS APPLICABLE TO PROPERTY TRANSFER | 8 |
| A. NEPA Compliance | 8 |
| B. Hazardous Substance Notice | 9 |
| C. CERCLA Covenant | 9 |
| D. CERCLA Access Clause..... | 9 |
| E. Land and Groundwater Restrictions | 9 |
| F. Environmental Compliance Agreements / Permits / Orders | 9 |
| G. Notification to Regulatory Agencies / Public | 10 |
| 6.0 SUITABILITY DETERMINATION..... | 10 |

EXHIBITS

| | |
|---|--|
| A | References |
| B | Vicinity Map |
| C | Parcel Maps |
| D | Survey Map |
| E | Tables |
| F | CERFA Concurrence |
| G | Asbestos Inspection Reports and Lead-Based Paint Inspection/Risk Assessment Report |
| H | Lead-Based Paint Hazards Advisory Statement |
| I | Responses to Comments |

FINDING OF SUITABILITY TO TRANSFER SALE PARCEL II - CAPEHART NAVAL ACTIVITY PUERTO RICO

1.0 PURPOSE

This Finding of Suitability to Transfer (FOST) summarizes how the requirements and notifications for hazardous substances, petroleum products, and other regulated material on the property have been satisfied, and documents my determination, as the responsible Department of Defense (DoD) component official, that certain real property and associated improvements known as Sale Parcel II - Capehart (Subject Property) at Naval Activity Puerto Rico (NAPR), Ceiba, Puerto Rico, are environmentally suitable for deed transfer. This decision is based primarily on my review of information contained in two of the documents listed in Exhibit A (References) – CERFA Identification of Uncontaminated Property, Former Naval Station Roosevelt Roads, Puerto Rico (the CERFA Report; Navy, 2006b), and Phase I/II Environmental Condition of Property Report, Former Naval Station Roosevelt Roads, Ceiba, Puerto Rico (the ECP Report; Navy, 2005). Factors leading to this decision and other pertinent information related to property transfer requirements are stated below.

2.0 DESCRIPTION OF PROPERTY

NAPR was formerly known as Naval Station Roosevelt Roads (NSRR) until it ceased operation as an active Naval Station on March 31, 2004, at which point it was designated NAPR to serve as the caretaker of the real property associated with NSRR and to assist in the transfer of the property. NAPR is located on the east coast of Puerto Rico adjacent to the municipality of Ceiba. The Subject Property consists of approximately 495 acres located in the southeast section of the installation, and is primarily comprised of residential neighborhoods. Additional facilities include a high school, community center, medical clinics, storage buildings and various recreational facilities. Exhibits B, C, and D provide a vicinity map, parcel maps from the Draft Report, Parcel Map for the Disposal of Naval Activity Puerto Rico (GMI, 2005), and a boundary survey map, respectively. The Subject Property is comprised of Sub-Parcels 8, 10, 14, 15 and 16, as shown in Exhibit C.

Seven of the eight former NSRR housing communities are located on the Subject Property. The Final Asbestos Inspection Report for Military Family Housing, Naval Activity Puerto Rico, Ceiba, Puerto Rico (Baker, 2005a) provides the following information for these housing areas:

FINDING OF SUITABILITY TO TRANSFER SALE PARCEL II - CAPEHART NAVAL ACTIVITY PUERTO RICO

- Algodones – 2, 3, and 4-Bedroom (BR) Apartment Style Units; constructed 1960; renovated 1991
- Caribe Breeze – 2, 3, and 4-BR Duplex Units; constructed 1974; renovated 2001-2003
- Cascajo Point – 2, 3, and 4-BR Single Family Houses; constructed 1960; renovated 1998-2001
- Coast Guard – 3 and 4-BR Single Family Houses; constructed 1960; renovated 1989-1992
- FDR Drive – 3-BR Single Family Houses; constructed 1960; renovated 1999-2000
- Manatee Bay – 2, 3, and 4-BR Single Family Houses; constructed 1960; renovated 2001-2003
- Mangrove Manor – 2, 3, and 4-BR Single Family Houses; constructed 1960; renovated 1989-1992

The housing units are concrete-framed buildings with concrete or ceramic exterior finishes. Interior walls are painted gypsum board and concrete. In addition to the housing units described above, there are approximately 46 other numbered buildings, structures, and facilities on the Subject Property (not including multiple pavilions at Community Beach). Table 1 (Exhibit E) provides their facility number, former user, name or description, area, and year of construction.

3. PAST USE AND PROPOSED REUSE

The Subject Property has been used as a military installation since its acquisition and development by the Navy in the 1940s. The Environmental Condition of Property (ECP) Report states that most of the arable land on what is now NAPR was previously used for sugar cane cultivation and cattle grazing. No significant industrial facilities or environmental concerns were identified with respect to activities conducted on the former NSRR prior to Navy ownership. The Navy has used the Subject Property for residential and ancillary purposes only.

The *Naval Station Roosevelt Roads Reuse Plan* (CBRE et al, 2004) developed by the Puerto Rico Department of Economic Development and Commerce (acting as the Local Redevelopment Authority) anticipates future use of the Subject Property as residential with ancillary uses including reuse of the high school and gymnasium. The Subject Property will be sold via public auction to the highest qualified bidder.

**FINDING OF SUITABILITY TO TRANSFER
SALE PARCEL II - CAPEHART
NAVAL ACTIVITY PUERTO RICO**

4. ENVIRONMENTAL FINDINGS

All available information concerning the past storage, release, or disposal of hazardous substances and/or petroleum products on NAPR, as collected through record searches, aerial photographs, personnel interviews, and on-site visual inspections, is contained in the ECP Report. The following summarizes the findings as they relate to the Subject Property and the corresponding Condition of Property Classification assigned to the real property to be transferred.

A. Hazardous Substance Contamination

There is nothing in the records that indicates any hazardous substance has been released or disposed of on the Subject Property, and the ECP investigation did not discover any radioactive materials at the medical clinics, nor any environmental issues associated with medical waste. There was once a satellite hazardous waste accumulation area for lab packs associated with Building 2200 (High School). The storage area was no longer in use at the time of the ECP inspection.

B. Petroleum Contamination

According to the ECP Report, there was one underground storage tank (UST) formerly located on the Subject Property. UST 1513 was a 280-gallon diesel fuel tank associated with Building 1513, a sewage lift station. The UST was removed in August 1996, as shown on Table 2 in Exhibit E. The ECP Report also documented three operational aboveground storage tanks (ASTs) used for storage of diesel fuel for sewage lift station standby generators on the Subject Property. One of these, AST 1972, replaced UST 1513. These ASTs are also listed in Table 2. According to the ECP Report, any contaminated soils identified during past replacement of tanks were excavated and disposed of off NSRR property, and the replaced tanks were closed in accordance with Title 40 Code of Federal Regulations (CFR) Part 280. The records do not indicate there have been any spills or releases associated with UST 1513 or the ASTs on the Subject Property, nor any other releases or instances of disposal of petroleum products or their derivatives.

C. Condition of Property Classification

The ECP Report divided all property at NAPR into parcels, and classified them into one of the three following categories:

**FINDING OF SUITABILITY TO TRANSFER
SALE PARCEL II - CAPEHART
NAVAL ACTIVITY PUERTO RICO**

- **Category 1** – Areas where no known or documented releases, or disposal of hazardous substances or petroleum products or their derivatives has occurred, including no migration of these substances from adjacent areas.
- **Category 2** – Areas where the release, disposal, or migration, or some combination thereof, of hazardous substances, or petroleum products or their derivatives has occurred, but at concentrations that do not require a removal or remedial action, or all remedial actions necessary to protect human health and the environment have been taken.
- **Category 3** – Areas where a confirmed or suspected release, disposal, or migration, or some combination thereof, of hazardous substances, or petroleum products or their derivatives has occurred, but required investigation and/or response actions have not yet been initiated or are ongoing.

These categories are derived from the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA), the Community Environmental Response Facilitation Act (CERFA) and the American Society for Testing and Materials (ASTM) Standard Practice for Conducting Environmental Baseline Surveys (ASTM Standard D 6008-96), which further incorporates ASTM D 5746-98 (2002) Standard Classification of Environmental Condition of Property Area Types for Defense Base Closure and Realignment Facilities.

CERFA stipulates that the federal government must identify "uncontaminated property" scheduled for transfer, and defines this as "...real property on which no hazardous substances and no petroleum products or their derivatives were known to have been released, or disposed of" [(Section 9620(h)(4)(A)]. In accordance with the property condition classification guidelines discussed above, the Navy classified the Subject Property as Category 1 uncontaminated property. Following its review of the CERFA Report, the Puerto Rico Environmental Quality Board (EQB) concurred with this classification and provided a concurrence statement (Exhibit F) in the Final CERFA Report on 11 August 2006.

D. Other Environmental Aspects

1. Munitions and Explosives of Concern

The records do not indicate ordnance handling, storage, or disposal activities have ever been conducted on the Subject Property.

**FINDING OF SUITABILITY TO TRANSFER
SALE PARCEL II - CAPEHART
NAVAL ACTIVITY PUERTO RICO**

2. Asbestos-Containing Materials

An asbestos-containing material (ACM) inspection of military family housing in the eight NAPR residential communities was performed in January and February 2005 in anticipation of property transfer. According to the June 2005 Final Asbestos Inspection Report for Military Family Housing, Naval Activity Puerto Rico, Ceiba, Puerto Rico (Baker, 2005a), NAPR housing was reportedly constructed between 1960 and 1975. Twenty-seven of the housing units in the Manatee Bay community are of original construction and the remaining 935 NAPR units were renovated to varying degrees beginning in 1989. Renovation of some of the units included removal of ACM.

While ACM was identified in all of the residential communities on the Subject Property, no friable, accessible, and damaged (FAD) ACM hazards were identified in the housing units that were inspected. Not all units in NAPR housing were inspected. Instead, a representative number of units were inspected in each housing community. Detailed information about the units inspected and the materials identified and sampled during the asbestos inspection, including summary tables, location drawings, photographs and laboratory reports is included in the report. The report text (without appendices) is included in Exhibit G of this FOST.

According to the June 2005 Final Asbestos Inspection Report for Naval Activity Puerto Rico, Ceiba, Puerto Rico (Baker, 2005b), ACM was identified in 6 of the 26 non-housing facilities inspected on the Subject Property, as summarized in Table 3 of Exhibit E. No FAD ACM hazards were identified in any of the facilities. Detailed information about the materials identified and sampled during the asbestos inspection, including summary tables, location drawings, photographs and laboratory reports, is included in the report. The report text (without appendices) is included in Exhibit G of this FOST.

If renovation of housing units is scheduled following transfer, a more comprehensive ACM inspection should be conducted to attempt to identify hidden ACM (e.g., behind walls, above ceilings, etc.) that would not have been identified during the non-destructive, baseline asbestos study. Furthermore, the possibility remains for the presence of undiscovered ACM associated with underground utilities and miscellaneous building materials at NAPR. While this potential ACM does not pose a hazard to site users, future demolition and/or subsurface work performed by the transferee could result in FAD ACM

FINDING OF SUITABILITY TO TRANSFER SALE PARCEL II - CAPEHART NAVAL ACTIVITY PUERTO RICO

hazards. Thus, the transferee will be required to use best management practices during any future renovation/demolition activities or underground utility work, and to comply with all applicable laws relating to ACM management in order to ensure future protection of human health and the environment.

3. Lead-Based Paint

A lead-based paint (LBP) inspection and risk assessment of military family housing at NAPR was performed in conjunction with the ACM inspection described above. According to the June 2005 *Final Lead-Based Paint Inspection/Risk Assessment Report for Military Family Housing, Naval Activity Puerto Rico, Ceiba, Puerto Rico* (Baker, 2005c), NAPR housing was reportedly constructed between 1960 and 1975. Twenty-seven of the housing units in the Manatee Bay community are of original construction and the remaining 935 NAPR units were renovated to varying degrees beginning in 1989. Renovation of some of the units included removal of LBP.

In accordance with U.S. Department of Housing and Urban Development regulations, the Navy is required to inspect and assess NAPR housing for LBP and LBP hazards and disclose the results to the next owner. Because the housing units were constructed in 1960 and later, LBP hazards are not required to be abated before the sale of the properties. LBP hazards were identified in the Algodones, Coast Guard, Manatee Bay, and Mangrove Manor housing communities only, and included deteriorated LBP on various components and slightly elevated lead in dust on floors. Hazards related to friction surfaces, impact surfaces, chewable surfaces, and soil were not identified in these communities. No LBP hazard of any type was identified in the Caribe Breeze, Cascajo Point, or FDR Drive communities. Not all units in NAPR housing were inspected. Instead, a representative number of units were inspected in each housing community. Detailed information about the inspection and risk assessment methodologies, units inspected and the materials identified and sampled during the LBP inspection, including summary tables, location drawings, photographs, laboratory reports, and LBP control options is included in the report. (Baker, 2005c) The report text (without appendices) is included in Exhibit G of this FOST.

FINDING OF SUITABILITY TO TRANSFER SALE PARCEL II - CAPEHART NAVAL ACTIVITY PUERTO RICO

The NAPR facilities list (Exhibit E, Table 1) indicates the majority of the non-housing buildings, structures and facilities on the Subject Property were constructed prior to 1978, the year in which LBP was banned for consumer use. These facilities, which were not included in the military family housing LBP survey, and any others built before 1978 are presumed to contain LBP.

A Lead-Based Paint Hazards Advisory Statement, Exhibit H to this FOST, will be provided to the transferee for execution at the time of transfer.

4. Polychlorinated Biphenyls

Only one polychlorinated biphenyl (PCB) containing-transformer remains at NAPR. The transformer, located in Building 386, is not on the Subject Property. All other PCB-contaminated transformers and equipment were removed from the former NSRR prior to 1998. Due to the age of the majority of facilities and the size of the station, it is possible that PCB-contaminated fluorescent light ballasts and other minor PCB sources may be present on NAPR. There is nothing in the records to indicate PCBs were ever stored or disposed of on the Subject Property.

5. Radon

According to the U.S. Geological Survey Open-File Report 93-292-K, *Preliminary Geologic Radon Potential Assessment of Puerto Rico* (USGS, 1993), the Commonwealth of Puerto Rico exhibits generally low indoor radon levels, and a survey of radon concentrations of offices, housing units, schools and other buildings was conducted by the DoD between 1989 and 1992 on federal military reservations in Puerto Rico, including the former NSRR. Indoor radon levels ranged from 0.0 to 1.9 picoCuries/Liter (pCi/L), well below the current U.S. Environmental Protection Agency (EPA) residential indoor radon screening action level of 4 pCi/L. The majority of the reservations, including NAPR, are situated on coastal plains, so the low indoor radon levels were not unexpected.

**FINDING OF SUITABILITY TO TRANSFER
SALE PARCEL II - CAPEHART
NAVAL ACTIVITY PUERTO RICO**

6. Threatened and Endangered Species

As shown on the individual parcel maps in Exhibit C, both sea turtle habitat and breeding habitat and nesting/foraging palms for the endangered yellow-shouldered blackbird have been identified on the Subject Property. The Commonwealth of Puerto Rico has committed to zone the property in a manner that will implement the planning, development, maintenance, mitigation and use requirements described on the parcel maps.

In accordance with the Endangered Species Act, the Navy developed a Biological Assessment (BA) for the former NSRR in 2006 to assess the potential impact on any federally protected species from the disposal of NSRR. Given the protection measures addressed in detail in the *Biological Assessment for the Disposal of Naval Station Roosevelt Roads/Naval Activity Puerto Rico Final Report* (Navy, 2006a), the Navy has determined that the disposal of the former NSRR and transfer of the property to future owners is not likely to adversely affect federally-listed species and would not result in adverse modification of designated critical habitat within the project area. The U.S. Fish and Wildlife Service concurred with this determination in a letter dated April 7, 2006.

5.0 REQUIREMENTS APPLICABLE TO PROPERTY TRANSFER

A. NEPA Compliance

In accordance with National Environmental Policy Act (NEPA) requirements, an Environmental Assessment and Finding of No Significant Impact (FONSI) have been prepared and executed in connection with the planned disposal and reuse of NAPR. The FONSI was signed on April 10, 2007.

B. Hazardous Substance Notice

In accordance with Section 120(h)(3)(A)(i) of CERCLA, all deeds transferring federal property must provide notice as to those hazardous substances which it is known, based on a complete search of agency files, were stored for one year or more, released or disposed on the Subject Property in excess of those reportable quantities specified under Title 40 CFR Part 373, and all response actions taken to date to address any such releases or disposals. No hazardous

FINDING OF SUITABILITY TO TRANSFER SALE PARCEL II - CAPEHART NAVAL ACTIVITY PUERTO RICO

substances are known to have been stored or released on the Subject Property in excess of their respective reportable quantities, thus, no deed notice is required in this instance.

C. CERCLA Covenant

In accordance with CERCLA Section 120(h)(4)(D)(i), the deed transferring the Subject Property shall contain a covenant warranting that any response action or corrective action found to be necessary after the date of transfer shall be conducted by the United States.

D. CERCLA Access Clause

In accordance with CERCLA Section 120(h)(4)(D)(ii), the deed transferring the Subject Property shall contain a clause granting to the United States, its officers, agents, employees, contractors, and subcontractors the right to enter upon the transferred property in any case that remedial or corrective action is found to be necessary after the date of transfer. The right to enter to be set forth shall include the right to conduct annual physical inspections, tests, investigations, long term monitoring, 5-year reviews, and surveys, including, where necessary, drilling, test pitting, boring, and other similar activities. Such right shall also include the right to construct, operate, maintain, or undertake any other response or remedial action as required or necessary, including, but not limited to, monitoring wells, pumping wells, and treatment facilities. The United States retains the authority to enter to conduct investigations on adjacent parcels as well as the parcel subject to the transfer. These access rights are in addition to those granted to Federal, state, and local authorities under applicable environmental laws and regulations.

E. Land and Groundwater Restrictions

The Navy will transfer all of the Subject Property without restrictions.

F. Environmental Compliance Agreements / Permits / Orders

On January 29, 2007, the U.S. Department of the Navy and EPA voluntarily entered into a Resource Conservation and Recovery Act (RCRA) Section 7003 Administrative Order on Consent (Consent Order; EPA, 2007). The Consent Order set out the Navy's RCRA corrective action obligations and replaced the 1994 RCRA permit as the document memorializing these obligations concerning NAPR. Although there are no RCRA solid waste management units or

**FINDING OF SUITABILITY TO TRANSFER
SALE PARCEL II - CAPEHART
NAVAL ACTIVITY PUERTO RICO**

areas of concern on the Subject Property, certain RCRA obligations defined in the Consent Order apply to the Subject Property including notification and additional work requirements for newly discovered releases, other notification requirements, and record retention requirements. There are no other environmental compliance agreements, permits, or orders associated with the Subject Property.

G. Notification to Regulatory Agencies / Public

In accordance with DoD guidance, EPA Region 2 and the Puerto Rico EQB have been advised of the proposed transfer of the Subject Property, and copies of the ECP Report and Draft FOST were provided to those agencies for review and comment. Two comments were received from EPA. Those comments and Navy responses are provided in Exhibit I. The ECP Report was made available for public review upon finalization. Copies of all transfer documentation will be made available to EPA and EQB representatives upon request after execution of the same.

6.0 SUITABILITY DETERMINATION

NOW THEREFORE, based on my review of the information contained in this FOST and in the ECP and CERFA Reports, I have determined that the Subject Property is presently suitable for deed transfer for unrestricted reuse.

1 / 3 / 08
Date

James E. Anderson
JAMES E. ANDERSON
Director
BRAC Program Management Office Southeast
North Charleston, South Carolina

Exhibit A
References

**FINDING OF SUITABILITY TO TRANSFER
SALE PARCEL II - CAPEHART
NAVAL ACTIVITY PUERTO RICO**

REFERENCES

Baker, 2005a. (Michael Baker Jr., Inc.) *Final Asbestos Inspection Report for Military Family Housing, Naval Activity Puerto Rico, Ceiba, Puerto Rico*. Moon Township, Pennsylvania. June 2005.

Baker, 2005b. (Michael Baker Jr., Inc.) *Final Asbestos Inspection Report for Naval Activity Puerto Rico, Ceiba, Puerto Rico*. Moon Township, Pennsylvania. June 2005.

Baker, 2005c. (Michael Baker Jr., Inc.) *Final Lead-Base Paint Inspection/Risk Assessment Report for Military Family Housing, Naval Activity Puerto Rico, Ceiba, Puerto Rico*. Moon Township, Pennsylvania. June 2005.

CBRE et al, 2004. (CB Richard Ellis Consulting, Cooper Robertson & Parnters, Moffatt & Nichol, Puerto Rico Management & Economic Consultants, Inc.) *Naval Station Roosevelt Roads Reuse Plan*. December 2004.

EPA, 2007. (U.S. Environmental Protection Agency) *RCRA § 7003 Administrative Order on Consent, In the Matter of United States, The Department of the Navy, Naval Activity Puerto Rico, formerly Naval Station Roosevelt Roads, Puerto Rico, EPA Docket No. RCRA-02-2007-7301*. January 2007.

GMI, 2005. (Geo-Marine, Inc.) *Draft Report, Parcel Map for the Disposal of Naval Activity Puerto Rico*. Hampton, Virginia. September 2005.



Navy, 2005. (Naval Facilities Engineering Command Atlantic) *Phase I/II Environmental Condition of Property Report, Former U.S. Naval Station Roosevelt Roads, Ceiba, Puerto Rico*. Norfolk, Virginia. July 15, 2005.

Navy, 2006a. (Naval Facilities Engineering Command Atlantic). *Biological Assessment for the Disposal of Naval Station Roosevelt Roads/Naval Activity Puerto Rico Final Report*. Norfolk, Virginia. January 2006.

Navy, 2006b. (Department of the Navy, Base Realignment and Closure Program Management Office Southeast) *CERFA Identification of Uncontaminated Property, Former Naval Station Roosevelt Roads, Puerto Rico*. North Charleston, South Carolina, April 27, 2006.

USGS, 1993. (U.S. Geological Survey) *Open File Report 93-292-K, Preliminary Geologic Radon Potential Assessment of Puerto Rico*. 1993.

Exhibit B
Vicinity Map



| | |
|--------------------|----------|
| DRAWN BY | DATE |
| S. STROZ | 10/08/07 |
| CHECKED BY | DATE |
| L. ANDERSON | 10/08/07 |
| COST/SCHEDULE-AREA | |
| SCALE AS NOTED | |



SALE PARCEL II
 NAVAL ACTIVITY PUERTO RICO
 CEIBA, PUERTO RICO

| | |
|-------------------------|-----------|
| CONTRACT NUMBER 0043 | |
| APPROVED BY — | DATE — |
| APPROVED BY — | DATE — |
| DRAWING NO. — | REV 0 |

Exhibit C
Parcel Maps

THREATENED AND ENDANGERED SPECIES CONSERVATION MEASURES—PARCEL 8

Common Name—Sale

Conveyance—Sale

Neighboring Parcel(s)—5, 6, 7, 9, 13-16

Yellow-shouldered Blackbird

GENERAL REQUIREMENTS

- No development is allowed in Parcel 5, 7, 9, and 13 (Conservation).
- All development related activities (new construction, ground clearing, demolition/remodeling) adjacent to conservation parcels (5, 7, 9, and 13) should occur between September 1 and March 15 (non-breeding season) or be restricted to an area 50 m from the conservation parcel boundary from March 15-August 30 (breeding season).
- Notify U.S. Fish and Wildlife Service (USFWS) if a yellow-shouldered blackbird nest is found anywhere on the property (787-851-7297).
- Pesticide and herbicide applications must follow Commonwealth of Puerto Rico regulations.

| Activity | Conservation Measures |
|------------------------------|---|
| Development Planning | Save as many existing on site palms and trees as possible in new development plans. |
| Demolition/Remodeling | Schedule activity from September 1 through March 14 or conduct outdoor survey of building(s) (ledges, etc.) and nearby trees (within 50 m of the building) for yellow-shouldered blackbird nests prior to start date if the activity is scheduled to occur between March 15 and August 30. Consult with USFWS if a yellow-shouldered blackbird nest is found. |
| Grounds Maintenance | No trimming or cutting of palms and trees between March 15 and August 30 except in an emergency (i.e., downed trees and palms from storms). |
| Building Maintenance | Check for yellow-shouldered blackbird nests prior to any outdoor building maintenance activities between March 15 and August 30. Determine identity of any bird nest found. Notify and consult with USFWS if a yellow-shouldered blackbird nest is found. |
| General Operations | Before moving parked outdoor equipment (e.g., light cars, carts, vehicles) check for yellow-shouldered blackbird nests (March 15-August 30). Notify USFWS if a yellow-shouldered blackbird nest is located. |
| Property Sale/Lease | Notify buyer/lessee of all mitigation requirements (see above) and include mitigation with all legal documents. |

Sea Turtle

GENERAL REQUIREMENTS

- Consult with USFWS and Puerto Rico Department of Environmental Resources (DNER) on all beach use plans and permit requirements.
- Notify USFWS if you observe an injured or dead turtle anywhere on the property (787-851-7297).
- Pesticide and herbicide applications must follow Commonwealth of Puerto Rico regulations.

***Parcel Map for the Disposal
of Naval Activity Puerto Rico***

| Activity | Conservation Measures |
|------------------------------|--|
| Beach Development/Use | Implement all USFWS and Puerto Rico DNER lighting standards/requirements (includes parcels bordering the nesting area) and USFWS/ Puerto Rico DNER precautionary measures for sea turtles before, during, and after development activities. Establish a 50 m buffer zone between any developed or undeveloped site and the land edge of a sea turtle nesting beach. |

Cobana Negra

GENERAL REQUIREMENTS


- Consult with USFWS regarding any recreational development plans (e.g., hiking trails) in Parcel 5.

NOTICE:

Consult with the U.S. Fish and Wildlife Service if you have any questions on the conservation measures. Property owners that cannot adhere to the conservation measures must consult with the U.S. Fish and Wildlife Service to seek a Section 10.0 permit for authorization to modify the identified critical habitat. Failure to comply with the identified conservation measures violates Section 9.0 and/or Section 10.0 of the Endangered Species Act. The U.S. Fish and Wildlife Service has the authority to prosecute violations under the Endangered Species Act.

This page intentionally left blank

*Parcel Map for the Disposal
of Naval Activity Puerto Rico*




Parcel Index 8

Common Name: Sale
Conveyance: Sale
Neighboring Parcel(s): 5, 6, 7, 9,
13-16


Legend

- Parcel
- Neighboring Parcel Boundaries
- Cleanup Status
 - Complete with Land Use Controls
 - Complete
 - Cleanup Remaining



August 18, 2005

1 inch equals 678 Feet



THREATENED AND ENDANGERED SPECIES CONSERVATION MEASURES—PARCEL 10

Common Name—Sale

Conveyance—Sale

Neighboring Parcel(s)—11, 12, 13

Yellow-shouldered Blackbird

GENERAL REQUIREMENTS

- No development is allowed in Parcel 11, 12 and 13 (Conservation).
- All development related activities (new construction, ground clearing, demolition/remodeling) adjacent to conservation parcels (11, 12, and 13) between September 1 and March 15 (non-breeding season) or be restricted to an area 50 m from the conservation parcel boundary from March 15-August 30 (breeding season).
- Notify USFWS if a yellow-shouldered blackbird nest is found anywhere on the property (787-851-7297).
- Pesticide and herbicide applications must follow Commonwealth of Puerto Rico regulations.

| Activity | Conservation Measures |
|----------------------------------|---|
| Development Planning | Save as many existing on site palms and trees as possible in new development plans. |
| New Construction/Clearing | If undeveloped yellow-shouldered blackbird habitat is proposed for clearing consult with the USFWS a minimum of one year prior to planned project initiation. |
| Demolition/Remodeling | Schedule activity from September 1 through March 14 or conduct outdoor survey of building(s) (ledges, etc.) and nearby trees (within 50 m of the building) for yellow-shouldered blackbird nests prior to start date if the activity is scheduled to occur between March 15 and August 30. Consult with USFWS if a yellow-shouldered blackbird nest is found. |
| Grounds Maintenance | No trimming or cutting of palms and trees between March 15 and August 30 except in an emergency (i.e., downed trees and palms from storms). |
| General Operations | Before moving check moveable outdoor equipment (e.g., carts, vehicles) for yellow-shouldered blackbird nests from March 15-August 30. Notify USFWS if a yellow-shouldered blackbird nest is located. |
| Property Sale/Lease | Notify buyer/lessee of all mitigation requirements (see above) and include mitigation with all legal documents. |

Sea Turtle

GENERAL REQUIREMENTS

- Consult with U.S. Fish and Wildlife Service (USFWS) and Puerto Rico Department of Environmental Resources (DNER) on all beach use plans and permit requirements.
- Notify USFWS if you observe an injured or dead turtle anywhere on the property (787-851-7297).
- Pesticide and herbicide applications must follow Commonwealth of Puerto Rico regulations.

*Parcel Map for the Disposal
of Naval Activity Puerto Rico*

| Activity | Conservation Measures |
|------------------------------|--|
| Beach Development/Use | Implement all USFWS and Puerto Rico DNER lighting standards/requirements (includes parcels bordering the nesting area). Implement USFWS/ Puerto Rico DNER precautionary measures for sea turtles before, during, and after development activities. Establish a 50 m buffer zone between any developed or undeveloped site and the land edge of the sea turtle nesting beach. |

NOTICE:

Consult with the U.S. Fish and Wildlife Service if you have any questions on the conservation measures. Property owners that cannot adhere to the conservation measures must consult with the U.S. Fish and Wildlife Service to seek a Section 10.0 permit for authorization to modify the identified critical habitat. Failure to comply with the identified conservation measures violates Section 9.0 and/or Section 10.0 of the Endangered Species Act. The U.S. Fish and Wildlife Service has the authority to prosecute violations under the Endangered Species Act.

This page intentionally left blank


*Parcel Map for the Disposal
of Naval Activity Puerto Rico*

Parcel Index 10

Common Name: *Salé*
Conveyance: *Salé*
Neighboring Parcel(s): 11, 12, 13


Legend

-  Parcel
-  Neighboring Parcel Boundaries
-  Sea Turtle Habitat
-  Yellow-shouldered Blackbird
-  Nesting/Foraging Palms
-  Breeding Habitat



August 18, 2005

1 inch equals 496 Feet



Parcel Index 10

Common Name: Sale
Conveyance: Sale
Neighboring Parcel(s): 11, 12, 13


August 18, 2005

Legend

-  Parcel
-  Neighboring Parcel Boundaries
- Cleanup Status**
-  Complete with Land Use Controls
-  Complete
-  Cleanup Remaining



1 inch equals 496 Feet



THREATENED AND ENDANGERED SPECIES CONSERVATION MEASURES—PARCEL 14

Common Name—Sale
Conveyance—Sale
Neighboring Parcel(s)—8, 13, 15, 16

Yellow-shouldered Blackbird

GENERAL REQUIREMENTS

- No development is allowed in Parcel 13 and 16 (Conservation).
- All development related activities (new construction, ground clearing, demolition/remodeling) adjacent to conservation parcel 13 and 16 should occur between September 1 and March 15 (non-breeding season) or be restricted to an area 50 m from the parcel boundary from March 15-August 30 (breeding season).
- Notify USFWS if a yellow-shouldered blackbird nest is found anywhere on the property (787-851-7297).
- Pesticide and herbicide applications must follow Commonwealth of Puerto Rico regulations.

| Activity | Conservation Measures |
|------------------------------|---|
| Development Planning | Save as many existing on site palms and trees as possible in new development plans. |
| Demolition/Remodeling | Schedule activity from September 1 through March 14 or conduct outdoor survey of building(s) (ledges, etc.) and nearby trees (within 50 m of the building) for yellow-shouldered blackbird nests prior to start date if the activity is scheduled to occur between March 15 and August 30. Consult with USFWS if a yellow-shouldered blackbird nest is found. |
| Grounds Maintenance | No trimming or cutting of palms and trees between March 15 and August 30 except in an emergency (i.e., downed trees and palms from storms). |
| Building Maintenance | Check for yellow-shouldered blackbird nests prior to any outdoor building maintenance activities between March 15 and August 30. Determine identity of any bird nest found. Notify and consult with USFWS if a yellow-shouldered blackbird nest is found. |
| General Operations | Before moving parked outdoor equipment (e.g., carts, vehicles) check for yellow-shouldered blackbird nests (March 15-August 30). Notify USFWS if a yellow-shouldered blackbird nest is located. |
| Property Sale/Lease | Notify buyer/lessee of all mitigation requirements (see above) and include mitigation with all legal documents. |

NOTICE:

Consult with the U.S. Fish and Wildlife Service if you have any questions on the conservation measures. Property owners that cannot adhere to the conservation measures must consult with the U.S. Fish and Wildlife Service to seek a Section 10.0 permit for authorization to modify the identified critical habitat. Failure to comply with the identified conservation measures violates Section 9.0 and/or Section 10.0 of the Endangered Species Act. The U.S. Fish and Wildlife Service has the authority to prosecute violations under the Endangered Species Act.

*Parcel Map for the Disposal
of Naval Activity Puerto Rico*


Parcel Index 14

Common Name: *Safe*
Conveyance: *Safe*
Neighboring Parcel(s): 8, 13, 15, 16


Legend

-  Parcel
-  Neighboring Parcel Boundary
- Yellow-shouldered Blackbird**
 -  Nesting/Foraging Palms
 -  Breeding Habitat

August 18, 2005



1 inch equals 507 Feet




Parcel Index 14

Common Name: Sale
Conveyance: Sale
Neighboring Parcel(s): 8, 13, 15, 16


Legend

- Parcel
- Neighboring Parcel Boundaries
- Cleanup Status
 - Complete with Land Use Controls
 - Complete
 - Cleanup Remaining

August 18, 2005



1 inch equals 507 Feet



THREATENED AND ENDANGERED SPECIES CONSERVATION MEASURES—PARCEL 15

Common Name—Sale

Conveyance—Sale

Neighboring Parcel(s)—5, 8, 13, 14, 16

Yellow-shouldered Blackbird

GENERAL REQUIREMENTS

- No development is allowed in Parcel 13 (Conservation).
- All development related activities (new construction, ground clearing, demolition/remodeling) adjacent to Parcel 13 should occur between September 1 and March 15 (non-breeding season) or be restricted to an area 50 m from the parcel boundary from March 15-August 30 (breeding season).
- Notify USFWS if a yellow-shouldered blackbird nest is found anywhere on the property (787-851-7297).
- Pesticide and herbicide applications must follow Commonwealth of Puerto Rico regulations.

| Activity | Conservation Measures |
|------------------------------|---|
| Development Planning | Save as many existing on site palms and trees as possible in new development plans. |
| Demolition/Remodeling | Schedule activity from September 1 through March 14 or conduct outdoor survey of building(s) (ledges, etc.) and nearby trees (within 50 m of the building) for yellow-shouldered blackbird nests prior to start date if the development activity is scheduled to occur between March 15 and August 30. Consult with USFWS if a yellow-shouldered blackbird nest is found. |
| Grounds Maintenance | No trimming or cutting of palms and trees between March 15 and August 30 except in an emergency (i.e., downed trees and palms from storms). |
| Building Maintenance | Check for yellow-shouldered blackbird nests prior to any outdoor building maintenance activities between March 15 and August 30. Determine identity of any bird nest found. Notify and consult with USFWS if a yellow-shouldered blackbird nest is found. |
| General Operations | Before moving parked outdoor equipment (e.g., carts, vehicles) check for yellow-shouldered blackbird nests (March 15-August 30). Notify USFWS if a yellow-shouldered blackbird nest is located. |
| Property Sale/Lease | Notify buyer/lessee of all mitigation requirements (see above) and include mitigation with all legal documents. |

NOTICE:

Consult with the U.S. Fish and Wildlife Service if you have any questions on the conservation measures. Property owners that cannot adhere to the conservation measures must consult with the U.S. Fish and Wildlife Service to seek a Section 10.0 permit for authorization to modify the identified critical habitat. Failure to comply with the identified conservation measures violates Section 9.0 and/or Section 10.0 of the Endangered Species Act. The U.S. Fish and Wildlife Service has the authority to prosecute violations under the Endangered Species Act.

*Parcel Map for the Disposal
of Naval Activity Puerto Rico*


Parcel Index 15

Common Name: Sale
Conveyance: Sale
Neighboring Parcel(s): 5, 8, 13,
14, 16



Legend

-  Parcel
-  Neighboring Parcel Boundaries
- Yellow-shouldered Blackbird
 -  Nesting/Foraging Palms
 -  Breeding Habitat

August 18, 2005



1 inch equals 266 Feet




Parcel Index 15


Common Name: Sale
Conveyance: Sale
Neighboring Parcel(s): 5, 8, 13,
14, 16

| Legend | |
|---|---------------------------------|
|  | Parcel |
|  | Neighboring Parcel Boundaries |
| Cleanup Status | |
|  | Complete with Land Use Controls |
|  | Complete |
|  | Cleanup Remaining |

August 18, 2005



1 inch equals 266 Feet



THREATENED AND ENDANGERED SPECIES CONSERVATION MEASURES—PARCEL 16

Common Name—Sale
Conveyance—Sale
Neighboring Parcel(s)—6, 8, 13, 15, 17, 25

Yellow-shouldered Blackbird

GENERAL REQUIREMENTS


- No development is allowed in Parcel 1 and 5 (Conservation).
- All development related activities (new construction, ground clearing, demolition/remodeling) adjacent to conservation parcels (1, 5) should occur between September 1 and March 15 (non-breeding season) or be restricted to an area 50 m from the parcel boundary from March 15-August 30 (breeding season).
- Notify the U.S. Fish and Wildlife Service (USFWS) if a yellow-shouldered blackbird nest is found anywhere on the property (787-851-7297).
- Pesticide and herbicide applications must follow Commonwealth of Puerto Rico regulations.

| Activity | Conservation Measures |
|----------------------------------|---|
| Development Planning | Save as many existing on site palms and trees as possible in new development plans. |
| New Construction/Clearing | If undeveloped yellow-shouldered blackbird habitat is proposed for clearing consult with USFWS a minimum of one year prior to planned project initiation. |
| Demolition/Remodeling | Schedule activity from September 1 through March 14 or conduct outdoor survey of building(s) (ledges, etc.) and nearby trees (within 50 m of the building) for yellow-shouldered blackbird nests prior to start date if the development activity is scheduled to occur between March 15 and August 30. Consult with USFWS if a yellow-shouldered blackbird nest is found. |
| Grounds Maintenance | No trimming or cutting of palms and trees between March 15 and August 30 except in an emergency (i.e., downed trees and palms from storms). |
| Building Maintenance | Check for yellow-shouldered blackbird nests prior to any outdoor building maintenance activities between March 15 and August 30. Determine identity of any bird nest found. Notify and consult with USFWS if a yellow-shouldered blackbird nest is found. |
| General Operations | Before moving parked outdoor equipment (e.g., carts, vehicles) check for yellow-shouldered blackbird nests (March 15-August 30). Notify USFWS if a yellow-shouldered blackbird nest is located. |
| Property Sale/Lease | Notify buyer/lessee of all mitigation requirements (see above) and include mitigation with all legal documents. |

NOTICE:

Consult with the U.S. Fish and Wildlife Service if you have any questions on the conservation measures. Property owners that cannot adhere to the conservation measures must consult with the U.S. Fish and Wildlife Service to seek a Section 10.0 permit for authorization to modify the identified critical habitat. Failure to comply with the identified conservation measures violates Section 9.0 and/or Section 10.0 of the Endangered Species Act. The U.S. Fish and Wildlife Service has the authority to prosecute violations under the Endangered Species Act.

*Parcel Map for the Disposal
of Naval Activity Puerto Rico*




Parcel Index 16

Common Name: Sale
Conveyance: Sale
Neighboring Parcel(s): 6, 8, 13,
15, 17, 25

| Legend | |
|----------------|---------------------------------|
| | Parcel |
| | Neighboring Parcel Boundaries |
| Cleanup Status | |
| | Complete with Land Use Controls |
| | Complete |
| | Cleanup Remaining |

August 18, 2005



1 inch equals 399 Feet






Exhibit D
Survey Map



SALE PARCEL II A
 17,530,166.2 SQ.FT. OR 402.437 ACRES OR
 1,628,612.3 SQ.MT. OR 414.363 CUERDAS

SALE PARCEL II A
 17,530,166.2 SQ.FT. OR 402.437 ACRES OR
 1,628,612.3 SQ.MT. OR 414.363 CUERDAS

| LINE | LENGTH | BEARING |
|------|--------|-------------|
| L5 | 100.99 | N18°32'14"E |
| L6 | 27.97 | S85°13'10"E |
| L7 | 75.05 | S83°32'22"E |
| L8 | 102.54 | S02°18'52"W |
| L9 | 33.82 | S29°40'44"E |
| L10 | 49.22 | S52°25'45"E |
| L11 | 45.01 | S75°38'56"E |
| L12 | 12.13 | S72°12'52"E |



| | |
|---|-----------------|
| | |
| 150 Bowers Plant Center Norfolk - Virginia - USA, 23510-1628 Phone: 757-243-1113 www.transystems.com | |
| APPROVED | DATE |
| ACTIVITY - SATISFACTORY TO | DATE APPROVED |
| FOR USE FOR CONSUMER PRACTICE | DATE |
| DATE | DESIGNER |
| DATE | DRAWN |
| DATE | CHECKED |
| DATE | IN CHARGE |
| PROJECT NUMBER | PROJECT MANAGER |
| PROJECT LOCATION | DESIGN PROJECT |
| DIVISION ATLANTIC DIVISION NAVAL STATION NAVAL ACTIVITY PUERTO RICO CEIBA, PUERTO RICO UNITED STATES GOVERNMENT PROPERTY FORMER NAVAL STATION ROOSEVELT ROADS SALE PARCEL II A | SHEET 5 OF 7 |

LEGAL DESCRIPTION FOR SALE PARCEL II A

Beginning at a survey control point in the Ward of Guayacan, said point being a brass disk set in concrete. Said point also known as 'DELVIS' and having a northing of 796646.7678 and an easting of 927749.8902 noted as the Point of Beginning on the plat labeled "UNITED STATES GOVERNMENT PROPERTY FORMER NAVAL STATION ROOSEVELT ROADS SALE PARCEL II A". Thence S78°52'34"E 168.01' to an iron rod set, the True Point of Beginning, having a northing of 796614.3537 and an easting of 927914.7410:

Thence N30°14'21"E 293.69' to an iron rod set;
Thence S59°48'07"E 125.93' to an iron rod set;
Thence N72°32'16"E 1288.66' to an iron rod set;
Thence N74°27'25"E 368.85' to an iron rod set;
Thence N82°52'22"E 549.92' to an iron rod set;
Thence S61°50'10"E 134.71' to an iron rod set;
Thence S22°03'47"W 964.43' to an iron rod set;
Thence S26°10'48"W 599.37' to an iron rod set;
Thence N83°59'37"W 552.67' to an iron rod set;
Thence S08°53'31"W 1095.55' to an iron rod set;
Thence S31°33'42"E 191.95' to an iron rod set;
Thence S32°08'22"E 369.47' to an iron rod set;
Thence S55°21'55"E 113.66' to an iron rod set;
Thence N38°20'03"E 320.99' to an iron rod set;
Thence N84°57'17"E 52.20' to an iron rod set;
Thence S57°57'00"E 121.21' to an iron rod set;
Thence S52°41'53"E 85.04' to an iron rod set;
Thence N56°14'39"E 285.03' to an iron rod set;
Thence N07°36'22"W 171.77' to an iron rod set;
Thence N34°34'26"W 439.85' to an iron rod set;
Thence N33°05'48"E 315.39' to an iron rod set;
Thence N74°17'17"E 370.33' to an iron rod set;
Thence N34°27'48"E 342.62' to an iron rod set;
Thence S74°42'52"E 421.32' to an iron rod set;
Thence S71°43'47"E 304.80' to an iron rod set;
Thence S26°34'31"E 108.86' to an iron rod set;
Thence S31°21'54"W 200.39' to an iron rod set;
Thence N87°34'09"W 598.54' to an iron rod set;
Thence S24°04'28"E 568.33' to an iron rod set;
Thence S29°04'14"E 1361.02' to an iron rod set;
Thence S67°01'49"W 288.42' to an iron rod set;
Thence S00°03'09"W 542.55' to an iron rod set;
Thence S75°55'37"W 993.35' to an iron rod set;
Thence S30°47'30"E 382.86' to an iron rod set;
Thence S75°57'53"W 662.53' to an iron rod set;
Thence following a curve to an iron rod set; with a long chord of 118.97', a chord bearing of S13°32'47"E,
 Radius= 849.14'
 Arc=119.07'
Thence S09°31'46"E 282.37' to an iron rod set;
Thence following a curve to an iron rod set; with a long chord of 294.29', a chord bearing of S40°30'35"E,
 Radius= 285.86'
 Arc=309.13'
Thence N18°32'14"E 100.99' to an iron rod set;
Thence S85°13'10"E 27.97' to an iron rod set;

Thence S63°37'29"E 75.85' to an iron rod set;
Thence N86°01'31"E 190.34' to an iron rod set;
Thence S02°38'57"W 102.54' to an iron rod set;
Thence S29°40'44"E 33.82' to an iron rod set;
Thence N84°48'02"E 151.40' to an iron rod set;
Thence following a curve to an iron rod set; with a long chord of 241.06', a chord bearing of S70°36'19"E,

Radius= 289.61'

Arc=248.63'

Thence following a curve to an iron rod set; with a long chord of 530.38', a chord bearing of N84°01'47"E,

Radius= 346.39'

Arc=604.07'

Thence S55°55'45"E 49.22' to an iron rod set;

Thence S75°35'56"E 45.01' to an iron rod set;

Thence S75°35'56"E 12.13' to a point not set at the approximate edge of water of Ensenada Honda;

Thence South along the approximate edge of water of Ensenada Honda to an iron rod set having a northing of 791042.2146 and an easting of 931277.3202;

Thence N50°46'20"W 41.29' to an iron rod set;

Thence S72°51'34"W 246.04' to an iron rod set;

Thence S39°58'07"W 213.05' to an iron rod set;

Thence S16°11'23"W 131.78' to an iron rod set;

Thence S15°08'29"E 188.74' to an iron rod set;

Thence S04°39'50"E 252.60' to an iron rod set;

Thence S25°28'22"W 155.74' to an iron rod set;

Thence S36°13'57"E 93.83' to an iron rod set;

Thence S75°07'17"E 147.17' to an iron rod set;

Thence S54°12'38"E 196.35' to an iron rod set;

Thence S38°58'48"E 73.05' to an iron rod set;

Thence N62°43'26"E 43.54' to an iron rod set on the approximate edge of water of Ensenada Honda;

Thence Southeast along the approximate edge of water of Ensenada Honda;

Thence West along the approximate edge of water of Ensenada Honda;

Thence Southwest along the approximate edge of water of Ensenada Honda;

Thence Northwest along the approximate edge of water of Ensenada Honda to an iron rod set having a northing of 789987.0329 and an easting of 928624.5970;

Thence N33°49'58"E 147.58' to an iron rod set;

Thence N18°59'26"E 428.38' to an iron rod set;

Thence N19°29'17"E 152.84' to an iron rod set;

Thence N27°35'05"E 129.36' to an iron rod set;

Thence N59°07'38"W 128.07' to an iron rod set;

Thence N02°18'32"E 102.65' to an iron rod set;

Thence N52°52'48"W 47.94' to an iron rod set;

Thence N37°21'10"W 444.05' to an iron rod set;

Thence N20°16'57"W 69.58' to an iron rod set;

Thence N14°16'15"E 143.46' to an iron rod set;

Thence N03°18'13"W 222.24' to an iron rod set;

Thence S64°17'45"W 49.06' to an iron rod set;

Thence S30°25'00"W 86.93' to an iron rod set;

Thence S46°32'39"W 270.16' to an iron rod set;

Thence S86°09'24"W 107.23' to an iron rod set;

Thence N72°55'21"W 216.16' to an iron rod set;

Thence N36°01'23"W 145.33' to an iron rod set;

Thence N00°38'19"W 228.13' to an iron rod set;

Thence N22°32'18"E 188.66' to an iron rod set;

Thence N14°36'26"W 271.50' to an iron rod set;
Thence N70°04'01"W 817.68' to an iron rod set;
Thence N32°00'57"E 476.26' to an iron rod set;
Thence N28°46'50"E 376.98' to an iron rod set;
Thence N02°48'57"W 255.62' to an iron rod set;
Thence N35°21'48"E 166.29' to an iron rod set;
Thence N26°49'10"E 179.97' to an iron rod set;
Thence N70°58'06"W 132.88' to an iron rod set;
Thence N34°06'09"W 116.68' to an iron rod set;
Thence N03°28'14"E 162.01' to an iron rod set;
Thence N24°25'54"E 158.18' to an iron rod set;
Thence N68°44'45"E 156.42' to an iron rod set;
Thence N09°21'33"W 203.14' to an iron rod set;
Thence N44°54'44"E 185.85' to an iron rod set;
Thence N88°04'12"E 174.03' to an iron rod set;
Thence S71°43'46"E 46.11' to an iron rod set;
Thence S48°12'02"E 100.29' to an iron rod set;
Thence S34°04'11"E 219.49' to an iron rod set;
Thence S71°39'50"E 278.41' to an iron rod set;
Thence S38°39'51"E 182.04' to an iron rod set;
Thence N72°03'33"E 437.50' to an iron rod set;
Thence N47°27'11"W 627.34' to an iron rod set;
Thence N40°53'33"W 308.83' to an iron rod set;
Thence N09°24'38"E 492.22' to an iron rod set;
Thence N88°42'04"E 164.09' to an iron rod set;
Thence N06°33'51"E 232.33' to an iron rod set;
Thence N06°35'07"W 36.56' to an iron rod set;
Thence N45°15'31"W 29.84' to an iron rod set;
Thence N52°30'55"W 383.91' to an iron rod set;
Thence N39°44'38"E 324.94' to an iron rod set;
Thence N17°59'43"E 176.84' to an iron rod set;
Thence N75°02'51"W 675.18' to an iron rod set, the True Point of Beginning.

Said parcel containing 17,530,166.2 square feet or 402.437 acres, which equates to 1,628,612.3 square meters or 414.363 cuerdas.

Said parcel is subject to the following easements as shown on plats titled "UNITED STATES GOVERNMENT PROPERTY FORMER NAVAL STATION ROOSEVELT ROADS EASEMENT 13" and "UNITED STATES GOVERNMENT PROPERTY FORMER NAVAL STATION ROOSEVELT ROADS EASEMENT 14" prepared by TranSystems Corporation and sealed by Luis Berrios Montes on XX, 2007.

SURVEY NOTES:



- BOUNDARY SURVEY PREPARED BY TRANSYSTEMS CORPORATION FROM FIELD DATA COLLECTED IN SEPTEMBER & DECEMBER 2006. FIELD PROCEDURES, CALCULATIONS AND FINAL PLAT HAVE BEEN REVIEWED FOR CONTENT BY LUIS BERRIOS MONTES & ASSOCIATES OF VEGA RUA, PUERTO RICO.
- HORIZONTAL COORDINATES SHOWN HEREON ARE IN FEET AND REFER TO THE PUERTO RICO/IRGIN ISLAND STATE PLANE COORDINATE SYSTEM, NAD 83 (1997 ADJUSTMENT). HORIZONTAL COORDINATES WERE DERIVED USING DUAL FREQUENCY GPS RECEIVERS AND ARE REFERENCED TO NATIONAL GEODETIC SURVEY MONUMENTS ANGEL (PID A059977), FAJARDO (PID A09834), HUMACAD 2 (PID A09849) AND MT. BRITTON (PID A09835).
- THE FOLLOWING PLATS AND DEEDS WERE USED TO ESTABLISH THE BOUNDARY LINES AS SHOWN ON THIS PLAT:
 - PLAT TITLED "UNITED STATES GOVERNMENT PROPERTY FORMER NAVAL STATION ROOSEVELT ROADS BOUNDARY REESTABLISHMENT SURVEY" PREPARED BY TRANSYSTEMS CORPORATION AND LUIS BERRIOS MONTES. NAVFAC DRAWING No. 4522929; DATED FEBRUARY 15, 2005.
- PLANIMETRIC DATA AND SHORELINE PROVIDED BY HOGGARD EURE ASSOCIATES PORTSMOUTH, VA. AERIAL SURVEY PERFORMED BY: AERO-DYNAMICS CORPORATION CHARLOTTE N.C. SURVEY FLOWN FEBRUARY 1998.
- DUE TO THE SPECIALIZED USAGE OF THE SUBJECT PROPERTY, TERRESTRIAL-MARITIME REGULATIONS ARE INAPPLICABLE, AS A SINE QUA NON CONDITION. ALL FUTURE RECIPIENTS OF THIS SUBJECT PROPERTY BY SUBDIVISION, SHALL RECOGNIZE THE BOUNDARY OF THESE LANDS WITH REGARDS TO THE TERRESTRIAL-MARITIME ZONE REGULATIONS. THE PUBLIC ACCESS TO PROPERTY TRANSFERRED TO OTHER FEDERAL AGENCIES SHALL REMAIN STATUS QUIDO.
- NOTE: THIS PLAT SHOWS EASEMENTS OF RECORD FOUND IN THE NAVY REAL ESTATE OFFICE. THIS PLAT MAY NOT SHOW ALL GRANTS OR EASEMENTS THAT COULD AFFECT SUBJECT PROPERTY.

LEGEND

- CONCRETE MONUMENT FOUND
- IRON ROD SET
- PROPERTY LINE
- EASEMENT LINE

| LINE | LENGTH | BEARING |
|------|--------|-------------|
| L1 | 72.71 | S76°11'44"W |
| L2 | 86.69 | S52°28'03"E |
| L9 | 254.40 | N17°28'49"E |
| L10 | 46.37 | N82°52'44"E |
| L11 | 48.91 | N52°08'34"E |

SALE PARCEL II B
 4,124,358.8 SQ. FT. OR 94.682 ACRES OR
 383,167.0 SQ. MT. OR 97.488 CUERDAS



CERTIFICATION

I, LUIS BERRIOS MONTES, CERTIFY THAT THE INFORMATION THAT FOLLOWS REPRESENTS FAITHFULLY WHAT I FOUND PHYSICALLY ON THE GROUND AND/OR BY THE INVESTIGATIONS THAT HAD BEEN MADE BY ME.

Date: 3/12/07

LUIS BERRIOS MONTES
 Surveyor License No. 8089

LUIS BERRIOS MONTES
 Agrimensor Lic. No. 8089
 Calle: P.O. Box 154-1524, Humacá 011-2005
 T. 0. (787) 785-5425
 F. 0. (787) 744-7447, T. 8.

1"=100' 0' 100' 200' 300' 400' 500'

| | |
|------------------|----------------|
| DATE | 1/15/07 |
| SCALE | AS NOTED |
| PROJECT NO. | NAVFAC 4522929 |
| DRAWN BY | LSM |
| CHECKED BY | LSM |
| DATE | 1/15/07 |
| PROJECT MANAGER | LSM |
| PREPARED BY | LSM |
| REVISION MANAGER | LSM |
| DESIGN DIRECTOR | LSM |

TransSystems
 150 Beach Street - Suite 1008
 Miraflores - San Juan - P.R. 00907-1113
 Phone: 787-744-7447
 Email: www.transystems.com

APPROVED: _____
 AUTHORITY: SUBORDINARY TO _____
 DATE: _____
 APPROVED: _____
 FOR USE FOR OWNERSHIP: _____
 DATE: _____
 AVE: _____ LTD: _____
 ECEM: _____
 DRAW: _____
 REVIEW: _____
 BY: _____
 CHECK: _____
 PROJECT MANAGER: _____
 PREPARED BY: _____
 REVISION MANAGER: _____
 DESIGN DIRECTOR: _____

ATLANTIC DIVISION
 NAVAL ACTIVITY PUERTO RICO
 CEIBA, PUERTO RICO
 UNITED STATES GOVERNMENT PROPERTY
 FORMER NAVAL STATION ROOSEVELT ROADS
SALE PARCEL II B

| | |
|------------------|----------------|
| CODE & NO. BOOK | DATE |
| SCALE | AS NOTED |
| DATE | 1/15/07 |
| PROJECT NO. | NAVFAC 4522929 |
| DRAWN BY | LSM |
| CHECKED BY | LSM |
| DATE | 1/15/07 |
| PROJECT MANAGER | LSM |
| PREPARED BY | LSM |
| REVISION MANAGER | LSM |
| DESIGN DIRECTOR | LSM |

LEGAL DESCRIPTION FOR SALE PARCEL II B

Beginning at a survey control point in the Ward of Guayacan, said point being a brass disk set in concrete. Said point also known as 'CASCAJO' and having a northing of 792718.7899 and an easting of 935655.9464 noted as the Point of Beginning on the plat labeled "UNITED STATES GOVERNMENT PROPERTY FORMER NAVAL STATION ROOSEVELT ROADS SALE PARCEL II B". Thence S00°09'52"E 191.46' to an iron rod set on the approximate edge of water of Ensenada Honda, the True Point of Beginning, having a northing of 792527.3349 and an easting of 935656.4956:

Thence S78°11'44"W 72.71' to an iron rod set;

Thence S39°17'10"W 197.50' to an iron rod set;

Thence S08°35'07"W 554.83' to an iron rod set;

Thence S56°28'03"E 86.69' to an iron rod set on the approximate edge of water of Ensenada Honda having a northing of 791763.1020 and an easting of 935449.7085;

Thence Southwest along the approximate edge of water of Vieques Passage;

Thence West along the approximate edge of water of Vieques Passage;

Thence North along the approximate edge of water to an iron rod set having a northing of 790646.4126 and an easting of 933016.8045

Thence S88°04'00"E 176.63' to an iron rod set

Thence N63°47'43"E 121.99' to an iron rod set;

Thence N80°58'39"E 153.66' to an iron rod set;

Thence N14°40'48"W 230.17' to an iron rod set;

Thence N87°12'00"W 269.55' to an iron rod set;

Thence N27°02'40"W 182.08' to an iron rod set;

Thence N20°29'37"W 194.61' to an iron rod set;

Thence N20°19'37"W 302.30' to an iron rod set;

Thence following a curve to an iron rod set; with a long chord of 136.56', a chord bearing of N23°36'05"W,

Radius= 1195.39'

Arc=136.64'

Thence N26°52'33"W 259.49' to an iron rod set;

Thence following a curve to an iron rod set; with a long chord of 230.12', a chord bearing of N34°09' 10"W,

Radius= 908.39'

Arc=230.74'

Thence N48°34'14"E 49.22' to an iron rod set;

Thence N48°34'14"E 55.09' to an iron rod set;

Thence N17°43'35"E 80.21' to an iron rod set;

Thence N48°47'03"E 102.45' to an iron rod set;

Thence N71°08'08"E 97.48' to an iron rod set;

Thence N71°08'08"E 33.22' to a point not set on the approximate edge of water of Ensenada Honda having a northing of 792384.4126 and an easting of 932873.2568;

Thence Southeast along the approximate edge of water of Ensenada Honda to an iron rod set having a northing of 791812.7113 and an easting of 933338.2827;

Thence S45°58'22"W 97.06' to an iron rod set;

Thence S48°49'44"W 93.85' to an iron rod set;

Thence S58°41'06"W 138.43' to an iron rod set;

Thence S18°28'24"E 268.60' to an iron rod set;

Thence S74°04'45"E 425.18' to an iron rod set;

Thence N17°26'49"E 254.40' to an iron rod set;

Thence N56°30'28"E 110.37' to an iron rod set;

Thence N07°44'44"E 276.03' to an iron rod set;

Thence N36°34'58"E 234.19' to an iron rod set;

Thence N55°30'53"E 337.29' to an iron rod set;

Thence N68°31'23"E 538.98' to an iron rod set;

Thence N03°56'03"E 232.44' to an iron rod set;

Thence N47°51'06"E 344.84' to an iron rod set;
Thence N57°17'07"E 199.60' to an iron rod set;
Thence S21°52'30"E 192.18' to an iron rod set;
Thence S79°06'21"E 190.07' to an iron rod set;
Thence N85°42'44"E 46.37' to an iron rod set;
Thence N58°08'36"E 48.91' to an iron rod set on the approximate edge of water of Ensenada Honda;
Thence East along the approximate edge of water of Ensenada Honda;
Thence South along the approximate edge of water of Ensenada Honda to the True Point of Beginning.

Said parcel containing 4,124,358.8 square feet or 94.682 acres, which equates to 383,167.0 square meters or 97.488 cuerdas.

Exhibit E

Tables

TABLE 1

**NAVAL ACTIVITY PUERTO RICO
SALE PARCEL II FOST
NON-HOUSING FACILITIES LIST
PAGE 1 of 2**

| Facility # | Former User | Name | Area | Unit | Yr Built |
|------------|-------------|--------------------------------|-------|------|----------|
| 673 | - | MAINTENANCE STORAGE BLDG | - | - | - |
| 793 | HSG | HOUSING OFFICE | 6400 | SF | 1966 |
| 884 | PWD | SEWAGE PUMP STATION | 280 | SF | 1959 |
| 885 | HSG | TEMP LODGING | 8638 | SF | 1960 |
| 886 | NAVY CAMPUS | NAVY CAMPUS | 7918 | SF | 1960 |
| 888 | HOSP | MEDICAL CLINICS (EIP/MDO) | 10583 | SF | 1960 |
| 968 | PWD | SEWAGE PUMPING STA(CAPEHART) | 280 | SF | 1959 |
| 1022 | - | - | - | - | - |
| 1028 | HSG | SNACK BAR BY HOUSING POOL | 276 | SF | - |
| 1073 | PWD | BUS SHLTR FDR DR (HSG) | 140 | SF | 1962 |
| 1075 | PWD | BUS SHLTR/CASCAJO OFFCRS HSG | 190 | SF | 1962 |
| 1303 | MWR | PLAYING FIELD BASEBALL | - | - | 1961 |
| 1316 | HSG | PLAYGROUND | - | - | - |
| 1469 | MWR | EM SWIM POOL/PUMP/FLTR HSE | 592 | SF | 1960 |
| 1471 | PWD | SEWAGE PUMPING STA CAPEHART | 360 | SF | 1959 |
| 1513 | PWD | SEWAGE LIFT STATION/TOILET | 170 | SF | 1959 |
| 1577 | MWR | BATHROOM-SNACK BAR EM POOL | 1056 | SF | 1962 |
| 1581 | PWD | BUS SHLTR BY COMM CTR | 140 | SF | 1962 |
| 1583 | MWR | OFFICERS SW POOL BATHOUSE | 396 | SF | 1963 |
| 1660 | HSG | YOUTH CENTER | 1800 | SF | - |
| 1698 | PWD | CAPEHART CARPENTRY SHOP | 1600 | SF | 1970 |
| 1746 | AFWTF | LIGHT TOWER CABRAS ISLAND | - | - | - |
| 1755 | HSG | HOUSING MAINTENANCE SHOP | 4000 | SF | 1971 |
| 1756 | HSG | HOUSING STORAGE/WHSE | 8000 | SF | 1974 |
| 1800 | MWR | TENNIS COURT | 1600 | SF | 1974 |
| 1811 | HSG | COMMUNITY CENTER | 5029 | SF | 1977 |
| 1916 | PWD | SEWAGE LIFT/ALGODONES APTS. | 64 | SF | 1978 |
| 1917 | PWD | SEWAGE LIFT/TURNKEY HSG. | 64 | SF | 1978 |
| 1918 | MWR | SOFTBALL FIELD (ALGODONES) | - | - | 1971 |
| 1919 | HSG | PUBLIC TOILET | - | - | - |
| 1920 | PWD | STANDBY GEN BY BLDG #1471 | 224 | SF | 1977 |
| 1923 | - | TOILET NEXT TO PUMP HOUSE 1513 | - | - | - |
| 1924 | PWD | SEWAGE PUMP ST | 64 | SF | 1971 |
| 1940 | PWD | SUBSTA BY FUEL TKS 56A/56B | - | - | 1976 |
| 1942 | MWR | REC GRNDS COMM BEACH | 4256 | SF | 1978 |
| 2170 | MWR | COMMUNITY BEACH HEADS | 390 | SF | 1984 |
| 2200 | ACSS | ACSS HIGH SCHOOL | 10961 | SF | 1960 |
| 2203 | PWD | SWGE LIFT STA BY B# 1811 | - | - | 1987 |
| 2221 | MWR | MALE/FEM HEAD AT BALLFIELD | 75 | SF | 1986 |
| 2223 | MWR | COMM. BEACH BALLFLD B&DUGOUT | - | - | 1986 |

TABLE 1

NAVAL ACTIVITY PUERTO RICO
SALE PARCEL II FOST
NON-HOUSING FACILITIES LIST
PAGE 2 of 2

| Facility # | Former User | Name | Area | Unit | Yr Built |
|------------|-------------|----------------------------|------|------|----------|
| 2237 | MWR | CONCESS STGECOM BCH BALLFL | 144 | SF | 1986 |
| 2251 | MWR | ADDTNL STGE B1811 | 336 | SF | 1987 |
| 2295 | ACSS | ACSS HIGH SCHOOL GYM | - | - | 1960 |
| 2305 | MWR | YOUTH CENTER | 7611 | SF | 1990 |
| 2378 | MWR | SWIM POOL FILTER HOSE | 144 | SF | 1978 |
| 2382 | PWD | SWGE PUMP STATION | 450 | SF | 1995 |

List based on 2003 NAPR base map (Base map - PREnew 11-2003.pdf), July 2001 Building Utilization List, List of Buildings To Be Inspected For Asbestos from June 2005 Asbestos Inspection Report, and field verification by NAPR personnel.

- Information not available or unknown

ACSS Antilles Consolidated School System
AFWTF Atlantic Fleet Weapons Training Facility
HOSP Hospital
HSG Housing
MWR Morale, Welfare and Recreation
PWD Public Works Department

TABLE 2

**NAVAL ACTIVITY PUERTO RICO
SALE II PARCEL FOST
AST AND UST LIST**

| Number | Type | Location or User | Capacity | Material Stored | Year Installed | Year Removed |
|---------------|---------------|-------------------------|-----------------|------------------------|-----------------------|---------------------|
| 1920 | AST (Vaulted) | PWD | 500 | Diesel | - | Active |
| 1972 | AST (Vaulted) | PWD | 250 | Diesel | - | Active |
| 2406 | AST (Vaulted) | PWD | 550 | Diesel | - | Active |
| 1513 | Former UST | 1513/PWD | 280 | Diesel | - | 1996 |

- Information not available or unknown

TABLE 3

**NAVAL ACTIVITY PUERTO RICO
SALE PARCEL II FOST
NON-HOUSING ASBESTOS-CONTAINING MATERIAL INSPECTION RESULTS**

| Facility # | Name | ACM Identified | Comments |
|------------|--------------------------------|----------------|------------|
| 673 | MAINTENANCE STORAGE BLDG | NI | |
| 793 | HOUSING OFFICE | Y | No FAD ACM |
| 884 | SEWAGE PUMP STATION | N | |
| 885 | TEMP LODGING | Y | No FAD ACM |
| 886 | NAVY CAMPUS | N | |
| 888 | MEDICAL CLINICS (EIP/MDO) | Y | No FAD ACM |
| 968 | SEWAGE PUMPING STA(CAPEHART) | Y | No FAD ACM |
| 1022 | - | NI | |
| 1028 | SNACK BAR BY HOUSING POOL | NI | |
| 1073 | BUS SHLTR FDR DR (HSG) | N | |
| 1075 | BUS SHLTR/CASCAJO OFFCRS HSG | N | |
| 1303 | PLAYING FIELD BASEBALL | NI | |
| 1316 | PLAYGROUND | NI | |
| 1469 | EM SWIM POOL/PUMP/FLTR HSE | NI | |
| 1471 | SEWAGE PUMPING STA CAPEHART | N | |
| 1513 | SEWAGE LIFT STATION/TOILET | NI | |
| 1577 | BATHROOM-SNACK BAR EM POOL | N | |
| 1581 | BUS SHLTR BY COMM CTR | N | |
| 1583 | OFFICERS SW POOL BATHOUSE | N | |
| 1660 | YOUTH CENTER | NI | |
| 1698 | CAPEHART CARPENTRY SHOP | N | |
| 1746 | LIGHT TOWER CABRAS ISLAND | NI | |
| 1755 | HOUSING MAINTENANCE SHOP | Y | No FAD ACM |
| 1756 | HOUSING STORAGE/WHSE | N | |
| 1800 | TENNIS COURT | NI | |
| 1811 | COMMUNITY CENTER | Y | No FAD ACM |
| 1916 | SEWAGE LIFT/ALGODONES APTS. | N | |
| 1917 | SEWAGE LIFT/TURNKEY HSG. | N | |
| 1918 | SOFTBALL FIELD (ALGODONES) | NI | |
| 1919 | PUBLIC TOILET | NI | |
| 1920 | STANDBY GEN BY BLDG #1471 | N | |
| 1923 | TOILET NEXT TO PUMP HOUSE 1513 | NI | |
| 1924 | SEWAGE PUMP ST | N | |
| 1940 | SUBSTA BY FUEL TKS 56A/56B | NI | |
| 1942 | REC GRNDS COMM BEACH | NI | |
| 2170 | COMMUNITY BEACH HEADS | N | |
| 2200 | ACSS HIGH SCHOOL | NI | |
| 2203 | SWGE LIFT STA BY B# 1811 | NI | |
| 2221 | MALE/FEM HEAD AT BALLFIELD | N | |
| 2223 | COMM. BEACH BALLFLD B&DUGOUT | NI | |
| 2237 | CONCESS STGECOM BCH BALLFL | N | |
| 2251 | ADDTNL STGE B1811 | N | |
| 2295 | ACSS HIGH SCHOOL GYM | NI | |
| 2305 | YOUTH CENTER | N | |
| 2378 | SWIM POOL FILTER HOSE | NI | |
| 2382 | SWGE PUMP STATION | N | |

Notes: Y = Yes
N = No
NI = Not Inspected
Hazard = friable, accessible and damaged (FAD) asbestos-containing material (ACM)

Source: Final Asbestos Inspection Report for Naval Activity Puerto Rico, Ceiba, Puerto Rico (Baker, June 2005)

Exhibit F
CERFA Concurrence

**CERFA Identification of Uncontaminated Property
Former Naval Station Roosevelt Roads, Puerto Rico**


Accordingly, this CERFA Uncontaminated Property Report reflects final site categorizations that may differ from those presented in the Final ECP report.

In summary, all NAPR property not otherwise identified as sites belonging to Categories 2 or 3 are classified as "CERFA Clean" (i.e. uncontaminated) as defined in CERFA [§9620 (h)(4)(A)]. The bulk of the NAPR acreage is classified as such. Of the approximately 8,400 acres of NSRR property, about 7,000 acres have been identified as "CERFA Clean" (i.e., Category 1). Figure 1 depicts the results of this classification.

Included in the CERFA Clean classification are a total of 14 SWMUs. Ten of these SWMUs were identified by EPA in the 1994 RCRA Part B permit, and an additional four sites were identified by the ECP. All 14 of these sites were originally identified based on a suspected release or disposal activity, but subsequent investigations determined that no release or disposal activity occurred. EPA has indicated their concurrence with this determination in the draft §7003 Order on Consent by designating each of these sites as having achieved "corrective action complete without controls" designation. The SWMUs and ECP sites designated as CERFA Clean are SWMUs 5, 15, 20, 21, 22, 47, 48, 49, 50, 52, 63 (ECP 9), 64 (ECP 10), 65 (ECP 11), and 66 (ECP 12). These sites are presented in Table 1.

The remaining property has been classified as Category 2 or 3 and as such is not qualified for designation as CERFA Clean.

Submitted




R. DAVID CRISWELL, P. E.
BRAC Environmental Coordinator

8/27/06
Date

Concurrence

Concurrence with CERFA Identification of Uncontaminated Property is indicated by signature below. This concurrence applies only to the identification of "CERFA Clean" (i.e. uncontaminated) property, identified in this document as ECP Category 1.



Carlos Lopez Freytes, President
Environmental Quality Board
Commonwealth of Puerto Rico


8/11/06
Date

Exhibit G

**Asbestos Inspection Reports
and
Lead-Based Paint Inspection/Risk Assessment Report**

Final
Asbestos Inspection Report
for
Military Family Housing
Naval Activity Puerto Rico
Ceiba, Puerto Rico

Contract N62472-01-D-1440 • Project Number 15 • June 2005



Prepared by
Michael Baker Jr., Inc.

Baker

Challenge Us.

Under Contract with
Department of the Navy
Naval Facilities Engineering Command
Engineering Field Activity, Northeast



TABLE OF CONTENTS

| | <u>Page</u> |
|--|-------------|
| EXECUTIVE SUMMARY..... | ES-1 |
| 1.0 INTRODUCTION..... | 1 |
| 1.1 Housing Community Overview | 2 |
| 2.0 ASBESTOS-CONTAINING MATERIAL INSPECTION | 5 |
| 2.1 Regulatory Background | 5 |
| 2.2 Methodology | 6 |
| 2.3 Selecting Units for Inspections | 7 |
| 2.4 Disclaimer | 11 |
| 2.5 Summary of Asbestos-Containing Materials | 12 |
| 2.6 Summary of Hazards | 22 |

LIST OF TABLES

Within Text

| | |
|---------|---|
| Table A | Renovation History for NAPR Housing |
| Table B | ACMs Identified at NAPR Housing |
| Table C | Renovation History for NAPR Housing |
| Table D | Units Selected for ACM Inspection at NAPR Housing |
| Table E | ACMs Identified at NAPR Housing |
| Table F | ACMs Identified by Address for Algodones |
| Table G | ACMs Identified by Address for Caribe Breeze |
| Table H | ACMs Identified by Address for Cascajo Point |
| Table I | ACMs Identified by Address for Coast Guard |
| Table J | ACMs Identified by Address for FDR Drive |
| Table K | ACMs Identified by Address for Manatee Bay |
| Table L | ACMs Identified by Address for Mangrove Manor |

Following Text

| | |
|---------|---|
| Table 1 | Summary of Homogeneous Materials (for each housing community) |
| Table 2 | Summary of Identified ACM (for each housing community) |

LIST OF APPENDICES

| | |
|------------|---|
| Appendix A | Training Certificates and Certificates of Accreditation |
| Appendix B | NAPR Map and Floor Plans |
| Appendix C | Analytical Laboratory Reports |
| Appendix D | Photographs |

EXECUTIVE SUMMARY

The US Navy Engineering Field Activity Northeast (EFANE) contracted Baker to perform an asbestos-containing material (ACM) inspection of military family housing at Naval Activity Puerto Rico (NAPR), located near Ceiba, Puerto Rico. The work was performed so that the federal government can transfer the properties. The Navy is considered the owner of all properties referenced in this report. The work was performed in accordance with the Scope of Work: Lead-Based Paint Inspection and Risk Assessment, and Asbestos Survey for Residential Property Transfer, dated September 9, 2004, under Contract Number N62472-01-D-1440. Field work for the project was performed from January 5, 2005 to February 11, 2005.

NAPR housing was reportedly constructed between 1960 and 1975 and contains 962 two, three, and four-bedroom apartment style, duplex, and single-family housing units. NAPR housing consists of eight communities: Algodones, Caribe Breeze, Cascajo Point, Coast Guard, FDR Drive, Manatee Bay, Mangrove Manor, and Rainbow Hill. Twenty-seven of the housing units in Manatee Bay are of original construction, while the remaining 935 units were renovated to varying degrees beginning in 1989. The square footage of the units ranges from 1023 to 2105 square feet. The concrete-framed buildings have concrete or ceramic exterior finishes. Interior walls are painted gypsum board and concrete. The units are generally in good condition.

Table A below summarizes the renovation history for the communities, as provided by the housing office manager.

| Table A. Renovation History for NAPR Housing | | | | |
|---|--|-----------------------|--------------------------|--|
| Address of Units Inspected | Style of Housing | Date of Const. | Date(s) of Renov. | Description of Renovation |
| Algodones | | | | |
| 889C, 889E, 889F, 889G, 889H, 891A, 891D, 893B, 893C, 895A, 895B, 895C, 897A, 897B, 897D, 897F, 897G, 897H, and 899B | Two, Three, and Four Bedroom Apartment-Style Units | 1960 | 1991 | <ul style="list-style-type: none"> ● Installation of carpeting ● Remodel bathrooms and kitchens ● Replace doors and windows |
| Caribe Breeze | | | | |
| 1A, 2C, 5B, 6B, 10D, 11A, 15A, 16B, 17C, 20A, 20B, 21B, 25C, 25A, 28A, 31B, 34B, 35A, 37A, 38B, 39C, 43B, and 47A American Circle 92A Saratoga Road 1B and 4B Point Cruz | Two, Three, and Four Bedroom Duplex Units | 1974 | 2001 - 2003 | <ul style="list-style-type: none"> ● Remove LBP and ACM ● Repaint all walls inside and outside ● Replace vinyl floor tile with ceramic tile ● Replace A/C ductwork and central A/C units ● Upgrade electrical systems ● Replace entrance doors ● Reconfigure outside storage areas and A/C mechanical rooms ● Replace kitchen cabinets ● Replace bathroom fixtures and tiles ● Reconfigure master bedrooms and bathroom ● Replace windows ● Install ceiling fans <p>Replace carpeting in upstairs of 2-bedroom units</p> |
| Cascado Point | | | | |
| 6, 11, 16, 21, 24, 30, and 31 FDR Drive 6 Bataan Drive 5 and 14 San Jacinto Road 4, 7, and 13 Cowrens Drive 4, 5, 13, 14, 19, 26, 29, 30, and 43 Monterey Road 2, 5, 12, and 14 Cabot Lake | Two, Three and Four Bedroom Single Family Houses | 1960 | 1998 - 2001 | <ul style="list-style-type: none"> ● Remove LBP and ACM ● Construct screened-in porches ● Repaint all walls inside and outside ● Replace vinyl floor tile with ceramic tile ● Replace A/C ductwork and central A/C units ● Upgrade electrical systems ● Replace kitchen cabinets ● Remodel laundry areas ● Replace bathroom fixtures and tiles ● Reconfigure master bedrooms and bathroom ● Install ceiling fans |
| Coast Guard | | | | |
| 1675, 1676, 1677, 1678, 1679, and 1680 Intrepid Street | Three and Four Bedroom Single Family Houses | 1960 | 1989 - 1992 | <ul style="list-style-type: none"> ● Replace floors tiles ● Replace kitchen cabinets ● Install central A/C ● Replace aluminum jealousy windows with French type glass louvered windows |

| Table A. Renovation History for NAPR Housing | | | | |
|--|---|----------------|-------------------|--|
| Address of Units Inspected | Style of Housing | Date of Const. | Date(s) of Renov. | Description of Renovation |
| FDR Drive | | | | |
| 1, 3, and 5 FDR Drive | Three Bedroom Single Family Houses | 1960 | 1999 - 2000 | <ul style="list-style-type: none"> ● Remove LBP and ACM ● Replace carpeting ● Repaint all walls inside and outside ● Replace A/C ductwork ● Reconfigure mechanical room ● Upgrade electrical systems ● Replace kitchen floors and cabinets ● Remodel bathrooms including replace bathroom fixtures (not 1 FDR) ● Install ceiling fans |
| Manatee Bay | | | | |
| 6 and 7 Intrepid Street 8, 11, 20, 36, 38, 49, 52, and 60 Ranger Road 2 and 20 Hancock Circle 4 and 15 Coral Sea Drive 3 and 18 Franklin Drive 8, 19, and 26 Hornet Road 3, 11, 21, 32, and 35 Yorktown Circle 67, 74, and 81 Lexington Drive | Two, Three and Four Bedroom Single Family Houses | 1960 | 2001 - 2003 | <ul style="list-style-type: none"> ● Remove LBP and ACM ● Construct screened-in porches ● Repaint all walls inside and outside ● Replace vinyl floor tile with ceramic tile ● Replace A/C ductwork and central A/C units ● Upgrade electrical systems ● Reconfigure kitchens and replace kitchen cabinets ● Remodel laundry areas ● Replace bathroom fixtures and tiles ● Reconfigure master bedrooms and bathroom ● Install ceiling fans |
| Mangrove Manor | | | | |
| 11, 12, 19, 20, 31, 38, 50, 68, and 82 Saratoga Road 2, 11, and 17 Essex Drive 6 Ticonderoga Street 18, 25, 34, 41, and 54 Enterprise Drive 9, 26, 33, 46, and 47 Lexington Drive 6, 15, and 32 Wasp Circle 7 Bunker Hill Road | Two, Three and Four Bedroom Single Family Houses | 1960 | 1989 - 1992 | <ul style="list-style-type: none"> ● Same as Coast Guard |
| Rainbow Hill | | | | |
| 2A, 4A, 4B, 5B, 7A, 8A, 10C, 13B, 14B, 15B, 16A, 18A, 19C, 20B, 22B, 23A, 24A, 27A, 28B, 29B, 32A, 33B, 34A, and 36A Nimitz Drive | Two, Three, and Four Bedroom Duplex and Apartment-Style Units | 1975 | 1998 - 2001 | <ul style="list-style-type: none"> ● Same as Caribe Breeze |

Base Realignment and Closure (BRAC) policy considers ACM to be a hazard when it meets all three of the following conditions: friable, accessible, and damaged. ACM hazards were not identified in the housing units that were inspected. Per the Scope of Work, Baker did not conduct walk-through inspections of all units of NAPR housing to identify ACMs and ACM hazards. Therefore, additional ACMs and ACM hazards may be present in NAPR housing. Table B below summarizes the ACMs that were identified at each housing community. No ACMs were identified at Rainbow Hill.

| Table B. ACMs Identified at NAPR Housing | | |
|--|--|--|
| Material | Location | Approximate Percent of Units with ACMs* |
| Algodones | | |
| Vinyl Floor Tile, 9" x 9" tan with brown streaks | LR/ DR, Hall 1, BR1, BR2, and BR3 | 47% |
| Floor Adhesive, under 9" x 9" tan with brown streaks vinyl floor tile | LR/ DR, Hall 1, BR1, BR2, and BR3 | 47% |
| Vinyl Floor Tile, 9" x 9" gray with black streaks | BR1 and BR2 | 42% |
| Floor Adhesive, under 9" x 9" gray with black streaks vinyl floor tile | BR1 and BR2 | 42% |
| Caribe Breeze | | |
| Tan/Black Floor Adhesive, under 1' x 1' tan mottled vinyl floor tile | BR1, BR2, BR3, BR4, ST2, ST3, Hall 1, Hall 2, Stair, Laundry, Kitchen, LR/DR | 43% |
| Yellow/Black Floor Adhesive, under 1' x 1' gray mottled vinyl floor tile | BR1, BR2, BR3, BR4, ST2, ST3, Hall 1, Hall 2, Stair, Laundry, Kitchen, LR/DR | 57% |
| Cascajo Point | | |
| Yellow/Black Floor Adhesive, under 1' x 1' tan mottled vinyl floor tile | BR1, BR2, BR3, BR4, LR, DR, LR-P, Hall, Laundry, and Kitchen | 100% |
| Coast Guard | | |
| Black Floor Adhesive, under 1' x 1' brown with white and red streaks vinyl floor tile | LR, DR, Kitchen, Hall, BR1, BR2, BR3, and BR4 | 66% |
| FDR Drive | | |
| Floor Adhesive, under 1' x 1' brown with red streaks vinyl floor tile | LR/DR | 33% |
| Vinyl Floor Tile, 9" x 9" gray with white streaks | BR1, BR2, BR3, Hall, and LR/DR | 66% |
| Floor Adhesive, under 9" x 9" gray with white streaks vinyl floor tile | BR1, BR2, BR3, Hall, and LR/DR | 66% |
| Floor Adhesive, under 1' x 1' tan mottled vinyl floor tile | BR1, BR2, BR3, and Hall | 33% |
| Vinyl Floor Tile, 1' x 1' brown with tan streaks | LR/DR | 33% |
| Manatee Bay | | |
| Vinyl Floor Tile, 1' x 1' yellow mottled | LR, DR, Kitchen, Hall, BR1, BR2, and BR3 | 3% |
| Black Floor Adhesive, under 1' x 1' yellow mottled and 1' x 1' brown with orange and white stripes vinyl floor tiles | LR, DR, Kitchen, Hall, BR1, BR2, and BR3 | 7% |
| Mangrove Manor | | |
| Vinyl Floor Tile, 1' x 1' brown mottled | LR, DR, Kitchen, Hall, BR1, BR2, BR3, and BR4 | 33% |
| Black Floor Adhesive, under 1' x 1' brown mottled, 1' x 1' white with brown streaks, 1' x 1' light brown mottled, 1' x 1' brown with light brown streaks, 1' x 1' brown with white streaks, 1' x 1' white with gray specks, and 1' x 1' white with black streaks vinyl floor tiles | LR, DR, Kitchen, Hall, BR1, BR2, BR3, and BR4 | 88% |
| Vinyl Floor Tile, 1' x 1' brown with light brown streaks | LR, DR, Kitchen, Hall, BR1, BR2, BR3, and BR4 | 4% |
| Vinyl Floor Tile, 1' x 1' white with black streaks | LR, DR, Kitchen, Hall, BR1, BR2, BR3, and BR4 | 7% |
| Vinyl Floor Tile, 1' x 1' tan mottled | LR, DR, Kitchen, Hall, BR1, BR2, BR3, and BR4 | 7% |
| Black Floor Adhesive, under 1' x 1' tan mottled and 1' x 1' white mottled vinyl floor tiles | LR, DR, Kitchen, Hall, BR1, BR2, BR3, and BR4 | 11% |
| Vinyl Floor Tile, 1' x 1' white mottled | LR, DR, Kitchen, Hall, BR1, BR2, BR3, and BR4 | 4% |
| Sink Coating, black | Kitchen | 96% |

*For NAPR Housing, percentages are based on a representative number of units inspected for ACM; not all units in NAPR Housing were inspected. A complete ACM inspection of all NAPR Housing units is recommended to verify actual quantities and conditions.

If renovation or demolition of housing units is scheduled, a more comprehensive ACM inspection should be conducted to attempt to identify hidden ACM (e.g., behind walls, above ceilings, etc.) that would not have been identified during this non-destructive, baseline study. Also, prior to renovation or demolition, ACM removal and disposal activities must be completed in accordance with EPA, Puerto Rico OSHA, Puerto Rico EQB, and other applicable federal and local regulations.

1.0 INTRODUCTION

The US Navy Engineering Field Activity Northeast (EFANE) contracted Baker to perform an asbestos-containing material (ACM) inspection of military family housing at Naval Activity Puerto Rico (NAPR), located near Cieba, Puerto Rico. The work was performed so that the federal government can transfer the properties. The Navy is considered the owner of all properties referenced in this report. The work was performed in accordance with the Scope of Work: Lead-Based Paint Inspection and Risk Assessment, and Asbestos Survey for Residential Property Transfer, dated September 9, 2004, under Contract Number N62472-01-D-1440. Field work for the project was performed from January 5, 2005 to February 11, 2005.

The body of the report is followed by the following appendices that contain supporting data:

- Appendix A contains copies of training certificates for the Baker and Environmental Development and Sustainability, Inc. (EDS) Baker subcontractor) staff who conducted the investigation and the certificates of accreditation for the laboratories that conducted sample analysis.
- Appendix B contains an NAPR map that shows the location of each of the housing communities and a floor plan for each type of housing unit that was inspected.
- Appendix C contains analytical laboratory reports for bulk material samples.
- Appendix D contains photographs pertinent to the ACM inspection. These photographs are also included on a CD that accompanies this report.

While preparing this report, Baker consulted the following regulations, guidance documents and policies:

- 29 CFR 1926.1101 - OSHA Asbestos Construction Standard
- 40 CFR 763 - Asbestos Hazard Emergency Response Act (AHERA) and Asbestos School Hazard Reauthorization Act (ASHARA) as Amended
- 40 CFR 61, Subpart M – National Emissions Standards for Hazardous Air Pollutants (NESHAPS)

- Puerto Rico Environmental Quality Board Regulation for the Control of Atmospheric Pollution, Rules 102, 422, and 501
- 41 CFR 101-47 – General Services Administration Federal Property Management Regulations: Utilization and Disposal of Real Property
- 15 United States Code 2680, 2681 and 2688 -Toxic Substances Control Act
- Department of Defense (DoD) Base Realignment and Closure Act (BRAC) Policy on Asbestos, Lead Paint and Radon Policies at BRAC Properties (October 31, 1994)
- EPA 560/5-85-030a – *Asbestos in Buildings: Simplified Sampling Scheme for Friable Surfacing Materials*

1.1 Housing Community Overview

NAPR housing was reportedly constructed between 1960 and 1975 and contains 962 two, three, and four-bedroom apartment style, duplex, and single-family units. NAPR housing consists of eight communities: Algodones, Caribe Breeze, Cascajo Point, Coast Guard, FDR Drive, Manatee Bay, Mangrove Manor, and Rainbow Hill. Twenty-seven of the housing units in Manatee Bay are of original construction, while the remaining 935 units were renovated beginning in 1989. The square footage of the units ranges from 1023 to 2105 square feet. The concrete-framed buildings have concrete or ceramic exterior finishes. Interior walls are painted gypsum board and concrete. The units are generally in good condition.

Table C below summarizes the renovation history for the communities, as provided by the housing office manager.

| Table C. Renovation History for NAPR Housing | | | | |
|--|--|----------------|-------------------|--|
| Address of Units Inspected | Style of Housing | Date of Const. | Date(s) of Renov. | Description of Renovation |
| Algodones | | | | |
| 889C, 889E, 889F, 889G, 889H, 891A, 891D, 893B, 893C, 895A, 895B, 895C, 897A, 897B, 897D, 897F, 897G, 897H, and 899B | Two, Three, and Four Bedroom Apartment-Style Units | 1960 | 1991 | <ul style="list-style-type: none"> • Installation of carpeting • Remodel bathrooms and kitchens • Replace doors and windows |

| Table C. Renovation History for NAPR Housing | | | | |
|---|--|----------------|-------------------|---|
| Address of Units Inspected | Style of Housing | Date of Const. | Date(s) of Renov. | Description of Renovation |
| Caribe Breeze | | | | |
| 1A, 2C, 5B, 6B, 10D, 11A, 15A, 16B, 17C, 20A, 20B, 21B, 25C, 25A, 28A, 31B, 34B, 35A, 37A, 38B, 39C, 43B, and 47A American Circle 92A Saratoga Road 1B and 4B Point Cruz | Two, Three, and Four Bedroom Duplex Units | 1974 | 2001 - 2003 | <ul style="list-style-type: none"> • Remove LBP and ACM • Repaint all walls inside and outside • Replace vinyl floor tile with ceramic tile • Replace A/C ductwork and central A/C units • Upgrade electrical systems • Replace entrance doors • Reconfigure outside storage areas and A/C mechanical rooms • Replace kitchen cabinets • Replace bathroom fixtures and tiles • Reconfigure master bedrooms and bathroom • Replace windows • Install ceiling fans Replace carpeting in upstairs of 2-bedroom units |
| Cascajo Point | | | | |
| 6, 11, 16, 21, 24, 30, and 31 FDR Drive 6 Bataan Drive 5 and 14 San Jacinto Road 4, 7, and 13 Cowrens Drive 4, 5, 13, 14, 19, 26, 29, 30, and 43 Monterey Road 2, 5, 12, and 14 Cabot Lake | Two, Three and Four Bedroom Single Family Houses | 1960 | 1998 - 2001 | <ul style="list-style-type: none"> • Remove LBP and ACM • Construct screened-in porches • Repaint all walls inside and outside • Replace vinyl floor tile with ceramic tile • Replace A/C ductwork and central A/C units • Upgrade electrical systems • Replace kitchen cabinets • Remodel laundry areas • Replace bathroom fixtures and tiles • Reconfigure master bedrooms and bathroom • Install ceiling fans |
| Coast Guard | | | | |
| 1675, 1676, 1677, 1678, 1679, and 1680 Intrepid Street | Three and Four Bedroom Single Family Houses | 1960 | 1989 - 1992 | <ul style="list-style-type: none"> • Replace floors tiles • Replace kitchen cabinets • Install central A/C • Replace aluminum jealously windows with French type glass louvered windows |
| FDR Drive | | | | |
| 1, 3, and 5 FDR Drive | Three Bedroom Single Family Houses | 1960 | 1999 - 2000 | <ul style="list-style-type: none"> • Remove LBP and ACM • Replace carpeting • Repaint all walls inside and outside • Replace A/C ductwork • Reconfigure mechanical room • Upgrade electrical systems • Replace kitchen floors and cabinets • Remodel bathrooms including replace bathroom fixtures (not 1 FDR) • Install ceiling fans |

| Table C. Renovation History for NAPR Housing | | | | |
|--|---|-----------------------|--------------------------|--|
| Address of Units Inspected | Style of Housing | Date of Const. | Date(s) of Renov. | Description of Renovation |
| Manatee Bay | | | | |
| 6 and 7 Intrepid Street 8, 11, 20, 36, 38, 49, 52, and 60 Ranger Road 2 and 20 Hancock Circle 4 and 15 Coral Sea Drive 3 and 18 Franklin Drive 8, 19, and 26 Hornet Road 3, 11, 21, 32, and 35 Yorktown Circle 67, 74, and 81 Lexington Drive | Two, Three and Four Bedroom Single Family Houses | 1960 | 2001 - 2003 | <ul style="list-style-type: none"> ● Remove LBP and ACM ● Construct screened-in porches ● Repaint all walls inside and outside ● Replace vinyl floor tile with ceramic tile ● Replace A/C ductwork and central A/C units ● Upgrade electrical systems ● Reconfigure kitchens and replace kitchen cabinets ● Remodel laundry areas ● Replace bathroom fixtures and tiles ● Reconfigure master bedrooms and bathroom ● Install ceiling fans |
| Mangrove Manor | | | | |
| 11, 12, 19, 20, 31, 38, 50, 68, and 82 Saratoga Road 2, 11, and 17 Essex Drive 6 Ticonderoga Street 18, 25, 34, 41, and 54 Enterprise Drive 9, 26, 33, 46, and 47 Lexington Drive 6, 15, and 32 Wasp Circle 7 Bunker Hill Road | Two, Three and Four Bedroom Single Family Houses | 1960 | 1989 - 1992 | <ul style="list-style-type: none"> ● Same as Coast Guard |
| Rainbow Hill | | | | |
| 2A, 4A, 4B, 5B, 7A, 8A, 10C, 13B, 14B, 15B, 16A, 18A, 19C, 20B, 22B, 23A, 24A, 27A, 28B, 29B, 32A, 33B, 34A, and 36A Nimitz Drive | Two, Three, and Four Bedroom Duplex and Apartment-Style Units | 1975 | 1998 - 2001 | <ul style="list-style-type: none"> ● Same as Caribe Breeze |

Floor plans of each type of housing unit are included in Appendix B, and exterior photographs are presented in Appendix D.

2.0 ASBESTOS-CONTAINING MATERIAL INSPECTION

2.1 Regulatory Background

In the 1970s and 1980s, the EPA banned the use of asbestos-containing spray-on materials, molded and wet applied asbestos, asbestos-containing thermal system insulation, and asbestos in acoustical or decorative applications. As of 1989, the EPA planned to ban the use of asbestos in other products. The ban was originally designed to be put into place in three phases; however, in 1991 the EPA ban was repealed. Because of the repeal, only the first stage of the ban was implemented. Products included in the first phase of the ban were felt products and asbestos cement products.

Several federal regulations pertain to managing ACMs. AHERA, 40 CFR 763 Subpart E, is perhaps the most well known asbestos regulation. The EPA developed AHERA to protect children in the United States from deteriorating ACMs in school buildings. AHERA was enacted in 1986 and required school systems to identify ACMs in all of their school buildings. AHERA also required school systems to develop management plans for the ACMs identified in schools and established reporting and record keeping requirements for educational authorities. Although AHERA is applicable only to schools, many of the accreditation requirements and sampling methodologies established by

the act have been incorporated into the asbestos inspection industry's procedures. ASHARA requires individuals working in public or commercial buildings to be AHERA accredited if they are performing ACM abatement projects, supervising ACM abatement projects, designing ACM abatement projects, or inspecting building for ACMs. The EPA NESHAPS requires inspections for ACM prior to renovation or demolition of structures, except for residential buildings with four or fewer dwelling units. NESHAPS contains work practice and disposal requirements for regulated ACM, which is defined as ACM that is friable or that is likely to become friable during renovation or demolition activities. The definition of a friable material is one that can be crushed, pulverized, or reduced to powder under hand pressure when dry. The definition of a non-friable material is one that cannot be crushed, pulverized, or reduced to powder under hand pressure when dry.

The Puerto Rico Environmental Quality Board (EQB) regulates ACM inspection, management, removal, and disposal activities. The majority of the regulations are found in the EQB's Regulation for the Control of Atmospheric Pollution Rules 102, 422, and 501. The rules require permits, notifications, training, and work plan submissions to EQB, among other items.

OSHA developed the Occupational Exposure to Asbestos regulation to help protect workers from asbestos hazards. The regulation defined Class I through IV asbestos work, established asbestos exposure limits, and implemented asbestos worker protection requirements. Unlike the EPA's regulations, the OSHA regulation was specifically written to protect workers rather than the public. The Puerto Rico Occupational Safety and Health Administration has adopted the federal standard.

Baker reviewed the Federal Property Management Regulations 41 CFR 101-47.304-13 and BRAC policy to identify regulations and guidelines for transferring properties with ACMs. Based on the review of the information, the Navy is required to disclose all knowledge of ACMs at NAPR Housing to any bidders or transferees. This report should be given to parties interested in NAPR Housing and will serve as the disclosure vehicle. As stated in the Federal Property Management Regulations, any bidders on NAPR Housing should be provided with a "Notice of the Presence of Asbestos—Warning!". The notice can be found in 41 CFR 101-47.304-13.

2.2 Methodology

Baker was unable to obtain any previous ACM reports for the housing communities. It is not known if previous ACM surveys were conducted.

Baker conducted the asbestos inspection in accordance with AHERA, ASHARA and OSHA asbestos regulations. AHERA-accredited asbestos inspectors identified building materials that could contain asbestos. Building materials were then grouped into homogeneous materials. Homogeneous materials are defined as building materials similar in appearance and texture. The asbestos inspectors then collected representative bulk material samples from each homogeneous material in general accordance with AHERA guidelines. Insulation materials that appeared to be composed of fiberglass were not considered potential (i.e., suspect) ACM. For each homogeneous material, the material description, location(s), approximate quantity, friability, condition, accessibility, and potential for damage were recorded.

In accordance with the Scope of Work, the number of samples for each homogeneous material was based on the quantity of homogeneous material present throughout the inspected housing units, as follows:

- \leq 1000 square feet – 3 samples
- \leq 5000 square feet – 5 samples
- $>$ 5000 square feet – 7 samples

Sample results from a homogeneous material represent the asbestos content for the homogeneous material throughout each particular housing community, regardless of the sample locations.

As per the scope of work, Baker sampled wallboard and associated joint compound as a composite material. The results are reported for individual layers as well as for the composite material.

Bulk building material samples were sent to Schneider Labs for analysis using polarized light microscopy with dispersion staining. Schneider Labs is accredited for asbestos analysis through the National Voluntary Laboratory Accreditation Program (NVLAP). Homogeneous materials were analyzed until a positive identification of asbestos was made or until all samples of the material were determined to contain less than or equal to 1 percent asbestos. Samples found to contain detectable, but less than 1 percent asbestos, were further analyzed by point count methodology to more accurately define their asbestos content. Quality Control (QC) samples, one per 10 bulk samples, were collected in accordance with the Scope of Work and were analyzed by RJ Lee Group, Inc., another NVLAP accredited laboratory. QC sample results were generally consistent with bulk sample results. However, where conflicting lab results were indicated (i.e., one lab found the material to contain greater than 1 percent asbestos and the other did not), the material was considered to be ACM. Laboratory reports are included in Appendix C. Inspector and laboratory certifications are included in Appendix A.

2.3 Selecting Units for Inspections

Per the Scope of Work, ACM inspections were performed in 19 of 32 Algodones housing units, 26 of 136 Caribe Breeze housing units, 26 of 139 Cascajo Point housing units, all six Coast Guard housing units, all three FDR Drive housing units, 26 of 262 Manatee Bay housing units, 27 of 275 Mangrove Manor housing units, and 24 of 88 Rainbow Hill housing units. NAPR Housing units selected for ACM inspection were chosen randomly. Units selected for ACM inspection are listed in Table D below. All units were vacant at the time of the inspections.

Table D. Units Selected for ACM Inspection at NAPR Housing

| Address | Date Inspected |
|---------------------|------------------|
| Algodones | |
| 889C | February 1, 2005 |
| 889E | February 1, 2005 |
| 889F | February 2, 2005 |
| 889G | February 2, 2005 |
| 889H | February 7, 2005 |
| 891A | February 3, 2005 |
| 891D | February 3, 2005 |
| 893B | February 3, 2005 |
| 893C | February 4, 2005 |
| 895A | February 4, 2005 |
| 895B | February 4, 2005 |
| 895C | February 4, 2005 |
| 897A | February 7, 2005 |
| 897B | February 2, 2005 |
| 897D | February 2, 2005 |
| 897F | February 2, 2005 |
| 897G | February 2, 2005 |
| 897H | February 2, 2005 |
| 899B | February 1, 2005 |
| Caribe Breeze | |
| 1A American Circle | January 5, 2005 |
| 2C American Circle | January 9, 2005 |
| 5B American Circle | January 7, 2005 |
| 6B American Circle | January 7, 2005 |
| 10D American Circle | January 10, 2005 |
| 11A American Circle | January 10, 2005 |
| 15A American Circle | January 10, 2005 |
| 16B American Circle | January 10, 2005 |
| 17C American Circle | January 11, 2005 |
| 20A American Circle | January 11, 2005 |
| 20B American Circle | January 11, 2005 |
| 21B American Circle | January 12, 2005 |
| 24C American Circle | January 12, 2005 |
| 25A American Circle | January 12, 2005 |
| 28A American Circle | January 12, 2005 |
| 31B American Circle | January 12, 2005 |
| 34B American Circle | January 13, 2005 |
| 35A American Circle | January 13, 2005 |
| 37A American Circle | January 13, 2005 |
| 38B American Circle | January 14, 2005 |
| 39C American Circle | January 14, 2005 |

Table D. Units Selected for ACM Inspection at NAPR Housing

| Address | Date Inspected |
|----------------------|-----------------------|
| Caribe Breeze | |
| 43B American Circle | January 14, 2005 |
| 47A American Circle | January 17, 2005 |
| 1B Point Cruz | January 17, 2005 |
| 4B Point Cruz | January 17, 2005 |
| 92A Saratoga Drive | January 17, 2005 |
| Cascaio Point | |
| 6 Bataan Drive | January 20, 2005 |
| 4 Cowrens Drive | January 21, 2005 |
| 7 Cowrens Drive | January 24, 2005 |
| 13 Cowrens Drive | January 24, 2005 |
| 6 FDR Drive | January 20, 2005 |
| 11 FDR Drive | January 20, 2005 |
| 16 FDR Drive | January 20, 2005 |
| 21 FDR Drive | January 20, 2005 |
| 24 FDR Drive | January 20, 2005 |
| 30 FDR Drive | January 21, 2005 |
| 31 FDR Drive | January 21, 2005 |
| 4 Monterey Road | January 26, 2005 |
| 5 Monterey Road | January 26, 2005 |
| 13 Monterey Road | January 26, 2005 |
| 14 Monterey Road | January 27, 2005 |
| 19 Monterey Road | January 27, 2005 |
| 26 Monterey Road | January 27, 2005 |
| 29 Monterey Road | January 27, 2005 |
| 30 Monterey Road | January 27, 2005 |
| 43 Monterey Road | January 27, 2005 |
| 5 San Jacinto Road | January 27, 2005 |
| 14 San Jacinto Road | January 25, 2005 |
| Coast Guard | |
| 1675 Intrepid Street | January 31, 2005 |
| 1676 Intrepid Street | January 31, 2005 |
| 1677 Intrepid Street | February 1, 2005 |
| 1678 Intrepid Street | February 5, 2005 |
| 1679 Intrepid Street | February 5, 2005 |
| 1680 Intrepid Street | January 31, 2005 |
| FDR Drive | |
| 1 FDR Drive | January 19, 2005 |
| 3 FDR Drive | January 21, 2005 |
| 5 FDR Drive | January 19, 2005 |
| Manatee Bay | |
| 4 Coral Sea Drive | January 12, 2005 |
| 15 Coral Sea Drive | January 12, 2005 |
| 3 Franklyn Drive | January 12, 2005 |
| 18 Franklyn Drive | January 12, 2005 |
| 2 Hancock Circle | January 11, 2005 |
| 20 Hancock Circle | January 11, 2005 |

Table D. Units Selected for ACM Inspection at NAPR Housing

| Address | Date Inspected |
|-----------------------|-----------------------|
| Manatee Bay | |
| 8 Homet Road | January 13, 2005 |
| 19 Homet Road | January 13, 2005 |
| 26 Homet Road | January 13, 2005 |
| 6 Intrepid Street | January 6, 2005 |
| 7 Intrepid Street | January 7, 2005 |
| 67 Lexington Drive | January 18, 2005 |
| 74 Lexington Drive | January 18, 2005 |
| 81 Lexington Drive | January 18, 2005 |
| 8 Ranger Road | January 7, 2005 |
| 11 Ranger Road | January 7, 2005 |
| 20 Ranger Road | January 10, 2005 |
| 36 Ranger Road | January 11, 2005 |
| 38 Ranger Road | January 10, 2005 |
| 49 Ranger Road | January 10, 2005 |
| 52 Ranger Road | January 10, 2005 |
| 60 Ranger Road | January 11, 2005 |
| 3 Yorktown Circle | January 14, 2005 |
| 11 Yorktown Circle | January 14, 2005 |
| 21 Yorktown Circle | January 14, 2005 |
| 32 Yorktown Circle | January 14, 2005 |
| 35 Yorktown Circle | January 17, 2005 |
| Mangrove Manor | |
| 7 Bunker Hill Road | January 27, 2005 |
| 18 Enterprise Drive | January 24, 2005 |
| 25 Enterprise Drive | January 24, 2005 |
| 34 Enterprise Drive | January 24, 2005 |
| 41 Enterprise Drive | January 25, 2005 |
| 54 Enterprise Drive | January 25, 2005 |
| 2 Essex Drive | January 21, 2005 |
| 11 Essex Drive | January 21, 2005 |
| 17 Essex Drive | January 21, 2005 |
| 9 Lexington Drive | January 25, 2005 |
| 26 Lexington Drive | January 26, 2005 |
| 33 Lexington Drive | January 26, 2005 |
| 46 Lexington Drive | January 26, 2005 |
| 47 Lexington Drive | January 26, 2005 |
| 6 Ticonderoga Road | January 24, 2005 |
| 11 Saratoga Road | January 19, 2005 |
| 12 Saratoga Road | January 19, 2005 |
| 19 Saratoga Road | January 19, 2005 |
| 20 Saratoga Road | January 19, 2005 |
| 31 Saratoga Road | January 20, 2005 |
| 38 Saratoga Road | January 20, 2005 |
| 50 Saratoga Road | January 20, 2005 |
| 68 Saratoga Road | January 20, 2005 |

| Table D. Units Selected for ACM Inspection at NAPR Housing | |
|---|-----------------------|
| Address | Date Inspected |
| Mangrove Manor | |
| 82 Saratoga Road | January 21, 2005 |
| 6 Wasp Circle | January 26, 2005 |
| 15 Wasp Circle | January 27, 2005 |
| 32 Wasp Circle | January 27, 2005 |
| Rainbow Hill | |
| 2A Nimitz Drive | January 27, 2005 |
| 4A Nimitz Drive | January 28, 2005 |
| 4B Nimitz Drive | January 28, 2005 |
| 5B Nimitz Drive | January 28, 2005 |
| 7A Nimitz Drive | January 28, 2005 |
| 8A Nimitz Drive | January 28, 2005 |
| 10C Nimitz Drive | January 31, 2005 |
| 13B Nimitz Drive | January 31, 2005 |
| 14B Nimitz Drive | January 31, 2005 |
| 15B Nimitz Drive | January 31, 2005 |
| 16A Nimitz Drive | February 1, 2005 |
| 18A Nimitz Drive | February 1, 2005 |
| 19C Nimitz Drive | February 1, 2005 |
| 20B Nimitz Drive | February 1, 2005 |
| 22B Nimitz Drive | February 2, 2005 |
| 23A Nimitz Drive | February 2, 2005 |
| 24A Nimitz Drive | February 2, 2005 |
| 27A Nimitz Drive | February 2, 2005 |
| 28B Nimitz Drive | February 3, 2005 |
| 29B Nimitz Drive | February 3, 2005 |
| 32A Nimitz Drive | February 3, 2005 |
| 33B Nimitz Drive | February 3, 2005 |
| 34A Nimitz Drive | February 4, 2005 |
| 36A Nimitz Drive | February 4, 2005 |

2.4 Disclaimer

Baker was contracted to perform an ACM inspection of NAPR Housing that would meet the requirements of an Operations and Maintenance Program for ACMs. As such, the inspection was not destructive and did not involve breaking into pipe chases, interstitial spaces or other inaccessible building areas. Therefore, ACMs may exist within inaccessible building areas. The presence or absence of ACMs applies only to materials sampled on the dates of the field visit. It should be noted that conditions might change due to vandalism, deterioration, or maintenance activities. Ongoing monitoring by the owner or transferee is necessary. If additional materials suspected of containing

asbestos are identified during renovation or demolition activities, they should be assumed to be ACMs or should be sampled and analyzed before being disturbed.

2.5 Summary of Asbestos-Containing Materials

By definition, an ACM contains greater than 1 percent asbestos. Table E below lists the ACMs identified within NAPR Housing by community. Note that additional ACMs may be present in the communities. ACMs were not identified in Rainbow Hill. Floor plans of typical units are presented in Appendix B. For a complete listing of the materials tested for asbestos, refer to Table 1 (for each housing community) following the text of this report.

| Table E. ACMs Identified at NAPR Housing | | |
|---|--|--|
| Material | Location | Approximate Percent of Units with ACMs* |
| Algodones | | |
| Vinyl Floor Tile, 9" x 9" tan with brown streaks | LR/DR, Hall 1, BR1, BR2, and BR3 | 47% |
| Floor Adhesive, under 9" x 9" tan with brown streaks vinyl floor tile | LR/DR, Hall 1, BR1, BR2, and BR3 | 47% |
| Vinyl Floor Tile, 9" x 9" gray with black streaks | BR1 and BR2 | 42% |
| Floor Adhesive, under 9" x 9" gray with black streaks vinyl floor tile | BR1 and BR2 | 42% |
| Caribe Breeze | | |
| Tan/Black Floor Adhesive, under 1' x 1' tan mottled vinyl floor tile | BR1, BR2, BR3, BR4, ST2, ST3, Hall 1, Hall 2, Stair, Laundry, Kitchen, LR/DR | 43% |
| Yellow/Black Floor Adhesive, under 1' x 1' gray mottled vinyl floor tile | BR1, BR2, BR3, BR4, ST2, ST3, Hall 1, Hall 2, Stair, Laundry, Kitchen, LR/DR | 57% |
| Cascajo Point | | |
| Yellow/Black Floor Adhesive, under 1' x 1' tan mottled vinyl floor tile | BR1, BR2, BR3, BR4, LR, DR, LR-P, Hall, Laundry, and Kitchen | 100% |
| Coast Guard | | |
| Black Floor Adhesive, under 1' x 1' brown with white and red streaks vinyl floor tile | LR, DR, Kitchen, Hall, BR1, BR2, BR3, and BR4 | 66% |
| FDR Drive | | |
| Floor Adhesive, under 1' x 1' brown with red streaks vinyl floor tile | LR/DR | 33% |
| Vinyl Floor Tile, 9" x 9" gray with white streaks | BR1, BR2, BR3, Hall, and LR/DR | 66% |
| Floor Adhesive, under 9" x 9" gray with white streaks vinyl floor tile | BR1, BR2, BR3, Hall, and LR/DR | 66% |
| Floor Adhesive, under 1' x 1' tan mottled vinyl floor tile | BR1, BR2, BR3, and Hall | 33% |
| Vinyl Floor Tile, 1' x 1' brown with tan streaks | LR/DR | 33% |

| Table E. ACMs Identified at NAPR Housing | | |
|--|---|--|
| Material | Location | Approximate Percent of Units with ACMs* |
| Manatee Bay | | |
| Vinyl Floor Tile, 1' x 1' yellow mottled | LR, DR, Kitchen, Hall, BR1, BR2, and BR3 | 3% |
| Black Floor Adhesive, under 1' x 1' yellow mottled and 1' x 1' brown with orange and white stripes vinyl floor tiles | LR, DR, Kitchen, Hall, BR1, BR2, and BR3 | 7% |
| Mangrove Manor | | |
| Vinyl Floor Tile, 1' x 1' brown mottled | LR, DR, Kitchen, Hall, BR1, BR2, BR3, and BR4 | 33% |
| Black Floor Adhesive, under 1' x 1' brown mottled, 1' x 1' white with brown streaks, 1' x 1' light brown mottled, 1' x 1' brown with light brown streaks, 1' x 1' brown with white streaks, 1' x 1' white with gray specks, and 1' x 1' white with black streaks vinyl floor tiles | LR, DR, Kitchen, Hall, BR1, BR2, BR3, and BR4 | 88% |
| Mangrove Manor | | |
| Vinyl Floor Tile, 1' x 1' brown with light brown streaks | LR, DR, Kitchen, Hall, BR1, BR2, BR3, and BR4 | 4% |
| Vinyl Floor Tile, 1' x 1' white with black streaks | LR, DR, Kitchen, Hall, BR1, BR2, BR3, and BR4 | 7% |
| Vinyl Floor Tile, 1' x 1' tan mottled | LR, DR, Kitchen, Hall, BR1, BR2, BR3, and BR4 | 7% |
| Black Floor Adhesive, under 1' x 1' tan mottled and 1' x 1' white mottled vinyl floor tiles | LR, DR, Kitchen, Hall, BR1, BR2, BR3, and BR4 | 11% |
| Vinyl Floor Tile, 1' x 1' white mottled | LR, DR, Kitchen, Hall, BR1, BR2, BR3, and BR4 | 4% |
| Sink Coating, black | Kitchen | 96% |

Table 2 (for each housing community) following the text of this report provides additional details on the ACMs that were identified, including asbestos content, friability, and total quantities for the housing units that were inspected. Tables F through L, following Table E, list the ACMs identified by housing unit address. Appendix D contains photographs of the identified ACMs. A CD that includes these photographs accompanies this report.

Table F. ACMs Identified by Address for Algodones

| Unit | Material | Material No. | Comment | Condition |
|----------------|--|--------------|--|-----------|
| 889C Algodones | Vinyl Floor Tile (9" X 9" Tan With Brown Streaks) | 006 | The Adhesive For This Material Is Material #007. | Undamaged |
| | Floor Adhesive (Black, Under 9" X 9" Tan With Brown Streaks Vinyl Floor Tile) | 007 | This Is The Adhesive For Material #006. | Undamaged |
| 889G Algodones | See Initial Entry for Material #006 | 006 | The Adhesive For This Material Is Material #007. | Undamaged |
| | See Initial Entry for Material #007 | 007 | This Is The Adhesive For Material #006. | Undamaged |
| | Vinyl Floor Tile (9" X 9" Gray With Black Streaks) | 010 | The Adhesive For This Material Is Material #010. This Material Is Located Below The Existing Carpet. | Undamaged |
| | Floor Adhesive (Black, Under 9" X 9" Gray With Black Streaks Vinyl Floor Tile) | 011 | This Is The Adhesive For Material #010. | Undamaged |
| 889H Algodones | See Initial Entry for Material #006 | 006 | The Adhesive For This Material Is Material #007. | Undamaged |
| | See Initial Entry for Material #007 | 007 | This Is The Adhesive For Material #006. | Undamaged |
| | See Initial Entry for Material #010 | 010 | The Adhesive For This Material Is Material #010. This Material Is Located Below The Existing Carpet. | Undamaged |
| | See Initial Entry for Material #011 | 011 | This Is The Adhesive For Material #010. | Undamaged |
| 891D Algodones | See Initial Entry for Material #006 | 006 | The Adhesive For This Material Is Material #007. | Undamaged |
| | See Initial Entry for Material #007 | 007 | This Is The Adhesive For Material #006. | Undamaged |
| | See Initial Entry for Material #010 | 010 | The Adhesive For This Material Is Material #010. This Material Is Located Below The Existing Carpet. | Undamaged |
| | See Initial Entry for Material #011 | 011 | This Is The Adhesive For Material #010. | Undamaged |
| 893C Algodones | See Initial Entry for Material #006 | 006 | The Adhesive For This Material Is Material #007. | Undamaged |
| | See Initial Entry for Material #007 | 007 | This Is The Adhesive For Material #006. | Undamaged |
| | See Initial Entry for Material #010 | 010 | The Adhesive For This Material Is Material #010. This Material Is Located Below The Existing Carpet. | Undamaged |
| | See Initial Entry for Material #011 | 011 | This Is The Adhesive For Material #010. | Undamaged |
| 895C Algodones | See Initial Entry for Material #006 | 006 | The Adhesive For This Material Is Material #007. | Undamaged |
| | See Initial Entry for Material #007 | 007 | This Is The Adhesive For Material #006. | Undamaged |
| | See Initial Entry for Material #010 | 010 | The Adhesive For This Material Is Material #010. This Material Is Located Below The Existing Carpet. | Undamaged |
| | See Initial Entry for Material #011 | 011 | This Is The Adhesive For Material #010. | Undamaged |
| 897D Algodones | See Initial Entry for Material #006 | 006 | The Adhesive For This Material Is Material #007. | Undamaged |
| 897D Algodones | See Initial Entry for Material #007 | 007 | This Is The Adhesive For Material #006. | Undamaged |
| | See Initial Entry for Material #010 | 010 | The Adhesive For This Material Is Material #010. This Material Is Located Below The Existing Carpet. | Undamaged |
| | See Initial Entry for Material #011 | 011 | This Is The Adhesive For Material #010. | Undamaged |
| 897G Algodones | See Initial Entry for Material #006 | 006 | The Adhesive For This Material Is Material #007. | Undamaged |
| | See Initial Entry for Material #007 | 007 | This Is The Adhesive For Material #006. | Undamaged |
| | See Initial Entry for Material #010 | 010 | The Adhesive For This Material Is Material #010. This Material Is Located Below The Existing Carpet. | Undamaged |
| | See Initial Entry for Material #011 | 011 | This Is The Adhesive For Material #010. | Undamaged |
| 897H Algodones | See Initial Entry for Material #006 | 006 | The Adhesive For This Material Is Material #007. | Undamaged |
| | See Initial Entry for Material #007 | 007 | This Is The Adhesive For Material #006. | Undamaged |
| | See Initial Entry for Material #010 | 010 | The Adhesive For This Material Is Material #010. This Material Is Located Below The Existing Carpet. | Undamaged |
| | See Initial Entry for Material #011 | 011 | This Is The Adhesive For Material #010. | Undamaged |

Table G. ACMs Identified by Address for Caribe Breeze

| Unit | Material | Material No. | Comment | Condition |
|---------------------|--|--------------|---|-----------|
| 10D American Circle | Floor Adhesive (Yellow With Black Residual, Under 1' X 1' Gray Mottled Vinyl Floor Tile) | 008 | This Is The Adhesive For Material #007. | Undamaged |
| 11A American Circle | Floor Adhesive (Tan With Black Residual, Under 1' X 1' Tan Mottled Vinyl Floor Tile) | 002 | This Is The Adhesive For Material #001. | Undamaged |
| 15A American Circle | See Initial Entry for Material #002. | 002 | This Is The Adhesive For Material #001. | Undamaged |
| 16B American Circle | See Initial Entry for Material #008. | 008 | This Is The Adhesive For Material #007. | Undamaged |
| 17C American Circle | See Initial Entry for Material #008. | 008 | This Is The Adhesive For Material #007. | Undamaged |
| 1A American Circle | See Initial Entry for Material #002. | 002 | This Is The Adhesive For Material #001. | Undamaged |
| 1B Point Cruz | See Initial Entry for Material #008. | 008 | This Is The Adhesive For Material #007. | Undamaged |
| 20A American Circle | See Initial Entry for Material #002. | 002 | This Is The Adhesive For Material #001. | Undamaged |
| 20B American Circle | See Initial Entry for Material #008. | 008 | This Is The Adhesive For Material #007. | Undamaged |
| 21B American Circle | See Initial Entry for Material #008. | 008 | This Is The Adhesive For Material #007. | Undamaged |
| 24C American Circle | See Initial Entry for Material #008. | 008 | This Is The Adhesive For Material #007. | Undamaged |
| 25A American Circle | See Initial Entry for Material #002. | 002 | This Is The Adhesive For Material #001. | Undamaged |
| 28A American Circle | See Initial Entry for Material #002. | 002 | This Is The Adhesive For Material #001. | Undamaged |
| 2C American Circle | See Initial Entry for Material #008. | 008 | This Is The Adhesive For Material #007. | Undamaged |
| 31B American Circle | See Initial Entry for Material #008. | 008 | This Is The Adhesive For Material #007. | Undamaged |
| 34B American Circle | See Initial Entry for Material #008. | 008 | This Is The Adhesive For Material #007. | Undamaged |
| 35A American Circle | See Initial Entry for Material #002. | 002 | This Is The Adhesive For Material #001. | Undamaged |
| 37A American Circle | See Initial Entry for Material #002. | 002 | This Is The Adhesive For Material #001. | Undamaged |
| 38B American Circle | See Initial Entry for Material #008. | 008 | This Is The Adhesive For Material #007. | Undamaged |
| 39C American Circle | See Initial Entry for Material #008. | 008 | This Is The Adhesive For Material #007. | Undamaged |
| 43B American Circle | See Initial Entry for Material #008. | 008 | This Is The Adhesive For Material #007. | Undamaged |
| 47A American Circle | See Initial Entry for Material #002. | 002 | This Is The Adhesive For Material #001. | Undamaged |
| 4B Point Cruz | See Initial Entry for Material #002. | 002 | This Is The Adhesive For Material #001. | Undamaged |
| 5B American Circle | See Initial Entry for Material #008. | 008 | This Is The Adhesive For Material #007. | Undamaged |
| 6B American Circle | See Initial Entry for Material #008. | 008 | This Is The Adhesive For Material #007. | Undamaged |
| 92A Saratoga Road | See Initial Entry for Material #002. | 002 | This Is The Adhesive For Material #001. | Undamaged |

Table H. ACMs Identified by Address for Cascajo Point

| Unit | Material | Material No. | Comment | Condition |
|---------------------|---|--------------|---|-----------|
| 11 FDR Drive | Floor Adhesive (Yellow With Black Residual, Under Tan 1' X 1' Mottled Vinyl Floor Tile) | 003 | This Is The Adhesive For Material #002. | Undamaged |
| 12 Cabot Lake | See Initial Entry for Material #003 | 003 | | Undamaged |
| 13 Cowrens Drive | See Initial Entry for Material #003 | 003 | | Undamaged |
| 13 Monterey Road | See Initial Entry for Material #003 | 003 | | Undamaged |
| 14 Cabot Lake | See Initial Entry for Material #003 | 003 | | Undamaged |
| 14 Monterey Road | See Initial Entry for Material #003 | 003 | | Undamaged |
| 14 San Jacinto Road | See Initial Entry for Material #003 | 003 | | Undamaged |
| 16 FDR Drive | See Initial Entry for Material #003 | 003 | | Undamaged |
| 19 Monterey Road | See Initial Entry for Material #003 | 003 | | Undamaged |
| 2 Cabot Lake | See Initial Entry for Material #003 | 003 | | Undamaged |
| 21 FDR Drive | See Initial Entry for Material #003 | 003 | | Undamaged |
| 26 Monterey Road | See Initial Entry for Material #003 | 003 | | Undamaged |
| 29 Monterey Road | See Initial Entry for Material #003 | 003 | | Undamaged |
| 30 FDR Drive | See Initial Entry for Material #003 | 003 | | Undamaged |
| 30 Monterey Road | See Initial Entry for Material #003 | 003 | | Undamaged |
| 31 FDR Drive | See Initial Entry for Material #003 | 003 | | Undamaged |
| 4 Cowrens Drive | See Initial Entry for Material #003 | 003 | | Undamaged |
| 4 Monterey Road | See Initial Entry for Material #003 | 003 | | Undamaged |
| 43 Monterey Road | See Initial Entry for Material #003 | 003 | | Undamaged |
| 5 Cabot Lake | See Initial Entry for Material #003 | 003 | | Undamaged |
| 5 Monterey Road | See Initial Entry for Material #003 | 003 | | Undamaged |
| 5 San Jacinto Road | See Initial Entry for Material #003 | 003 | | Undamaged |
| 6 Bataan Drive | See Initial Entry for Material #003 | 003 | | Undamaged |
| 6 FDR Drive | See Initial Entry for Material #003 | 003 | | Undamaged |
| 7 Cowrens Drive | See Initial Entry for Material #003 | 003 | | Undamaged |

Table 1. ACMs Identified by Address for Coast Guard

| Unit | Material | Material No. | Comment | Condition |
|----------------------|---|--------------|---|-----------|
| 1675 Intrepid Street | Floor Adhesive (Black, Under 1' X 1' Brown With White And Red Streaks Vinyl Floor Tile) | 007 | This Is The Adhesive For Material #006. | Undamaged |
| 1677 Intrepid Street | See Initial Entry for Material #007 | 007 | | Undamaged |
| 1678 Intrepid Street | See Initial Entry for Material #007 | 007 | | Undamaged |
| 1679 Intrepid Street | See Initial Entry for Material #007 | 007 | | Undamaged |

Table J. ACMs Identified by Address for FDR Drive

| Unit | Material | Material No. | Comment | Condition |
|-------------|--|--------------|--|-----------|
| 1 FDR Drive | Vinyl Floor Tile (9" X 9" Gray With White Streaks) | 006 | The Adhesive For This Material Is Material #007. This Material Is Located Below The Existing Carpet. | Undamaged |
| | Floor Adhesive (Black, Under 9" X 9" Gray With White Streaks Vinyl Floor Tile) | 007 | This Is The Adhesive For Material #006. | Undamaged |
| 3 FDR Drive | Floor Adhesive (Black, Under 1' X 1' Tan Mottled Vinyl Floor Tile) | 009 | This Is The Adhesive For Material #007. | Undamaged |
| | Vinyl Floor Tile (1' X 1' Brown With Tan Streaks) | 011 | The Adhesive For This Material Is Material #012. This Material Is Located Below The Existing Carpet. | Undamaged |
| 5 FDR Drive | Floor Adhesive (Black, Under 1' X 1' Brown With Red Streaks Vinyl Floor Tile) | 005 | This Is The Adhesive For Material #004. | Undamaged |
| | Vinyl Floor Tile (9" X 9" Gray With White Streaks) | 006 | The Adhesive For This Material Is Material #007. This Material Is Located Below The Existing Carpet. | Undamaged |
| | Floor Adhesive (Black, Under 9" X 9" Gray With White Streaks Vinyl Floor Tile) | 007 | This Is The Adhesive For Material #006. | Undamaged |

Table K. ACMs Identified by Address for Manatee Bay

| Unit | Material | Material No. | Comment | Condition |
|-------------------|---|--------------|---|-----------|
| 6 Intrepid Street | Vinyl Floor Tile (1' X 1' Yellow Mottled) | 001 | The Adhesive For This Material Is Material #002. | Damaged |
| | Floor Adhesive (Black, Under 1' X 1' Yellow Mottled And 1' X 1' Brown With White And Orange Stripes Vinyl Floor Tile) | 002 | This Is The Adhesive For Materials #001 And #005. | Damaged |
| 7 Intrepid Street | Floor Adhesive (Black, Under 1' X 1' Yellow Mottled And 1' X 1' Brown With White And Orange Stripes Vinyl Floor Tile) | 002 | This Is The Adhesive For Materials #001 And #005. | Damaged |

Table I. ACMs Identified by Address for Mangrove Manor

| Unit | Material | Material No. | Comment | Condition |
|---------------------|--|--------------|--|-----------|
| 11 Essex Drive | Floor Adhesive (Black, Under 1' X 1' Brown Mottled, 1' X 1' White With Brown Streaks, 1' X 1' White With Black Streaks, 1' X 1' White With Gray Specks, 1' X 1' Brown With Light Brown Streaks, 1' X 1' Brown With White Streaks, And 1' X 1' Light Brown Mottled Vinyl Floor Tiles) | 002 | This Is The Adhesive For Materials #001, #005, #006, #007, #008, #009, And #010. | Undamaged |
| | Sink Coating (Black) | 004 | | Undamaged |
| 11 Saratoga Road | Vinyl Floor Tile (1' X 1' Brown Mottled) | 001 | The Adhesive For This Material Is Material #002. | Undamaged |
| | See Initial Entry for Material #002 | 002 | | Undamaged |
| | Sink Coating (Black) | 004 | | Undamaged |
| 12 Saratoga Road | See Initial Entry for Material #002 | 002 | | Undamaged |
| | Sink Coating (Black) | 004 | | Undamaged |
| 15 Wasp Drive | See Initial Entry for Material #002 | 002 | | Undamaged |
| | Sink Coating (Black) | 004 | | Undamaged |
| 17 Essex Drive | Vinyl Floor Tile (1' X 1' Brown Mottled) | 001 | The Adhesive For This Material Is Material #002. | Undamaged |
| | See Initial Entry for Material #002 | 002 | | Undamaged |
| | Sink Coating (Black) | 004 | | Undamaged |
| 18 Enterprise Drive | Vinyl Floor Tile (1' X 1' Brown Mottled) | 001 | The Adhesive For This Material Is Material #002. | Undamaged |
| | See Initial Entry for Material #002 | 002 | | Undamaged |
| | Sink Coating (Black) | 004 | | Undamaged |
| 19 Saratoga Road | See Initial Entry for Material #002 | 002 | | Undamaged |
| | Sink Coating (Black) | 004 | | Undamaged |
| | Vinyl Floor Tile (1' X 1' Brown With Light Brown Streaks) | 007 | The Adhesive For This Material Is Material #002. | Undamaged |
| 2 Essex Drive | See Initial Entry for Material #002 | 002 | | Undamaged |
| | Sink Coating (Black) | 004 | | Undamaged |
| 20 Saratoga Road | See Initial Entry for Material #002 | 002 | | Undamaged |
| | Sink Coating (Black) | 004 | | Undamaged |
| 25 Enterprise Drive | Sink Coating (Black) | 004 | | Undamaged |
| | Vinyl Floor Tile (1' X 1' Tan Mottled) | 011 | The Adhesive For This Material Is Material #012. | Damaged |
| | Floor Adhesive (Black, Under 1' X 1' Tan Mottled And 1' X 1' White Mottled Vinyl Floor Tile) | 012 | This Is The Adhesive For Material #011. | Damaged |
| 26 Lexington Drive | See Initial Entry for Material #002 | 002 | | Undamaged |
| | Sink Coating (Black) | 004 | | Undamaged |
| 31 Saratoga Road | See Initial Entry for Material #002 | 002 | | Undamaged |
| | Sink Coating (Black) | 004 | | Undamaged |
| 32 Wasp Drive | See Initial Entry for Material #002 | 002 | | Undamaged |
| | Sink Coating (Black) | 004 | | Undamaged |

Table L. ACMs Identified by Address for Mangrove Manor

| Unit | Material | Material No. | Comment | Condition |
|----------------------|--|--------------|--|-----------|
| 33 Lexington Drive | Vinyl Floor Tile (1' X 1' Brown Mottled) | 001 | The Adhesive For This Material Is Material #002. | Undamaged |
| | See Initial Entry for Material #002 | 002 | | Undamaged |
| 34 Enterprise Drive | Sink Coating (Black) | 004 | | Undamaged |
| | Floor Adhesive (Black, Under 1' X 1' Tan Mottled And 1' X 1' White Mottled Vinyl Floor Tile) | 012 | This Is The Adhesive For Material #011. | Damaged |
| | Vinyl Floor Tile (1' X 1' White Mottled) | 013 | The Adhesive For This Material Is Material #012. | Damaged |
| 38 Saratoga Road | See Initial Entry for Material #002 | 002 | | Undamaged |
| | Sink Coating (Black) | 004 | | Undamaged |
| 41 Enterprise Drive | Vinyl Floor Tile (1' X 1' Brown Mottled) | 001 | The Adhesive For This Material Is Material #002. | Undamaged |
| | See Initial Entry for Material #002 | 002 | | Undamaged |
| | Sink Coating (Black) | 004 | | Undamaged |
| 46 Lexington Drive | Sink Coating (Black) | 004 | | Undamaged |
| | Vinyl Floor Tile (1' X 1' Tan Mottled) | 011 | The Adhesive For This Material Is Material #012. | Damaged |
| | Floor Adhesive (Black, Under 1' X 1' Tan Mottled And 1' X 1' White Mottled Vinyl Floor Tile) | 012 | This Is The Adhesive For Material #011. | Damaged |
| 47 Lexington Drive | Vinyl Floor Tile (1' X 1' Brown Mottled) | 001 | The Adhesive For This Material Is Material #002. | Undamaged |
| | See Initial Entry for Material #002 | 002 | | Undamaged |
| | Sink Coating (Black) | 004 | | Undamaged |
| 50 Saratoga Road | See Initial Entry for Material #002 | 002 | | Undamaged |
| | Sink Coating (Black) | 004 | | Undamaged |
| 54 Enterprise Drive | See Initial Entry for Material #002 | 002 | | Undamaged |
| | Sink Coating (Black) | 004 | | Undamaged |
| 6 Ticonderoga Street | Vinyl Floor Tile (1' X 1' Brown Mottled) | 001 | The Adhesive For This Material Is Material #002. | Undamaged |
| | See Initial Entry for Material #002 | 002 | | Undamaged |
| | Sink Coating (Black) | 004 | | Undamaged |
| 6 Wasp Drive | See Initial Entry for Material #002 | 002 | | Undamaged |
| | Sink Coating (Black) | 004 | | Undamaged |
| | Vinyl Floor Tile (1' X 1' White With Black Streaks) | 010 | The Adhesive For This Material Is Material #002. | Undamaged |
| 68 Saratoga Road | See Initial Entry for Material #002 | 002 | | Undamaged |
| | Sink Coating (Black) | 004 | | Undamaged |
| 7 Bunker Hill Road | Vinyl Floor Tile (1' X 1' Brown Mottled) | 001 | The Adhesive For This Material Is Material #002. | Undamaged |
| | See Initial Entry for Material #002 | 002 | | Undamaged |
| | Sink Coating (Black) | 004 | | Undamaged |
| 82 Saratoga Road | See Initial Entry for Material #002 | 002 | | Undamaged |
| | Sink Coating (Black) | 004 | | Undamaged |
| | Vinyl Floor Tile (1' X 1' White With Black Streaks) | 010 | The Adhesive For This Material Is Material #002. | Undamaged |
| 9 Lexington Drive | Vinyl Floor Tile (1' X 1' Brown Mottled) | 001 | The Adhesive For This Material Is Material #002. | Undamaged |
| | See Initial Entry for Material #002 | 002 | | Undamaged |
| | Sink Coating (Black) | 004 | | Undamaged |

2.6 Summary of Hazards

Base Realignment and Closure (BRAC) policy considers an ACM to be a hazard when it meets all three of the following conditions: friable, accessible, and damaged. No ACM hazards were identified in the 158 NAPR Housing units that were inspected. Per the Scope of Work, Baker did not conduct walk-through inspections of all NAPR Housing units to identify ACMs and ACM hazards. Therefore, additional ACMs and ACM hazards may be present at NAPR Housing.

If renovation or demolition of housing units is scheduled, a more comprehensive ACM inspection should be conducted to attempt to identify hidden ACM (e.g., behind walls, above ceilings, etc.) that would not have been identified during this non-destructive, baseline study. Also, prior to renovation or demolition, ACM removal and disposal activities must be completed in accordance with EPA, Puerto Rico OSHA, Puerto Rico EQB, and other applicable federal and local regulations.

Final
Asbestos Inspection Report
for
Naval Activity Puerto Rico
Ceiba, Puerto Rico

Volume 1 of 7

(Text and Appendices A through D)

Contract N62472-01-D-1440 • Project Number 14 • June 2005



Prepared by
Michael Baker Jr., Inc.

Baker

ChallengeUs.

Under Contract with
Department of the Navy
Naval Facilities Engineering Command
Engineering Field Activity, Northeast



TABLE OF CONTENTS

| | <u>Page</u> |
|--|-------------|
| EXECUTIVE SUMMARY..... | ES-1 |
| 1.0 INTRODUCTION..... | 1 |
| 1.1 Buildings Overview | 2 |
| 2.0 ASBESTOS-CONTAINING MATERIAL INSPECTION | 2 |
| 2.1 Regulatory Background | 2 |
| 2.2 Methodology | 4 |
| 2.3 Disclaimer | 7 |
| 2.4 Summary of Asbestos-Containing Materials | 7 |
| 2.5 Summary of Hazards | 7 |
| 3.0 RECOMMENDATION..... | 8 |

LIST OF TABLES

| | |
|---------|-------------------------|
| Table A | ACM Hazards Identified |
| Table B | Buildings Not Inspected |
| Table C | ACM Hazards Identified |

LIST OF APPENDICES

| | |
|------------|--|
| Appendix A | Training Certificates and Certificates of Accreditation |
| Appendix B | NAPR Map |
| Appendix C | NAPR Buildings List |
| Appendix D | Analytical Laboratory Reports for Quality Control (QC) Samples |
| Appendix E | Building-Specific Summaries |

EXECUTIVE SUMMARY

The US Navy Engineering Field Activity Northeast (EFANE) contracted Baker to perform an asbestos-containing material (ACM) inspection of 546 buildings at Naval Activity Puerto Rico (NAPR), located near Ceiba, Puerto Rico. An inspection of military family housing at NAPR was conducted simultaneously and is documented in a companion Baker report, Asbestos Inspection Report, Military Family Housing, for Naval Activity Puerto Rico, dated June 2005. The work was performed so that the federal government can transfer the properties. The Navy is considered the owner of all properties referenced in this report. The work was performed in accordance with the Scope of Work: Asbestos Survey, Naval Activity Puerto Rico, dated September 9, 2004, under Contract Number N62472-01-D-1440. Field work for the project was performed from December 1, 2004 to February 15, 2005.

The years of construction for the buildings at NAPR were not readily available. The buildings were predominantly vacant at the time of the inspections, and had served various purposes, including, but not limited to, dormitory-style housing, offices, and warehouses. The construction of the buildings varied widely, and sizes ranged from approximately 35 square feet to 131,000 square feet. The condition of the buildings ranged from poor to good.

Baker and NAPR staff were unable to locate 14 of the buildings, and three could not be accessed due to lack of keys, impassable access roads, or safety issues. In addition, 13 buildings had been removed according to NAPR staff and/or observation. Six buildings were inspected as a part of the simultaneously conducted housing inspections. A summary of this information is presented in Table B in Section 2.2.

A total of 2,006 homogeneous materials were identified during this investigation. Of those, 317 were found by laboratory analysis to be ACM, and five were assumed to be ACM due to access or safety issues that precluded sampling. The ACMs that were identified are presented in the building-specific sections of the report, which are included in Appendix E.

Base Realignment and Closure (BRAC) policy considers ACM to be a hazard when it meets all three of the following conditions: friable, accessible, and damaged. Several ACM hazards were identified in the buildings. Table A below summarizes those hazards.

| Table A. ACM Hazards Identified | | |
|--|-----------------------------|-----------------|
| Building Number | Material | Quantity |
| 31 | Pipe Insulation | 2 lf |
| 296 | Pipe Insulation | 20 lf |
| 426 | Duct Insulation | 34 sf |
| 598 | Pipe Insulation | 6 lf |
| 1686 | Pipe and Fitting Insulation | 1 lf |

Recommendations include the following: 1) The ACM hazards identified should be remedied prior to transfer of the properties. 2) The information on the presence and location of all ACMs should be communicated to the property transferee. 3) If renovation or demolition of buildings is scheduled, a more comprehensive ACM inspection should be conducted to attempt to identify hidden ACM (e.g., behind walls, above ceilings, etc.) that would not have been identified during this non-destructive, baseline study. Also, prior to renovation or demolition, ACM removal and disposal activities must be completed in accordance with EPA, Puerto Rico OSHA, Puerto Rico EQB, and other applicable federal and local regulations.

1.0 INTRODUCTION

The US Navy Engineering Field Activity Northeast (EFANE) contracted Baker to perform an asbestos-containing material (ACM) inspection of 546 buildings at Naval Activity Puerto Rico (NAPR), located near Ceiba, Puerto Rico. An inspection of military family housing at NAPR was conducted simultaneously and is documented in a companion Baker report, Asbestos Inspection Report, Military Family Housing, for Naval Activity Puerto Rico, dated June 2005. The work was performed so that the federal government can transfer the properties. The Navy is considered the owner of all properties referenced in this report. The work was performed in accordance with the Scope of Work: Asbestos Survey, Naval Activity Puerto Rico, dated September 9, 2004, under Contract Number N62472-01-D-1440. Field work for the project was performed from December 1, 2004 to February 11, 2005.

The body of the report is followed by the following appendices that contain supporting data:

- Appendix A contains copies of training certificates for the Baker and Environmental Development and Sustainability, Inc. (EDS, Baker subcontractor) staff who conducted the investigation and the certificates of accreditation for the laboratories that conducted sample analysis.
- Appendix B contains an NAPR map that shows building locations
- Appendix C contains a list of the buildings that were included in the scope of work
- Appendix D contains the analytical laboratory results for the quality control (QC) samples that were collected

Appendix E of this report contain building-specific summaries. These sections include a brief description of the number/type of suspect materials and ACM identified, summary tables of identified homogeneous materials and ACMs, photographs, sample location / ACM location drawings, and analytical laboratory reports.

All of the photographs that are presented in this report are included on a CD that accompanies this report. In addition, all ACM data presented in this report is included in three excel files on a CD that accompanies this report.

While preparing this report, Baker consulted the following regulations, guidance documents and

policies:

- 29 CFR 1926.1101 - OSHA Asbestos Construction Standard
- 40 CFR 763 - Asbestos Hazard Emergency Response Act (AHERA) and Asbestos School Hazard Reauthorization Act (ASHARA) as Amended
- Puerto Rico Environmental Quality Board Regulation for the Control of Atmospheric Pollution, Rules 102, 422, and 501
- 41 CFR 101-47 – General Services Administration Federal Property Management Regulations: Utilization and Disposal of Real Property
- 15 United States Code 2680, 2681 and 2688 -Toxic Substances Control Act
- Department of Defense (DoD) Base Realignment and Closure Act (BRAC) Policy on Asbestos, Lead Paint and Radon Policies at BRAC Properties (October 31, 1994)
- EPA 560/5-85-030a – *Asbestos in Buildings: Simplified Sampling Scheme for Friable Surfacing Materials*

1.1 Buildings Overview

The years of construction for the buildings at NAPR were not readily available. The buildings were predominantly vacant at the time of the inspections, and had served various purposes, including, but not limited to, dormitory-style housing, offices, and warehouses. The construction of the buildings varied widely, and sizes ranged from approximately 35 square feet to 131,000 square feet. The condition of the buildings ranged from poor to good.

2.0 ASBESTOS-CONTAINING MATERIAL INSPECTION

2.1 Regulatory Background

In the 1970s and 1980s, the EPA banned the use of asbestos-containing spray-on materials, molded and wet applied asbestos, asbestos-containing thermal system insulation, and asbestos in acoustical or decorative applications. As of 1989, the EPA planned to ban the use of asbestos in other products. The

ban was originally designed to be put into place in three phases; however, in 1991 the EPA ban was repealed. Because of the repeal, only the first stage of the ban was implemented. Products included in the first phase of the ban were felt products and asbestos cement products.

Several federal regulations pertain to managing ACMs. AHERA, 40 CFR 763 Subpart E, is perhaps the most well known asbestos regulation. The EPA developed AHERA to protect children in the United States from deteriorating ACMs in school buildings. AHERA was enacted in 1986 and required school systems to identify ACMs in all of their school buildings. AHERA also required school systems to develop management plans for the ACMs identified in schools and established reporting and record keeping requirements for educational authorities. Although AHERA is applicable only to schools, many of the accreditation requirements and sampling methodologies established by the act have been incorporated into the asbestos inspection industry's procedures. ASHARA requires individuals working in public or commercial buildings to be AHERA accredited if they are performing ACM abatement projects, supervising ACM abatement projects, designing ACM abatement projects, or inspecting building for ACMs. The EPA NESHAPS requires inspections for ACM prior to renovation or demolition of structures, except for residential buildings with four or fewer dwelling units. NESHAPS contains work practice and disposal requirements for regulated ACM, which is defined as ACM that is friable or that is likely to become friable during renovation or demolition activities. The definition of a friable material is one that can be crushed, pulverized, or reduced to powder under hand pressure when dry. The definition of a non-friable material is one that cannot be crushed, pulverized, or reduced to powder under hand pressure when dry.

The Puerto Rico Environmental Quality Board (EQB) regulates ACM inspection, management, removal, and disposal activities. The majority of the regulations are found in the EQB's Regulation for the Control of Atmospheric Pollution Rules 102, 422, and 501. The rules require permits, notifications, training, and work plan submissions to EQB, among other items.

OSHA developed the Occupational Exposure to Asbestos regulation to help protect workers from asbestos hazards. The regulation defined Class I through IV asbestos work, established asbestos exposure limits, and implemented asbestos worker protection requirements. Unlike the EPA's regulations, the OSHA regulation was specifically written to protect workers rather than the public. The Puerto Rico Occupational Safety and Health Administration has adopted the federal standard.

Baker reviewed the Federal Property Management Regulations 41 CFR 101-47.304-13 and BRAC policy to identify regulations and guidelines for transferring properties with ACMs. Based on the review of the information, the Navy is required to disclose all knowledge of ACMs at NAPR to any bidders or transferees. This report should be given to parties interested in the NAPR buildings and will serve as the disclosure vehicle. As stated in the Federal Property Management Regulations, any bidders on NAPR buildings should be provided with a “Notice of the Presence of Asbestos—Warning!”. The notice can be found in 41 CFR 101-47.304-13.

2.2 Methodology

Baker reviewed several previous ACM reports that had been prepared by others for several of the NAPR buildings. However, Baker elected to not utilize these reports due to their age. Therefore, the inspections were approached as if the buildings had never been inspected.

Baker, with assistance from Environmental Development and Sustainability, Inc., conducted the asbestos inspections in accordance with AHERA, ASHARA and OSHA asbestos regulations during the period of December 1, 2004 to February 15, 2005. NAPR staff assisted in locating buildings and providing access. AHERA-accredited asbestos inspectors identified building materials that could contain asbestos. Building materials were then grouped into homogeneous materials. Homogeneous materials are defined as building materials similar in age, appearance, and texture. The asbestos inspectors then collected representative bulk material samples from each homogeneous material in general accordance with AHERA guidelines. Insulation materials that appeared to be composed of fiberglass were not considered potential (i.e., suspect) ACM. For each homogeneous material, the material description, location(s), approximate quantity, friability, condition, accessibility, and potential for damage were recorded.

In accordance with the Scope of Work, the number of samples for each homogeneous material was based on the quantity of homogeneous material present throughout the building, as follows:

- \leq 1000 square feet – 3 samples
- \leq 5000 square feet – 5 samples
- $>$ 5000 square feet – 7 samples

Sample results from a homogeneous material represent the asbestos content for the homogeneous material throughout each particular building, regardless of the sample locations.

As per the scope of work, Baker sampled wallboard and associated joint compound as a composite material. The results are reported for individual layers as well as for the composite material.

Bulk building material samples were sent to Schneider Labs for analysis using polarized light microscopy with dispersion staining. Schneider Labs is accredited for asbestos analysis through the National Voluntary Laboratory Accreditation Program (NVLAP). Homogeneous materials were analyzed until a positive identification of asbestos was made or until all samples of the material were determined to contain less than or equal to 1 percent asbestos. Samples found to contain detectable, but less than 1 percent asbestos, were further analyzed by point count methodology to more accurately define their asbestos content. Quality Control (QC) samples, one per 10 bulk samples, were collected in accordance with the Scope of Work and were analyzed by RJ Lee Group, Inc., another NVLAP accredited laboratory. QC sample results were generally consistent with bulk sample results. However, where conflicting lab results were indicated (i.e., one lab found the material to contain greater than 1 percent asbestos and the other did not), the material was considered to be ACM. Laboratory reports are included in the building-specific summaries. Laboratory reports for QC samples are included in Appendix D. Inspector and laboratory certifications are included in Appendix A.

Table B below shows the buildings that: 1) were inspected as a part of the simultaneously conducted housing inspections (Project 15); 2) were removed according to NAPR staff and/or observation; 3) could not be located by Baker and NAPR staff; and 4) could not be accessed due to lack of keys, impassable access roads, or safety issues.

Table B. Buildings Not Inspected

| Included in Housing Inspections | Removed | Could Not Be Located | Could Not Be Accessed |
|--|----------------|-----------------------------|------------------------------|
| 889 | 871 | 157 | 38* |
| 891 | 2003 | 247 | 500 (partial) |
| 893 | 2191 | 2222 | 774 (partial) |
| 895 | 2224 | 2314 | 2439 |
| 897 | 2388 | 2389 | 3006 |
| 899 | 2424 | 2395 | |
| | 2438 | 2442 | |
| | 2488 | 2455 | |
| | 2496 | 2582 | |
| | 2508 | 2583 | |
| | 2564 | 3150 | |
| | 2601 | 6000 | |
| | 2685 | 6001 | |
| | | 6003 | |

* In December 2004, Baker requested that Building 38 be removed from the scope of work due to health and safety issues related to the following: no lighting, PCB-contaminated concrete and soil, dilapidated floors, bat infestation and related bat waste, water-filled trenches, and extensive ACM debris. EFANE indicated that Building 38 is part of another on-going environmental investigation, and agreed that Building 38 could be removed from the scope of work.

2.3 Disclaimer

Baker was contracted to perform an ACM inspection of NAPR buildings that would meet the requirements of an Operations and Maintenance Program for ACMs. As such, the inspection was not destructive and did not involve breaking into pipe chases, interstitial spaces or other inaccessible building areas. Therefore, ACMs may exist within inaccessible building areas. The presence or absence of ACMs applies only to materials sampled on the dates of the field visit. It should be noted that conditions might change due to vandalism, deterioration, or maintenance activities. Ongoing monitoring by the owner or transferee is necessary. If additional materials suspected of containing asbestos are identified during renovation or demolition activities, they should be assumed to be ACMs or should be sampled and analyzed before being disturbed.

2.4 Summary of Asbestos-Containing Materials

A total of 2,006 homogeneous materials were identified. Of those, 317 were found by laboratory analysis to be ACM, and five were assumed to be ACM due to access or safety issues that precluded sampling. By definition, an ACM contains greater than 1 percent asbestos. Table 1 in each building section indicates all of the suspect homogeneous materials that were identified for that particular building. Table 2 in each building section provides the following information on each of the identified ACMs: homogeneous material number, material description, asbestos percentage and type, friability, location, condition, and comments.

2.5 Summary of Hazards

Base Realignment and Closure (BRAC) policy considers an ACM to be a hazard when it meets all three of the following conditions: friable, accessible, and damaged. Friable, accessible, and damaged ACM that were identified are presented in Table 3 in each building section. A summary of all friable, accessible, and damaged ACM identified is presented in Table C below.

| Table C. ACM Hazards Identified | | |
|--|-------------------------------------|-----------------|
| Building Number | Material | Quantity |
| 31 | Pipe Insulation | 2 lf |
| 296 | Pipe Insulation | 20 lf |
| 426 | Duct Insulation | 34 sf |
| 598 | Pipe Insulation | 6 lf |
| 1686 | Pipe and Pipe Fitting Insulation | 1 lf |


3.0 RECOMMENDATIONS

- The information on the presence and location of all ACMs should be communicated to the property transferee.
- The ACM hazards identified should be remedied prior to transfer of the properties.
- If renovation or demolition of buildings is scheduled, a more comprehensive ACM inspection should be conducted to attempt to identify hidden ACM (e.g., behind walls, above ceilings, etc.) that would not have been identified during this non-destructive, baseline study. Also, prior to renovation or demolition, ACM removal and disposal activities must be completed in accordance with EPA, Puerto Rico OSHA, Puerto Rico EQB, and other applicable federal and local regulations.

Final
**Lead-Based Paint Inspection/
Risk Assessment Report**

for
Military Family Housing
Naval Activity Puerto Rico
Ceiba, Puerto Rico
Volume I of II
(Text and Appendices A through E)

Contract N62472-01-D-1440 • Project Number 15 • June 2005



Prepared by
Michael Baker Jr., Inc.

Baker

ChallengeUs.

Under Contract with
Department of the Navy
Naval Facilities Engineering Command
Engineering Field Activity, Northeast



TABLE OF CONTENTS

| | <u>Page</u> |
|---|-------------|
| EXECUTIVE SUMMARY | ES-1 |
| 1.0 INTRODUCTION | 1 |
| 1.1 Housing Community Overview | 2 |
| 2.0 LEAD-BASED PAINT INSPECTION | 5 |
| 2.1 Regulatory Background | 5 |
| 2.2 Methodology | 6 |
| 2.3 Selecting Units for Inspection..... | 7 |
| 2.4 Disclaimer | 11 |
| 2.5 Results | 11 |
| 3.0 LEAD-BASED PAINT RISK ASSESSMENT | 12 |
| 3.1 Regulatory Background | 12 |
| 3.2 Methodology | 12 |
| 3.3 Selecting Units for Assessment | 13 |
| 3.4 Summary of Hazards | 13 |

LIST OF TABLES

(Within Text)

| | |
|---------|---|
| Table A | Renovation History for NAPR Housing |
| Table B | Summary of LBP Issues at NAPR Housing |
| Table C | Renovation History for NAPR Housing |
| Table D | Lead-Based Paint Hazard Reduction Act (Title X) |
| Table E | Units Selected for LBP Inspection at NAPR Housing |
| Table F | LBP Hazards Identified in LBP Risk Assessed Units at NAPR Housing |

(Following Text)

| | |
|-------------|---|
| Tables 1-8 | Summary of LBP Results for NAPR Housing |
| Table 9 | Summary of LBP Results by Housing Community |
| Table 10-13 | Summary of LBP Hazards for NAPR Housing |

LIST OF APPENDICES

| | |
|------------|--|
| Appendix A | NAPR Map and Floor Plans |
| Appendix B | Training Certificates, Licenses, and Certificates of Accreditation |
| Appendix C | Performance Characteristic Sheet, XRF Analyzer Calibration Data |
| Appendix D | Analytical Laboratory Reports |
| Appendix E | Photographs |
| Appendix F | Paint, Soil, Dust, and Building Condition Data |

EXECUTIVE SUMMARY

The US Navy Engineering Field Activity Northeast contracted Baker to perform lead-based paint (LBP) inspections and LBP risk assessments in military family housing at Naval Activity Puerto Rico (NAPR), located near Ceiba, Puerto Rico. The work was performed so that the federal government can transfer the properties. The Navy is considered the owner of all properties referenced in this report. The work was performed in accordance with the Scope of Work: Lead-Based Paint Inspection and Risk Assessment, and Asbestos Survey For Residential Property Transfer, dated September 9, 2004, under Contract Number N62472-01-D-1440. Field work for the project was performed from January 5, 2005 to February 11, 2005.

NAPR housing was reportedly constructed between 1960 and 1975 and contains 962 two, three, and four-bedroom apartment style, duplex, and single-family housing units. NAPR housing consists of eight communities: Algodones, Caribe Breeze, Cascajo Point, Coast Guard, FDR Drive, Manatee Bay, Mangrove Manor, and Rainbow Hill. Twenty-seven of the housing units in Manatee Bay are of original construction, while the remaining 935 units were renovated to varying degrees beginning in 1989. The square footage of the units ranges from 1023 to 2105 square feet. The concrete-framed buildings have concrete or ceramic exterior finishes. Interior walls are painted gypsum board and concrete. The units are generally in good condition.

Table A below summarizes the renovation history for the communities, as provided by the housing office manager.

| Table A. Renovation History for NAPR Housing | | | | |
|--|--|----------------|-------------------|--|
| Address of Units Inspected | Style of Housing | Date of Const. | Date(s) of Renov. | Description of Renovation |
| Algodones | | | | |
| 889C, 889E, 889F, 889G, 889H, 891A, 891D, 893B, 893C, 895A, 895B, 895C, 897A, 897B, 897D, 897F, 897G, 897H, and 899B | Two, Three, and Four Bedroom Apartment-Style Units | 1960 | 1991 | <ul style="list-style-type: none"> ● Installation of carpeting ● Remodel bathrooms and kitchens ● Replace doors and windows |

| Table A. Renovation History for NAPR Housing | | | | |
|---|--|-----------------------|--------------------------|--|
| Address of Units Inspected | Style of Housing | Date of Const. | Date(s) of Renov. | Description of Renovation |
| Caribe Breeze | | | | |
| 1A, 2C, 5B, 6B, 10D, 11A, 15A, 16B, 17C, 20A, 20B, 21B, 25C, 25A, 28A, 31B, 34B, 35A, 37A, 38B, 39C, 43B, and 47A American Circle 92A Saratoga Road 1B and 4B Point Cruz | Two, Three, and Four Bedroom Duplex Units | 1974 | 2001 - 2003 | <ul style="list-style-type: none"> • Remove LBP and ACM • Repaint all walls inside and outside • Replace vinyl floor tile with ceramic tile • Replace A/C ductwork and central A/C units • Upgrade electrical systems • Replace entrance doors • Reconfigure outside storage areas and A/C mechanical rooms • Replace kitchen cabinets • Replace bathroom fixtures and tiles • Reconfigure master bedrooms and bathroom • Replace windows • Install ceiling fans • Replace carpeting in upstairs of 2-bedroom units |
| Cascajo Point | | | | |
| 6, 11, 16, 21, 24, 30, and 31 FDR Drive 6 Bataan Drive 5 and 14 San Jacinto Road 4, 7, and 13 Cowrens Drive 4, 5, 13, 14, 19, 26, 29, 30, and 43 Monterey Road 2, 5, 12, and 14 Cabot Lake | Two, Three and Four Bedroom Single Family Houses | 1960 | 1998 - 2001 | <ul style="list-style-type: none"> • Remove LBP and ACM • Construct screened-in porches • Repaint all walls inside and outside • Replace vinyl floor tile with ceramic tile • Replace A/C ductwork and central A/C units • Upgrade electrical systems • Replace kitchen cabinets • Remodel laundry areas • Replace bathroom fixtures and tiles • Reconfigure master bedrooms and bathroom • Install ceiling fans |
| Coast Guard | | | | |
| 1675, 1676, 1677, 1678, 1679, and 1680 Intrepid Street | Three and Four Bedroom Single Family Houses | 1960 | 1989 - 1992 | <ul style="list-style-type: none"> • Replace floors tiles • Replace kitchen cabinets • Install central A/C • Replace aluminum jealousy windows with French type glass louvered windows |
| FDR Drive | | | | |
| 1, 3, and 5 FDR Drive | Three Bedroom Single Family Houses | 1960 | 1999 - 2000 | <ul style="list-style-type: none"> • Remove LBP and ACM • Replace carpeting • Repaint all walls inside and outside • Replace A/C ductwork • Reconfigure mechanical room • Upgrade electrical systems • Replace kitchen floors and cabinets • Remodel bathrooms including replace bathroom fixtures (not 1 FDR) • Install ceiling fans |

| Table A. Renovation History for NAPR Housing | | | | |
|--|---|-----------------------|--------------------------|--|
| Address of Units Inspected | Style of Housing | Date of Const. | Date(s) of Renov. | Description of Renovation |
| Manatee Bay | | | | |
| 6 and 7 Intrepid Street 8, 11, 20, 36, 38, 49, 52, and 60 Ranger Road 2 and 20 Hancock Circle 4 and 15 Coral Sea Drive 3 and 18 Franklin Drive 8, 19, and 26 Hornet Road 3, 11, 21, 32, and 35 Yorktown Circle 67, 74, and 81 Lexington Drive | Two, Three and Four Bedroom Single Family Houses | 1960 | 2001 - 2003 | <ul style="list-style-type: none"> • Remove LBP and ACM • Construct screened-in porches • Repaint all walls inside and outside • Replace vinyl floor tile with ceramic tile • Replace A/C ductwork and central A/C units • Upgrade electrical systems • Reconfigure kitchens and replace kitchen cabinets • Remodel laundry areas • Replace bathroom fixtures and tiles • Reconfigure master bedrooms and bathroom • Install ceiling fans |
| Mangrove Manor | | | | |
| 11, 12, 19, 20, 31, 38, 50, 68, and 82 Saratoga Road 2, 11, and 17 Essex Drive 6 Ticonderoga Street 18, 25, 34, 41, and 54 Enterprise Drive 9, 26, 33, 46, and 47 Lexington Drive 6, 15, and 32 Wasp Circle 7 Bunker Hill Road | Two, Three and Four Bedroom Single Family Houses | 1960 | 1989 - 1992 | <ul style="list-style-type: none"> • Same as Coast Guard |
| Rainbow Hill | | | | |
| 2A, 4A, 4B, 5B, 7A, 8A, 10C, 13B, 14B, 15B, 16A, 18A, 19C, 20B, 22B, 23A, 24A, 27A, 28B, 29B, 32A, 33B, 34A, and 36A Nimitz Drive | Two, Three, and Four Bedroom Duplex and Apartment-Style Units | 1975 | 1998 - 2001 | <ul style="list-style-type: none"> • Same as Caribe |

In accordance with Department of Housing and Urban Development (HUD) regulations, the Navy is required to inspect and assess NAPR Housing for LBP and LBP hazards and disclose the results of the inspection and assessment to the next owner. The risk assessment must occur no more than 12 months prior to property transfer. Because the housing units were constructed in 1960 and later, LBP hazards are not required to be abated before the sale of the properties.

Baker was unable to obtain previous LBP reports for the properties. It is not known whether LBP inspections and/or risk assessments were previously conducted.

Baker performed LBP inspections in 19 of 32 Algodones housing units, 26 of 136 Caribe Breeze housing units, 26 of 139 Cascajo Point housing units, all six Coast Guard housing units, all three FDR Drive housing units, 26 of 262 Manatee Bay housing units, 27 of 275 Mangrove Manor housing units, and 24 of 88 Rainbow Hill housing units in accordance with the Scope of Work. All of the units were vacant at the time of the inspections. The inspections were performed in accordance with federal regulations. Refer to Table C for a listing of LBP components identified.

Baker also performed LBP risk assessments in the same units in which LBP inspections were conducted. The risk assessments were performed in accordance with federal regulations. LBP hazards were only identified in the Algodones, Coast Guard, Manatee Bay, and Mangrove Manor housing communities, and include deteriorated LBP on various components and slightly elevated lead in dust on floors. Hazards related to friction surfaces, impact surfaces, chewable surfaces, and soil were not identified in these communities. No LBP hazard of any type was identified in the Caribe Breeze, Cascajo Point, FDR Drive, and Rainbow Hill housing communities. Table B summarizes the LBP-related issues for NAPR Housing housing. Tables 1-13 following the text of this report expand upon the information in this table.

| Table B. Summary of LBP Issues at NAPR Housing | | |
|--|---|----------------------------------|
| Community Addresses | Assessed Units | LBP-containing Components |
| | | LBP Hazards |
| Algodones | | |
| 889A-H 891A-D 893A-D 895A-D 897A-H 899A-D | 889C, 889E, 889F, 889G, 889H, 891A, 891D, 893B, 893C, 895A, 895B, 895C, 897A, 897B, 897D, 897F, 897G, 897H, and 899B | None Identified |
| | | Dust – Floors |
| Caribe Breeze | | |
| 1A-47B American Circle 84-92 Saratoga Road 1-4 Point Cruz | 1A, 2C, 5B, 6B, 10D, 11A, 15A, 16B, 17C, 20A, 20B, 21B, 25C, 25A, 28A, 31B, 34B, 35A, 37A, 38B, 39C, 43B, and 47A American Circle 92A Saratoga Road 1B and 4B Point Cruz | Concrete Wall |
| | | None Identified |

| Table B. Summary of LBP Issues at NAPR Housing | | |
|---|--|--|
| Community Addresses | Assessed Units | LBP-containing Components |
| | | LBP Hazards |
| Cascajo Point | | |
| 4-31 FDR Drive 1-8 Bataan Drive 1-20 San Jacinto Road 1-19 Cowrens Drive 1-55 Monterey Road 1-26 Cabot Lake | 6, 11, 16, 21, 24, 30, and 31 FDR Drive 6 Bataan Drive 5 and 14 San Jacinto Road 4, 7, and 13 Cowrens Drive 4, 5, 13, 14, 19, 26, 29, 30, and 43 Monterey Road 2, 5, 12, and 14 Cabot Lake | None Identified |
| | | None Identified |
| Coast Guard | | |
| 1675, 1676, 1677, 1678, 1679, and 1680 Intrepid Street | Same | Wood Ceiling, Wood Door Casing/Jamb/Stop, Wood Door, Wood Folding Door Casing, Wood Folding Door, Wood Shelf/Coat Rack, Wood Shelf/Shelf Support, Wood Sliding Door Casing, Wood Sliding Door, Concrete Wall, and Drywall Wall |
| | | Deteriorated Paint – Wood Door Casing/Jamb/Stop Dust - Floors |
| FDR Drive | | |
| 1, 3, and 5 FDR Drive | Same | None Identified |
| | | None Identified |
| Manatee Bay | | |
| 1-20 Intrepid Street 1-60 Ranger Road 1-28 Hancock Circle, 1-37 Coral Sea Drive 1-18 Franklin Drive 1-26 Homet Road 1-54 Yorktown Circle 67-93 Lexington Drive | 6 and 7 Intrepid Street 8, 11, 20, 36, 38, 49, 52, and 60 Ranger Road 2 and 20 Hancock Circle 4 and 15 Coral Sea Drive 3 and 18 Franklin Drive 8, 19, and 26 Homet Road 3, 11, 21, 32, and 35 Yorktown Circle 67, 74, and 81 Lexington Drive | None Identified |
| | | Dust – Floors |
| Mangrove Manor | | |
| 1-82 Saratoga Road, 1-22 Essex Drive 1-12 Ticonderoga Street 1-60 Enterprise Drive 1-58 Lexington Drive 1-38 Wasp Circle 1-8 Bunker Hill Road | 11, 12, 19, 20, 31, 38, 50, 68, and 82 Saratoga Road 2, 11, and 17 Essex Drive 6 Ticonderoga Street 18, 25, 34, 41, and 54 Enterprise Drive 9, 26, 33, 46, and 47 Lexington Drive 6, 15, and 32 Wasp Circle, 7 Bunker Hill Road | Wood Door Casing/ Jamb/Stop, Wood Door, Ceramic Exterior Wall, Wood Sliding Door, and Wood Window Sash |
| | | Dust – Floors |
| Rainbow Hill | | |
| 1A-36B Nimitz Drive | 2A, 4A, 4B, 5B, 7A, 8A, 10C, 13B, 14B, 15B, 16A, 18A, 19C, 20B, 22B, 23A, 24A, 27A, 28B, 29B, 32A, 33B, 34A, and 36A Nimitz Drive | None Identified |
| | | None Identified |

Table B. Summary of LBP Issues at NAPR Housing

For NAPR Housing:

Actions:

1) Test the components in/on the remaining 804 units that were not inspected for LBP, determine which components contain LBP, and assess for LBP hazards,

Or

2) Assume all like components contain LBP and assess the other 804 units for LBP hazards

HUD requires that LBP hazards be abated in housing constructed prior to 1960. Because the housing units that were the subject of this study were reportedly constructed in 1960 or later, abatement of the identified LBP hazards is not required by HUD.

Control options are nevertheless listed below.

Control options for deteriorated LBP include:

- Paint Film Stabilization (considered an interim control)
- Encapsulation
- Enclosure
- Paint Removal
- Building Component Replacement

Control options for dust include:

- Dust Removal
- Cover Bare Soil

Control options for soil include:

- Plant Grass or Sod
- Cover with Mulch
- Pave Over
- Soil Removal

Other recommendations include: 1) The property transferee should be made aware of the presence of LBP and LBP hazards in the housing units, 2) Contractors who disturb LBP should comply with the requirements of the Puerto Rico Occupational Safety & Health Administration (OSHA) Lead Standard, which mirrors the federal OSHA standard (29 CFR 1926.62).

1.0 INTRODUCTION

The US Navy Engineering Field Activity Northeast contracted Baker to perform lead-based paint (LBP) inspections and LBP risk assessments in military family housing at Naval Activity Puerto Rico (NAPR), located near Ceiba, Puerto Rico. The work was performed so that the federal government can transfer the properties. The Navy is considered the owner of all properties referenced in this report. The work was performed in accordance with the Scope of Work: Lead-Based Paint Inspection and Risk Assessment, and Asbestos Survey For Residential Property Transfer, dated September 9, 2004, under Contract Number N62472-01-D-1440. Field work for the project was performed from January 5, 2005 to February 11, 2005.

The body of the report is followed by the following appendices that contain supporting data:

- Appendix A contains a map of NAPR that shows the locations of each of the housing communities, and floor plans of each style of housing unit that was inspected.
- Appendix B contains inspector training certificates, company licenses, and laboratory certificates of accreditation.
- Appendix C contains the Niton XRF Analyzer Performance Characteristic Sheet and XRF analyzer calibration data.
- Appendix D contains analytical laboratory reports.
- Appendix E contains photographs pertinent to the LBP inspection. A CD that includes all of these photographs accompanies this report.
- Appendix F contains paint, soil sample, dust sample, and building condition data.

While preparing this report, Baker consulted the following regulations, guidance documents and policies:

- 24 CFR 35, Subparts A, B, C and R -Department of Housing and Urban Development (HUD) LBP Requirements.

- 29 CFR 1926.62 -Occupational Safety and Health Administration (OSHA) Lead Construction Standard.
- 40 CFR 745, Subparts D, L, and Q -Environmental Protection Agency (EPA) LBP Requirements.
- 41 CFR 101-47 – General Services Administration Federal Property Management Regulations: Utilization and Disposal of Real Property.
- 15 United States Code 2680, 2681 and 2688 -Toxic Substances Control Act.
- Department of Defense (DoD) Base Realignment and Closure Act (BRAC) Policy on Asbestos, Lead Paint and Radon Policies at BRAC Properties (October 31, 1994).
- HUD Guidelines 1995: Chapters 5 and 7, 1997 Revision.
- American Society for Testing and Materials E-6 -Standards for Lead.
- EPA 747-R-95-001 *Residential Sampling for Lead: Protocols for Dust and Soil Sampling*, March 1995.
- Puerto Rico Environmental Quality Board (EQB) Lead Regulations.

1.1 Housing Community Overview

NAPR housing was reportedly constructed between 1960 and 1975 and contains 962 two, three, and four-bedroom apartment style, duplex, and single family units. NAPR housing consists of eight communities: Algodones, Caribe Breeze, Cascajo Point, Coast Guard, FDR Drive, Manatee Bay, Mangrove Manor, and Rainbow Hill. Twenty-seven of the housing units in Manatee Bay are of original construction, while the remaining 935 units were renovated to varying degrees beginning in 1989. The square footage of the units ranges from 1023 to 2105 square feet. The concrete-framed buildings have concrete or ceramic exterior finishes. Interior walls are painted gypsum board and concrete. The units are generally in good condition.

Table C below summarizes the renovation history for the communities, as provided by the housing office manager.

| Table C. Renovation History for NAPR Housing | | | | |
|---|--|-----------------------|--------------------------|--|
| Address of Units Inspected | Style of Housing | Date of Const. | Date(s) of Renov. | Description of Renovation |
| Algodones | | | | |
| 889C, 889E, 889F, 889G, 889H, 891A, 891D, 893B, 893C, 895A, 895B, 895C, 897A, 897B, 897D, 897F, 897G, 897H, and 899B | Two, Three, and Four Bedroom Apartment-Style Units | 1960 | 1991 | <ul style="list-style-type: none"> ● Installation of carpeting ● Remodel bathrooms and kitchens ● Replace doors and windows |
| Caribe Breeze | | | | |
| 1A, 2C, 5B, 6B, 10D, 11A, 15A, 16B, 17C, 20A, 20B, 21B, 25C, 25A, 28A, 31B, 34B, 35A, 37A, 38B, 39C, 43B, and 47A American Circle 92A Saratoga Road 1B and 4B Point Cruz | Two, Three, and Four Bedroom Duplex Units | 1974 | 2001 - 2003 | <ul style="list-style-type: none"> ● Remove LBP and ACM ● Repaint all walls inside and outside ● Replace vinyl floor tile with ceramic tile ● Replace A/C ductwork and central A/C units ● Upgrade electrical systems ● Replace entrance doors ● Reconfigure outside storage areas and A/C mechanical rooms ● Replace kitchen cabinets ● Replace bathroom fixtures and tiles ● Reconfigure master bedrooms and bathroom ● Replace windows ● Install ceiling fans ● Replace carpeting in upstairs of 2-bedroom units |
| Cascajo Point | | | | |
| 6, 11, 16, 21, 24, 30, and 31 FDR Drive 6 Bataan Drive 5 and 14 San Jacinto Road 4, 7, and 13 Cowrens Drive 4, 5, 13, 14, 19, 26, 29, 30, and 43 Monterey Road 2, 5, 12, and 14 Cabot Lake | Two, Three and Four Bedroom Single Family Houses | 1960 | 1998 - 2001 | <ul style="list-style-type: none"> ● Remove LBP and ACM ● Construct screened-in porches ● Repaint all walls inside and outside ● Replace vinyl floor tile with ceramic tile ● Replace A/C ductwork and central A/C units ● Upgrade electrical systems ● Replace kitchen cabinets ● Remodel laundry areas ● Replace bathroom fixtures and tiles ● Reconfigure master bedrooms and bathroom ● Install ceiling fans |
| Coast Guard | | | | |
| 1675, 1676, 1677, 1678, 1679, and 1680 Intrepid Street | Three and Four Bedroom Single Family Houses | 1960 | 1989 - 1992 | <ul style="list-style-type: none"> ● Replace floors tiles ● Replace kitchen cabinets ● Install central A/C ● Replace aluminum jealously windows with French type glass louvered windows |
| FDR Drive | | | | |
| 1, 3, and 5 FDR Drive | Three Bedroom Single Family Houses | 1960 | 1999 - 2000 | <ul style="list-style-type: none"> ● Remove LBP and ACM ● Replace carpeting ● Repaint all walls inside and outside ● Replace A/C ductwork ● Reconfigure mechanical room ● Upgrade electrical systems ● Replace kitchen floors and cabinets ● Remodel bathrooms including replace bathroom fixtures (not 1 FDR) ● Install ceiling fans |

| Table C. Renovation History for NAPR Housing | | | | |
|--|---|-----------------------|--------------------------|--|
| Address of Units Inspected | Style of Housing | Date of Const. | Date(s) of Renov. | Description of Renovation |
| Manatee Bay | | | | |
| 6 and 7 Intrepid Street 8, 11, 20, 36, 38, 49, 52, and 60 Ranger Road 2 and 20 Hancock Circle 4 and 15 Coral Sea Drive 3 and 18 Franklin Drive 8, 19, and 26 Hornet Road 3, 11, 21, 32, and 35 Yorktown Circle 67, 74, and 81 Lexington Drive | Two, Three and Four Bedroom Single Family Houses | 1960 | 2001 - 2003 | <ul style="list-style-type: none"> • Remove LBP and ACM • Construct screened-in porches • Repaint all walls inside and outside • Replace vinyl floor tile with ceramic tile • Replace A/C ductwork and central A/C units • Upgrade electrical systems • Reconfigure kitchens and replace kitchen cabinets • Remodel laundry areas • Replace bathroom fixtures and tiles • Reconfigure master bedrooms and bathroom • Install ceiling fans |
| Mangrove Manor | | | | |
| 11, 12, 19, 20, 31, 38, 50, 68, and 82 Saratoga Road 2, 11, and 17 Essex Drive 6 Ticonderoga Street 18, 25, 34, 41, and 54 Enterprise Drive 9, 26, 33, 46, and 47 Lexington Drive 6, 15, and 32 Wasp Circle 7 Bunker Hill Road | Two, Three and Four Bedroom Single Family Houses | 1960 | 1989 - 1992 | <ul style="list-style-type: none"> • Same as Coast Guard |
| Rainbow Hill | | | | |
| 2A, 4A, 4B, 5B, 7A, 8A, 10C, 13B, 14B, 15B, 16A, 18A, 19C, 20B, 22B, 23A, 24A, 27A, 28B, 29B, 32A, 33B, 34A, and 36A Nimitz Drive | Two, Three, and Four Bedroom Duplex and Apartment-Style Units | 1975 | 1998 - 2001 | <ul style="list-style-type: none"> • Caribe Breeze |

Floor plans of the housing units are included in Appendix A, and exterior photographs are presented in Appendix E.

2.0 LEAD-BASED PAINT INSPECTION

2.1 Regulatory Background

NAPR Housing units are federal properties and are subject to federal regulations. The DoD recognizes that the Residential Lead-Based Paint Hazard Reduction Act governs LBP activities in DoD residential housing. The Act, commonly known as Title X of the Housing and Residence Development Act of 1992 (42 United States Code 4822), requires federal departments and agencies to address lead hazards in residential properties. The following table identifies the salient sections of Title X.

| Table D. Lead-Based Paint Hazard Reduction Act (Title X) | |
|--|---|
| Section Number | Regulatory Requirement |
| 402 | Train and certify people involved in LBP activities |
| 403 | Create provisions for developing regulations for identifying LBP hazards in residential property, including standards for dust and soil |
| 1013 | Inspect and abate LBP hazards in all federally owned target housing constructed prior to 1960 when transferring property. Inspect all federally owned target housing constructed between 1960-1977 for LBP and LBP hazards when transferring property |
| 1012 and 1013 | Directs HUD to issue regulations requiring LBP inspections, risk assessments and interim controls and abatement of LBP hazards in federally owned target housing and target housing receiving federal assistance when transferring property |
| 1018 | Disclose known LBP and LBP hazards before sale or lease of federally owned and federally assisted housing |

HUD and the EPA developed regulations to implement Title X. The implementing regulations are 24 CFR 35 and 40 CFR 745. Within 24 CFR 35, Subpart A describes disclosure responsibilities, Subpart B provides definitions and establishes programs, Subpart C addresses federal property transfers and Subpart R establishes methods and standards for assessing LBP hazards. Within 40 CFR 745, Subpart D provides information on identifying dangerous levels of lead and Subpart L establishes the HUD guidelines as the criteria for performing risk assessments and creating risk assessment reports.

Baker reviewed BRAC policy and HUD regulations to identify the requirements for transferring properties with LBP. Based on the review of the information, the Navy is not required to abate LBP hazards at NAPR Housing, or insure that the purchaser abates LBP hazards prior to use as

target housing. However, the Navy is required to disclose all knowledge of LBP and LBP hazards at NAPR Housing to any bidders or transferees. This report should be given to parties interested in NAPR Housing and will serve as the disclosure vehicle. The results of the LBP inspection and LBP risk assessment should be incorporated into the Environmental Baseline Survey of NAPR Housing. The LBP inspection and risk assessment should be referenced in the Findings of Suitability for Transfer as well as the deed or contract for sale of NAPR Housing.

The Puerto Rico EQB requires licensing of firms and individuals involved in inspection, assessment, and abatement of LBP. It also requires notification and permitting procedures for LBP abatement projects.

HUD regulations were followed for the disposition of residential property owned by a federal agency other than HUD. Puerto Rico EQB and/or EPA-accredited LBP Inspectors/Risk Assessors performed all work for this project.

2.2 Methodology

This LBP inspection involved testing paint for lead using an x-ray fluorescence (XRF) analyzer. According to EPA and HUD guidelines, XRF testing is an acceptable technology to determine the concentration of lead in paint. Baker subcontracted the services of Environmental Development and Sustainability, Inc. (EDS) of Catano, Puerto Rico to conduct the XRF testing. Baker is located at 100 Airside Drive, Moon Township, Pennsylvania, 15108, telephone number (412) 269-6300. EDS is located at Las Nereidas St., Cond. Bahia Court, #1, Catano, Puerto Rico, 00962, telephone number (787) 788-7644. Mr. Ramon E. Ramirez and Mr. Jose Marquez, EPA/Puerto Rico EQB certified Inspectors/Risk Assessors, performed the XRF testing at Baker's direction using a Niton XRF spectrum analyzer Model Number XL-309. The analyzer has a Performance Characteristic Sheet (PCS) that defines the parameters for its use in the field; a copy of the PCS is included in Appendix C. XRF testing results by housing unit are included in Appendix F. XRF results are reported in milligrams of lead per square centimeter (mg/cm^2). According to federal and Puerto Rico EQB regulations, paint is considered lead based when XRF test results equal or exceed $1.0 \text{ mg}/\text{cm}^2$.

Each testing combination in each room equivalent was tested for lead. A room equivalent refers to a distinct room (e.g., Kitchen, Bedroom 1), while a testing combination refers to a given room, component, and substrate combination (e.g., kitchen, window sash, wood). With the exception of walls, one reading was taken on each testing combination in each room equivalent. Four readings were collected from the walls in each room equivalent, one from each wall. For each housing unit, testing combinations, paint colors, paint conditions, location(s), approximate quantities (if positive and in fair or poor condition), and XRF readings were recorded. For simplicity, all readings that were less than 0.1 mg/cm² were recorded as 0.0 mg/cm².

The identification of walls for a given room is as follows: Wall 1 is the wall that is located on the street side of the room, when in the room looking toward the street. Walls 2, 3, and 4 are the walls that are present going clockwise from Wall 1.

2.3 Selecting Units for Inspections

Per the Scope of Work, ACM inspections were performed in 19 of 32 Algodones housing units, 26 of 136 Caribe Breeze housing units, 26 of 139 Cascajo Point housing units, all six Coast Guard housing units, all three FDR Drive housing units, 26 of 262 Manatee Bay housing units, 27 of 275 Mangrove Manor housing units, and 24 of 88 Rainbow Hill housing units. NAPR Housing units selected for LBP inspection were chosen randomly. Units selected for LBP inspection are listed in Table E below. All units were vacant at the time of the inspections.

| Table E. Units Selected for LBP Inspection at NAPR Housing | |
|---|-----------------------|
| Address | Date Inspected |
| Algodones | |
| 889C | February 1, 2005 |
| 889E | February 1, 2005 |
| 889F | February 2, 2005 |
| 889G | February 2, 2005 |
| 889H | February 7, 2005 |
| 891A | February 3, 2005 |
| 891D | February 3, 2005 |
| 893B | February 3, 2005 |
| 893C | February 4, 2005 |
| 895A | February 4, 2005 |
| 895B | February 4, 2005 |
| 895C | February 4, 2005 |

| Table E. Units Selected for LBP Inspection at NAPR Housing | |
|---|-----------------------|
| Address | Date Inspected |
| Algodones | |
| 897A | February 7, 2005 |
| 897B | February 2, 2005 |
| 897D | February 2, 2005 |
| 897F | February 2, 2005 |
| 897G | February 2, 2005 |
| 897H | February 2, 2005 |
| 899B | February 1, 2005 |
| Caribe Breeze | |
| 1A American Circle | January 5, 2005 |
| 2C American Circle | January 9, 2005 |
| 5B American Circle | January 7, 2005 |
| 6B American Circle | January 7, 2005 |
| 10D American Circle | January 10, 2005 |
| 11A American Circle | January 10, 2005 |
| 15A American Circle | January 10, 2005 |
| 16B American Circle | January 10, 2005 |
| 17C American Circle | January 11, 2005 |
| 20A American Circle | January 11, 2005 |
| 20B American Circle | January 11, 2005 |
| 21B American Circle | January 12, 2005 |
| 24C American Circle | January 12, 2005 |
| 25A American Circle | January 12, 2005 |
| 28A American Circle | January 12, 2005 |
| 31B American Circle | January 12, 2005 |
| 34B American Circle | January 13, 2005 |
| 35A American Circle | January 13, 2005 |
| 37A American Circle | January 13, 2005 |
| 38B American Circle | January 14, 2005 |
| 39C American Circle | January 14, 2005 |
| 43B American Circle | January 14, 2005 |
| 47A American Circle | January 17, 2005 |
| 92A Saratoga Drive | January 17, 2005 |
| 1B Point Cruz | January 17, 2005 |
| 4B Point Cruz | January 17, 2005 |
| Casajó Point | |
| 6 FDR Drive | January 20, 2005 |
| 11 FDR Drive | January 20, 2005 |
| 16 FDR Drive | January 20, 2005 |
| 21 FDR Drive | January 20, 2005 |
| 24 FDR Drive | January 20, 2005 |
| 30 FDR Drive | January 21, 2005 |
| 31 FDR Drive | January 21, 2005 |
| 6 Bataan Drive | January 20, 2005 |
| 5 San Jacinto Road | January 27, 2005 |
| 14 San Jacinto Road | January 25, 2005 |
| 4 Cowrens Drive | January 21, 2005 |
| 7 Cowrens Drive | January 24, 2005 |
| 13 Cowrens Drive | January 24, 2005 |

| Table E. Units Selected for LBP Inspection at NAPR Housing | |
|---|-----------------------|
| Address | Date Inspected |
| Cascajo Point | |
| 4 Monterey Road | January 26, 2005 |
| 5 Monterey Road | January 26, 2005 |
| 13 Monterey Road | January 26, 2005 |
| 14 Monterey Road | January 27, 2005 |
| 19 Monterey Road | January 27, 2005 |
| 26 Monterey Road | January 27, 2005 |
| 29 Monterey Road | January 27, 2005 |
| 30 Monterey Road | January 27, 2005 |
| 43 Monterey Road | January 27, 2005 |
| 2 Cabot Lake | January 24, 2005 |
| 5 Cabot Lake | January 24, 2005 |
| 12 Cabot Lake | January 24, 2005 |
| 14 Cabot Lake | January 27, 2005 |
| Coast Guard | |
| 1675 Intrepid Street | January 31, 2005 |
| 1676 Intrepid Street | January 31, 2005 |
| 1677 Intrepid Street | February 1, 2005 |
| 1678 Intrepid Street | February 5, 2005 |
| 1679 Intrepid Street | February 5, 2005 |
| 1680 Intrepid Street | January 31, 2005 |
| FDR Drive | |
| 1 FDR Drive | January 19, 2005 |
| 3 FDR Drive | January 21, 2005 |
| 5 FDR Drive | January 19, 2005 |
| Manatee Bay | |
| 6 Intrepid Street | January 6, 2005 |
| 7 Intrepid Street | January 7, 2005 |
| 8 Ranger Road | January 7, 2005 |
| 11 Ranger Road | January 7, 2005 |
| 20 Ranger Road | January 10 2005 |
| 36 Ranger Road | January 11, 2005 |
| 38 Ranger Road | January 10, 2005 |
| 49 Ranger Road | January 10, 2005 |
| 52 Ranger Road | January 10, 2005 |
| 60 Ranger Road | January 11, 2005 |
| 2 Hancock Circle | January 11, 2005 |
| 20 Hancock Circle | January 11, 2005 |
| 4 Coral Sea Drive | January 12, 2005 |
| 15 Coral Sea Drive | January 12, 2005 |
| 3 Franklyn Drive | January 12, 2005 |
| 18 Franklyn Drive | January 12, 2005 |
| 8 Hornet Road | January 13, 2005 |
| 19 Hornet Road | January 13, 2005 |
| 26 Hornet Road | January 13, 2005 |
| 3 Yorktown Circle | January 14, 2005 |
| 11 Yorktown Circle | January 14, 2005 |
| 21 Yorktown Circle | January 14, 2005 |
| 32 Yorktown Circle | January 14, 2005 |

| Table E. Units Selected for LBP Inspection at NAPR Housing | |
|---|-----------------------|
| Address | Date Inspected |
| Manatee Bay | |
| 35 Yorktown Circle | January 17, 2005 |
| 67 Lexington Drive | January 18, 2005 |
| 74 Lexington Drive | January 18, 2005 |
| 81 Lexington Drive | January 18, 2005 |
| Mangrove Manor | |
| 11 Saratoga Road | January 19, 2005 |
| 12 Saratoga Road | January 19, 2005 |
| 19 Saratoga Road | January 19, 2005 |
| 20 Saratoga Road | January 19, 2005 |
| 31 Saratoga Road | January 20, 2005 |
| 38 Saratoga Road | January 20, 2005 |
| 50 Saratoga Road | January 20, 2005 |
| 68 Saratoga Road | January 20, 2005 |
| 82 Saratoga Road | January 21, 2005 |
| 2 Essex Drive | January 21, 2005 |
| 11 Essex Drive | January 21, 2005 |
| 17 Essex Drive | January 21, 2005 |
| 6 Ticonderoga Road | January 24, 2005 |
| 18 Enterprise Drive | January 24, 2005 |
| 25 Enterprise Drive | January 24, 2005 |
| 34 Enterprise Drive | January 24, 2005 |
| 41 Enterprise Drive | January 25, 2005 |
| 54 Enterprise Drive | January 25, 2005 |
| 9 Lexington Drive | January 25, 2005 |
| 26 Lexington Drive | January 26, 2005 |
| 33 Lexington Drive | January 26, 2005 |
| 46 Lexington Drive | January 26, 2005 |
| 47 Lexington Drive | January 26, 2005 |
| 6 Wasp Circle | January 26, 2005 |
| 15 Wasp Circle | January 27, 2005 |
| 32 Wasp Circle | January 27, 2005 |
| 7 Bunker Hill Road | January 27, 2005 |
| Rainbow Hill | |
| 2A Nimitz Drive | January 27, 2005 |
| 4A Nimitz Drive | January 28, 2005 |
| 4B Nimitz Drive | January 28, 2005 |
| 5B Nimitz Drive | January 28, 2005 |
| 7A Nimitz Drive | January 28, 2005 |
| 8A Nimitz Drive | January 28, 2005 |
| 10C Nimitz Drive | January 31, 2005 |
| 13B Nimitz Drive | January 31, 2005 |
| 14B Nimitz Drive | January 31, 2005 |
| 15B Nimitz Drive | January 31, 2005 |
| 16A Nimitz Drive | February 1, 2005 |
| 18A Nimitz Drive | February 1, 2005 |
| 19C Nimitz Drive | February 1, 2005 |
| 20B Nimitz Drive | February 1, 2005 |
| 22B Nimitz Drive | February 2, 2005 |

| Table E. Units Selected for LBP Inspection at NAPR Housing | |
|--|------------------|
| Address | Date Inspected |
| Rainbow Hill | |
| 23A Nimitz Drive | February 2, 2005 |
| 24A Nimitz Drive | February 2, 2005 |
| 27A Nimitz Drive | February 2, 2005 |
| 28B Nimitz Drive | February 3, 2005 |
| 29B Nimitz Drive | February 3, 2005 |
| 32A Nimitz Drive | February 3, 2005 |
| 33B Nimitz Drive | February 3, 2005 |
| 34A Nimitz Drive | February 4, 2005 |
| 36A Nimitz Drive | February 4, 2005 |

2.4 Disclaimer

The presence or absence of LBP applies only to tested surfaces on the date of the field visit. It should be noted that conditions might change due to vandalism, deterioration or maintenance activities. Ongoing monitoring by the owner or transferee is necessary. The concentration of lead in paint that renders it a LBP is not relevant for worker protection concerns during construction or maintenance work. When workers disturb paint that contains any level of lead (determined by a valid test method), Puerto Rico OSHA requires adherence to its Lead Standard.

2.5 Results

Baker performed LBP inspections in 19 of 32 Algodones housing units, 26 of 136 Caribe Breeze housing units, 26 of 139 Cascajo Point housing units, all six Coast Guard housing units, all three FDR Drive housing units, 26 of 262 Manatee Bay housing units, 27 of 275 Mangrove Manor housing units, and 24 of 88 Rainbow Hill housing units. Baker's inspection identified LBP on several types of components in the Caribe Breeze, Coast Guard, and Mangrove Manor housing communities. LBP was not identified in the Algodones, Cascajo Point, FDR Drive, Manatee Bay, and Rainbow Hill housing communities. Complete surface-by-surface results for the XRF testing are included in Appendix F. Table B in the Executive Summary also provides a list of the positive components in the Caribe Breeze, Coast Guard, and Mangrove Manor housing communities. A summary of the number of positive and negative XRF readings by component for the housing units in which testing was conducted is included in Tables 1–8 following the text of this report. A list of the components that should be assumed to be coated with LBP in the NAPR Housing units that were not tested is included in Table 9 following the text of this report. Photographs of components coated in LBP are presented in Appendix E.

3.0 LEAD-BASED PAINT RISK ASSESSMENT

3.1 Regulatory Background

Section 2.1 of this report addresses the regulatory background of LBP in the United States.

3.2 Methodology

This LBP risk assessment involved a visual inspection of the units as well as the collection of environmental samples of dust and soil for laboratory analysis. The visual inspection also included a building condition assessment including observation for the presence of holes or cracks in the roof, missing exterior siding, foundation cracks, etc. Building condition forms are included in Appendix F.

Mr. Mark Zetts and Mr. Michael Arthur, EPA-certified Risk Assessors, conducted the visual assessment and directed the collection of environmental samples. Mr. Zetts and Mr. Arthur were assisted by Mr. Ramirez and Mr. Marquez of EDS, who are Puerto Rico EQB / EPA-certified Risk Assessors. Copies of training certificates are included in Appendix B. The methodologies for the environmental sampling performed in support of the risk assessment are discussed below.

During the LBP inspection, painted components were analyzed for lead using an XRF analyzer as stated in Section 2.2. In addition, Baker collected dust wipe samples, dust vacuum samples (where carpets instead of hard floors were present), and soil samples in accordance with HUD and EPA protocols. Dust wipe samples were collected from floors only. The housing units did not have window sills. Field blanks (1 per 20 wipe samples) were also collected and submitted for laboratory analysis. All samples were submitted with chain of custody documentation to Schneider Laboratories, Inc. for lead analysis by EPA Method 3050B/7420.

When bare soil was present, Baker collected composite soil samples. No bare soil was present at Algodones. One composite sample was collected from the children's play area (if present), one was collected from the building's dripline, and one was collected from any other areas of the yard, referred to as "mid-yard." Baker calculated the arithmetic mean of the dripline composite sample and the mid-yard composite sample to represent a yard average. Children's play area composite samples were reported separately.

Schneider Laboratories analyzed the dust wipe and soil samples using EPA method 3050B/7420. Schneider Laboratories is fully accredited for lead analysis under the National Lead Laboratory Accreditation Program. Laboratory certifications are presented in Appendix B. Laboratory reports for dust wipe and soil samples are included in Appendix D. Summaries of dust wipe, dust vacuum, and soil sample results by housing unit are presented in Appendix F.

3.3 Selecting Units for Assessment

The same units that were selected for LBP inspection were also selected for LBP risk assessment.

3.4 Summary of Hazards

Based on federal regulations, a lead hazard exists when one or more of the following conditions exist:

- LBP on a component is deteriorated.
- LBP is present on a friction surface, the LBP shows signs of abrasion, and lead levels in dust on nearest horizontal surface underneath the friction surface exceed dust-lead hazard standards ($40 \mu\text{g}/\text{ft}^2$ for floors; $250 \mu\text{g}/\text{ft}^2$ for windowsills).
- LBP is present on an impact surface, the LBP is damaged/deteriorated, and the damage is caused by impact of a related building component.
- LBP is present on a chewable surface and teeth marks are evident.
- Lead in floor dust wipe samples equals or exceeds 40 micrograms per square foot ($\mu\text{g}/\text{ft}^2$).
- Lead in interior window sill dust wipe samples equals or exceeds $250 \mu\text{g}/\text{ft}^2$

- Lead in bare soil play area samples equals or exceeds 400 part per million (ppm).
- Lead in bare soil samples equals or exceeds 1,200 ppm as a yard average.

Table F summarizes the LBP hazards identified within NAPR Housing. For additional details on LBP hazards, see Tables 10-13 following the text of the report. Floor plans of typical units are presented in Appendix A. Photographs of typical LBP hazards are presented in Appendix E.

| Table F. LBP Hazards Identified in LBP Risk Assessed Units at NAPR Housing | | | | |
|---|--|-------------------------|------------------|--------------------|
| Address | Hazard / Deteriorated LBP Component | Location | Condition | Quantity |
| Algodones | | | | |
| 889F | Dust - Floor | Hall 2 Floor | NA | NA |
| Coast Guard | | | | |
| 1676 Intrepid Street | Wood Door Casing/Jamb/Stop | BR3 | Fair | 1 |
| 1677 Intrepid Street | | ST/ME | | 1 |
| 1680 Intrepid Street | | BR3, Laundry, and ST/ME | NA | 3 |
| 1678 Intrepid Street | | Dust - Floor | | Bath 1 and Kitchen |
| Manatee Bay | | | | |
| 7 Intrepid Street | Dust - Floor | Bath 2 | NA | NA |
| Mangrove Manor | | | | |
| 68 Saratoga Road | Dust - Floor | Bath 1 - Floor | NA | NA |
| 25 Enterprise Drive | | Bath 1, DR - Floor | | |
| 6 Wasp Circle | | Hall - Floor | | |

No LBP hazards related to friction surfaces, impact surfaces, chewable surfaces, or soil were identified in the communities in Table F above. No LBP hazard of any type was identified in the Caribe Breeze, Cascajo Point, FDR Drive, and Rainbow Hill housing communities.

Implementation of one of the following two options is recommended for identifying LBP hazards that may exist at the NAPR Housing units that were not inspected:

- Test the components in the remaining 804 units that were not inspected for LBP, and identify all LBP hazards that are present.
- Assume all like components in the untested units contain LBP, and identify all LBP hazards that are present.

Although not required due to the age of NAPR Housing, control options for deteriorated LBP include:

- Paint Film Stabilization (considered an interim control)
- Encapsulation
- Enclosure
- Paint Removal
- Building Component Replacement

Control options for dust include:

- Dust Removal
- Cover Bare Soil

Control options for soil include:

- Plant Grass or Sod
- Cover with Mulch
- Pave Over
- Soil Removal

Other recommendations include:

- 1) The property transferee should be made aware of the presence of LBP and LBP hazards in the housing units.
- 2) Contractors who disturb LBP should comply with the requirements of the Puerto Rico Occupational Safety & Health Administration (OSHA) Lead Standard, which mirrors the federal OSHA standard (29 CFR 1926.62).

Exhibit H

Lead-Based Paint Hazards Advisory Statement

**LEAD-BASED PAINT HAZARD
DISCLOSURE AND ACKNOWLEDGEMENT FORM**

LEAD WARNING STATEMENT

YOU ARE ADVISED THAT STRUCTURES CONSTRUCTED PRIOR TO 1978 MAY PRESENT EXPOSURE TO LEAD FROM LEAD-BASED PAINT THAT MAY PLACE YOUNG CHILDREN AT RISK OF DEVELOPING LEAD POISONING. LEAD POISONING IN YOUNG CHILDREN MAY PRODUCE PERMANENT NEUROLOGICAL DAMAGE. YOU ARE FURTHER ADVISED THAT LEAD POISONING ALSO POSES A PARTICULAR RISK TO PREGNANT WOMEN. WORKERS MAY ALSO SUFFER ADVERSE HEALTH EFFECTS FROM LEAD DUST AND FUME EXPOSURE

ACKNOWLEDGEMENT

I acknowledge that:

1. I have read and understand the above stated Lead Warning Statement;
2. I have received from the Federal Government the following document(s): *Phase I/II Environmental Condition of Property Report, Former Naval Station Roosevelt Roads, Ceiba, Puerto Rico* and *Finding of Suitability to Transfer, Sale Parcel II - Capehart, Naval Activity Puerto Rico, Ceiba, Puerto Rico* representing the best information available to the Government as to the presence of Lead-Based Paint and Lead-Based Paint hazards for the non-residential buildings covered by this Transfer. I have also received the *Final Lead-Based Paint Inspection/Risk Assessment Report for Military Family Housing, Naval Activity Puerto Rico, Ceiba, Puerto Rico* representing the best information available to the Government as to the presence of Lead-Based Paint and Lead-Based Paint hazards for the residential buildings covered by this Transfer;
3. I understand that my failure to inspect, or to become fully informed as to the condition of all or any portion of the property offered will not constitute grounds for any claim or demand for adjustment or withdrawal of any bid or offer made after its opening or tender; and
4. I understand that upon execution of this Transfer, I shall assume full responsibility for preventing future lead exposure by properly managing and maintaining or, as required by applicable Federal, state, or local laws or regulations, for abating any lead-based paint hazard that may pose a risk to human health.

Transferee (or duly authorized agent)

Date

Exhibit I
Responses to Comments

Navy Responses to U.S. Environmental Protection Agency (EPA) Comments
Draft Finding of Suitability to Transfer
Sale Parcel II - Capehart

EPA Comment 1:

EPA does not fully agree with the statement given in Section 5.0.F (Environmental Compliance Agreements/Permits/Orders) of the FOST that "...there are no RCRA obligations related to the Subject Property at this time. EPA considers certain requirements of the January 2007 RCRA Consent Order between the Navy and EPA to be applicable to the Subject Property, including, among others, those given in: a) Paragraph 26 "Notification and Additional Work Requirements for Newly Discovered Releases"; Paragraph 27.H) "Imminent and Substantial Endangerment due to Solid Waste or Hazardous Waste"; and all of Section XVI (Record Retention).

Navy response:

The text of Section 5.F. has been revised to state the following:

On January 29, 2007, the U.S. Department of the Navy and EPA voluntarily entered into a Resource Conservation and Recovery Act (RCRA) Section 7003 Administrative Order on Consent (Consent Order; EPA, 2007). The Consent Order set out the Navy's RCRA corrective action obligations and replaced the 1994 RCRA permit as the document memorializing these obligations concerning NAPR. Although there are no RCRA solid waste management units or areas of concern on the Subject Property, certain RCRA obligations defined in the Consent Order apply to the Subject Property including notification and additional work requirements for newly discovered releases, other notification requirements, and record retention requirements. There are no other environmental compliance agreements, permits, or orders associated with the Subject Property.

EPA Comment 2:

References - the January 2007 Administrative Order on Consent should be listed in the reference section.

Navy response:

The January 2007 Administrative Order on Consent has been added to the list of references in Exhibit A.

EXHIBIT "E"

DEPARTMENT OF DEFENSE INSTRUCTION 4165.72

*gfb
mfb*



Department of Defense INSTRUCTION

NUMBER 4165.72
December 21, 2007

USD(AT&L)

SUBJECT: Real Property Disposal

- References:
- (a) DoD Directive 4165.6, "Real Property," October 13, 2004
 - (b) DoD Directive 4275.5, "Acquisition and Management of Industrial Resources," October 6, 1980
 - (c) DoD Instruction 4165.69, "Realignment of DoD Sites Overseas," April 6, 2005
 - (d) DoD Directive 5110.4, "Washington Headquarters Services (WHS)," October 19, 2001
 - (e) through (v), see Enclosure 1

1. PURPOSE

This Instruction:

- 1.1. Implements policy and assigns responsibility pursuant to Reference (a) for the disposal of real property.
- 1.2. Re-delegates various statutory and regulatory authorities and responsibilities relating to real property disposal.

2. APPLICABILITY AND SCOPE

This Instruction:

- 2.1. Applies to the Office of the Secretary of Defense, the Military Departments (including their Reserve components), the Office of the Chairman of the Joint Chiefs of Staff, the Combatant Commands, the Office of the Inspector General of the Department of Defense, the Defense Agencies, the DoD Field Activities, and all other organizational entities in the Department of Defense (hereafter referred to collectively as the "DoD Components").
- 2.2. Applies to all DoD real property holdings except:
 - 2.2.1. Civil works projects.

Handwritten initials, possibly "JJP" and "MS", are located in the right margin of the page.

2.2.2. The acquisition and management of defense industrial plants that are governed by DoD Directive 4275.5 (Reference (b)).

2.3. Does not apply to DoD real property holdings:

2.3.1. Disposed of pursuant to a base closure law, except for paragraphs 5.1.2., 5.5., 5.8., 5.9., 5.10., and 5.11., which do apply.

2.3.2. Outside the United States with regard to those provisions of law not having extraterritorial application. (See DoD Instruction 4165.69 (Reference (c))).

3. DEFINITIONS

3.1. Consistent with DoD Directive 5110.4 (Reference (d)), for purposes of the Pentagon Reservation, Washington Headquarters Services shall be considered a Military Department and its Director the secretary thereof.

3.2. Other terms used in this Instruction are defined in Joint Publication 1-02 (Reference (e)) and section 101 of title 10, United States Code (U.S.C.) (Reference (f)).

4. RESPONSIBILITIES

4.1. The Under Secretary of Defense for Acquisition, Technology, and Logistics (USD(AT&L)) shall establish overarching guidance and procedures regarding the disposal of real property.

4.2. The Deputy Under Secretary of Defense for Installations and Environment (DUSD(I&E)), under the USD(AT&L):

4.2.1. Shall provide additional guidance and procedures for the implementation of DoD real property disposal policy and this Instruction.

4.2.2. Is hereby re-delegated, with authority to re-delegate, all those authorities and responsibilities delegated or re-delegated, as the case may be, to the USD(AT&L) under paragraph 5.1.3. of Reference (a) that relate to the disposal of real property.

4.3. The Secretaries of the Military Departments shall:

4.3.1. Establish programs and procedures to dispose of real property that conform with applicable law and the policies, guidance, and procedures provided by and pursuant to Reference (a) and this Instruction.

4.3.2. Accurately inventory and account for the real property under their jurisdiction, management, and control in accordance with DoD Instruction 4165.14 (Reference (g)).

4.4. The Heads of the DoD Components shall:

4.4.1. Ensure compliance with this Instruction.

4.4.2. Provide, within 45 days after a Military Department gives notice of the availability of real property for which a DoD Component has a requirement, a firm commitment to take real property accountability for the property in the case of a Military Department, or a firm commitment from a Combatant Command, Defense Agency, or DoD Field Activity that it requires the property and has secured the agreement of a Military Department to accept real property accountability for the property. A Combatant Command, Defense Agency, or DoD Field Activity that is supported by a specific Military Department for its real property requirements will communicate its requirements through that Military Department.

5. PROCEDURES

5.1. Disposal of Real Property. The programs of the Military Departments shall ensure that, after screening with the other DoD Components, real property for which there is no foreseeable military requirement, either in peacetime or for mobilization, and for which the Department of Defense does not have disposal authority, is promptly reported for disposal to the General Services Administration (GSA), or the Department of the Interior in the case of land withdrawals, in accordance with applicable regulations of those agencies.

5.1.1. Real property may be transferred, at no cost, among the Armed Forces, including the Coast Guard, pursuant to section 2696 of title 10, U.S.C. (Reference (h)). Subject to the authority, direction, and control of the Secretary of Defense with regard to the DoD Components, this transfer authority cannot be precluded, directly or indirectly, by any regulatory, program, or policy restrictions issued by any agency or official within the Executive Branch of the Federal Government.

5.1.2. Subject to Reference (h), ensure compliance with part 373 of title 40, Code of Federal Regulations (CFR), "Reporting Hazardous Substance Activity When Selling or Transferring Federal Real Property" (Reference (i)).

5.1.3. Subject to Reference (h), ensure compliance with the Federal Management Regulation (Reference (j)) dealing with real property disposal, part 102-75 of title 41, CFR.

5.1.4. Ensure compliance with chapter 6 of volume 4 of the DoD Financial Management Regulations, DoD 7000.14-R (Reference (k)) relating to valuation of property assets.

5.1.5. Until such time during the disposal process that GSA assumes such responsibility, the holding Military Department will ensure compliance with the McKinney-Vento Homeless Assistance Act, as amended, section 11411 of title 42, U.S.C., (Reference (l)) with regard to

identifying unutilized, underutilized, excess, or surplus property that may be suitable for use by the homeless.

5.1.6. Disposal of real property may include disposing of associated interests in real property such as authorized by section 2668a of title 10, U.S.C. (Reference (m)), including those needed to comply with the requirements of the National Historic Preservation Act, section 470 et seq. of title 16, U.S.C. (Reference (n)).

5.1.7. In the case of withdrawn lands not accepted back by the Department of the Interior, always address disposition of mineral rights during the disposal process. (See part 2720 of title 43, CFR (Reference (o))).

5.1.8. For granting uses of real property such as outgrants, see DoD Instruction 4165.70 (Reference (p)).

5.1.9. Before disposing of real property containing floodplains or wetlands, ensure compliance with Executive Orders 11988 and 11990 (References (q) and (r), respectively).

5.2. Mobilization Requirements. Real property may be held solely to meet a mobilization requirement.

5.2.1. Such property may be made available for interim use in one of the following ways, provided it will not involve modifying the property in a manner that would prevent its timely use in meeting its mobilization requirements:

5.2.1.1. By permit to another Government agency.

5.2.1.2. By outgranting by license, easement, or lease.

5.2.1.3. By declaring it as excess to GSA for disposal subject to adequate provisions for recapture in accordance with existing regulations, instructions, and statutes.

5.2.2. Any property subject to interim use in accordance with paragraphs 5.2.1.1. and 5.2.1.2. shall have a provision in the granting document requiring immediate return of the property, without cost to the Department of Defense, upon the demand of the holding Military Department, after it determines the property is required for mobilization.

5.3. Release of Reverter and Reuse Rights and of Covenants. The release of reverter and emergency reuse (recapture) rights and of covenants retained by the Government may be effected in response to a petition from the current owner to the Secretary of Defense through the original Federal grantor agency, such as the Departments of Interior, Health and Human Services, Housing and Urban Development, and Education; the Federal Aviation Administration; or GSA; if there is no current requirement for the right or covenant by any of the Military Departments.

5.3.1. Upon notification by DUSD(I&E) that such a petition has been received, the holding Military Department shall review:

5.3.1.1. In the case of reverter or reuse rights, plans covering contemplated use of the facility in light of the current and projected physical condition of the improvements.

5.3.1.2. In the case of a covenant, the original reason for the covenant, State regulatory concurrence if applicable, and changed circumstances.

5.3.2. The holding Military Department shall also notify the other DoD Components that the reverter or reuse rights it has reserved may be extinguished and request they provide, within 45 days, their objections, if any, to the release of such rights along with their rationale for objecting.

5.3.3. The holding Military Department:

5.3.3.1. If it was not the grantor agency, shall then make a recommendation to DUSD(I&E) as to whether the reverter or reuse rights or the covenant should be extinguished.

5.3.3.2. If it was the grantor agency and intends to extinguish the reverter or reuse rights or the covenant, shall advise DUSD(I&E) of its intention and wait 15 days before taking further action.

5.3.4. DUSD(I&E) shall, in the case of paragraph 5.3.3.1., then provide the position of the Department of Defense to the Federal grantor agency as to whether the reverter or reuse rights or the covenant should be extinguished.

5.4. Environmental Impacts. The holding Military Department shall accomplish any environmental analysis, including of the environmental condition of the property, required by law or its regulations prior to disposing of property, whether the disposal is done directly or by transfer to another agency for disposal or reuse.

5.5. Clauses Under section 120(h) of the Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (CERCLA), section 9620(h) of title 42, U.S.C., (Reference (s)).

5.5.1. Reference (s) provides an exception to the prohibitions of the Anti-Deficiency Act by allowing the commitment of a future unfunded obligation, namely the potential return of the United States to conduct a remedial action on former DoD properties. The Department of Defense has no authority to increase or decrease the commitments directed to be provided by section 120(h).

5.5.2. Any deed transferring title to real property shall contain, to the extent they are required by law, the notices, descriptions, assurances, access rights, warranties, and covenants (collectively referred to as "120(h) clauses" in this Instruction) specified in Reference (s) as provided by this Instruction. The 120(h) clauses contained in this Instruction shall not be

inserted into any other real property transfer documents other than a deed transferring real property, nor shall any other versions of such clauses be inserted into such other documents.

5.5.2.1. Such 120(h) clauses:

5.5.2.1.1. Ensure compliance with Reference (s) when a DoD Component transfers real property to a non-Federal entity.

5.5.2.1.2. Provide uniformity in transaction documents.

5.5.2.1.3. Ensure the liability of the United States is not increased beyond that provided by law.

5.5.2.1.4. Ensure the commitments made by the United States to non-Federal recipients of DoD real property are not less than those required to be provided by Reference (s).

5.5.2.2. Such 120(h) clauses shall contain without change or limitation the applicable language provided in Enclosure 2. Changes or limitations to the language provided in Enclosure 2 are only authorized with the prior written approval of DUSD(I&E).

5.5.2.3. This paragraph 5.5. has limited application:

5.5.2.3.1. It addresses the provision of 120(h) clauses under Reference (s). It does not address all obligations under Reference (s). (See paragraph 5.1.2., for example.)

5.5.2.3.2. Not all property transfers are subject to this paragraph:

5.5.2.3.2.1. Only those transfers by deed (or other agreement in the case of section 120(h)(3)(C)(ii) assurances), i.e., transfer of title outside of the Federal Government, are subject to these 120(h) clauses. Leases and easements are not a transfer of title.

5.5.2.3.2.2. Only those transfers of title that occurred after the enactment of the relevant provisions of paragraphs 120(h)(3) and (4) of Reference (s) would be subject to its provisions relating to 120(h) clauses. For instance, a formerly used defense site transferred before the date of enactment of sections 120(h)(3) and (4) would not have had the 120(h) clauses provided in the deed.

5.5.2.4. No other 120(h) clauses, other than those provided in Enclosure 2, or changed or limited with the permission of DUSD(I&E) pursuant to paragraph 5.5.2.2., shall be used to comply with Reference (s). As a negotiated aspect of a business transaction, the Secretary concerned may agree to other deed provisions that are not inconsistent with the 120(h) clauses in Enclosure 2. Such negotiated provisions shall not increase or reduce the liability of the United States with regard to its section 120(h) obligations. Such negotiated provisions may include, for example, contractual transfer of responsibility for conducting the remedial action in instances of early transfer, contractual agreements relating to insurance to ensure performance of other contractual obligations, and environmental covenants or similar restrictions to ensure

viability of a remedy. As an aid in applying paragraph 5.5., Enclosure 3 contains a table providing a broad overview as to which 120(h) clauses should be used in various circumstances.

5.5.2.4.1. Property subject to paragraph 120(h)(3) of Reference (s). For property subject to paragraph 120(h)(3) of Reference (s), but excluding property subject to deferral under paragraph 120(h)(3)(C) of Reference (s), the following 120(h) clauses shall be used in the deed:

5.5.2.4.1.1. The appropriate option for the 120(h) clause found at paragraph E2.1.1. of Enclosure 2 entitled "Property Covered by Notice, Description, Access Rights, and Covenants Made Pursuant to Section 120(h)(3)(A) of the Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (42 U.S.C. § 9620(h)(3)(A))";

5.5.2.4.1.2. The appropriate option for the 120(h) clause found at paragraph E2.1.2. of Enclosure 2 entitled "Notices Pursuant to Section 120(h)(3)(A)(i)(I) and (II) of the Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (42 U.S.C. § 9620(h)(3)(A)(i)(I) and (II))";

5.5.2.4.1.3. The appropriate option for the 120(h) clause found at paragraph E2.1.3. of Enclosure 2 entitled "Description of Remedial Action Taken, if Any, Pursuant to Section 120(h)(3)(A)(i)(III) of the Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (42 U.S.C. § 9620(h)(3)(A)(i)(III))";

5.5.2.4.1.4. The 120(h) clause found at paragraph E2.1.4. of Enclosure 2 entitled "Covenant Pursuant to Section 120(h)(3)(A)(ii) and (B) of the Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (42 U.S.C. § 9620(h)(3)(A)(ii) and (B))" [this 120(h) clause shall not be provided in any case in which the person or entity to whom the real property is transferred is a potentially responsible party with respect to such property]; and

5.5.2.4.1.5. The 120(h) clause found at paragraph E2.1.5. of Enclosure 2 entitled "Access Rights Pursuant to Section 120(h)(3)(A)(iii) of the Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (42 U.S.C. § 9620(h)(3)(A)(iii)).

5.5.2.4.2. Property subject to paragraph 120(h)(3)(C) of Reference (s).

5.5.2.4.2.1. For property subject to paragraph 120(h)(3) of Reference (s) but where the requirement to provide the warranty under paragraph 120(h)(3)(A)(ii)(I) of Reference (s) has been deferred pursuant to paragraph 120(h)(3)(C) of Reference (s), the following 120(h) clauses shall be used in the deed (or other agreement addressing the response action assurances in the case of the 120(h) clause addressed in paragraph 5.5.2.4.2.1.5):

5.5.2.4.2.1.1. The appropriate option for the 120(h) clause found at paragraph E2.2.1. of Enclosure 2 entitled "Property Covered by Notice, Description, Assurances, Access Rights, and Covenants Made Pursuant to Section 120(h)(3)(A) of the Comprehensive

Environmental Response, Compensation, and Liability Act of 1980 (42 U.S.C. § 9620(h)(3)(A))”;

5.5.2.4.2.1.2. The appropriate option for the 120(h) clause found at paragraph E2.1.2. of Enclosure 2 entitled “Notices Pursuant to Section 120(h)(3)(A)(i)(I) and (II) of the Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (42 U.S.C. § 9620(h)(3)(A)(i)(I) and (II))”;

5.5.2.4.2.1.3. The appropriate option for the 120(h) clause found at paragraph E2.1.3. of Enclosure 2 entitled “Description of Remedial Action Taken, if Any, Pursuant to Section 120(h)(3)(A)(i)(III) of the Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (42 U.S.C. § 9620(h)(3)(A)(i)(III))”;

5.5.2.4.2.1.4. The 120(h) clause found at paragraph E2.2.2. of Enclosure 2 entitled “Covenant Pursuant to Section 120(h)(3)(A)(ii)(II) and (B) of the Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (42 U.S.C. § 9620(h)(3)(A)(ii)(II) and (B))” [this 120(h) clause shall not be provided in any case in which the person or entity to whom the real property is transferred is a potentially responsible party with respect to such property];

5.5.2.4.2.1.5. The 120(h) clause found at paragraph E.2.2.3. of Enclosure 2 entitled “Assurances Pursuant to Section 120(h)(3)(C)(ii) of the Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (42 U.S.C. § 9620(h)(3)(C)(ii))”;

5.5.2.4.2.1.6. The 120(h) clause found at paragraph E.2.1.5. of Enclosure 2 entitled “Access Rights Pursuant to Section 120(h)(3)(A)(iii) of the Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (42 U.S.C. § 9620(h)(3)(A)(iii))”.

5.5.2.4.2.2. When all response action necessary to protect human health and the environment with respect to any substance remaining on the property on the date of transfer has been taken, the following 120(h) clauses shall be provided to the transferee in an appropriate document [these 120(h) clauses shall not be provided in any case in which the person or entity to whom the real property is transferred is a potentially responsible party with respect to such property]:

5.5.2.4.2.2.1. The appropriate option for the 120(h) clause found at paragraph E2.2.1. of Enclosure 2 entitled “Property Covered by Notice, Description, Assurances, Access Rights, and Warranty Made Pursuant to Section 120(h)(3)(A) of the Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (42 U.S.C. § 9620(h)(3)(A))”;

5.5.2.4.2.2.2. The 120(h) clause found at paragraph E2.2.4. of Enclosure 2 entitled “Warranty Pursuant to Section 120(h)(3)(C)(iii) of the Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (42 U.S.C. § 9620(h)(3)(C)(iii))”.

5.5.2.4.3. Property subject to paragraph 120(h)(4) of Reference (s). For property subject to paragraph 120(h)(4) of Reference (s), the following 120(h) clauses shall be used in the deed:

5.5.2.4.3.1. The appropriate option for the 120(h) clause found at paragraph E2.3.1. of Enclosure 2 entitled "Property Covered by Covenant and Access Rights Made Pursuant to Section 120(h)(4)(D) of the Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (42 U.S.C. § 9620(h)(4)(D))";

5.5.2.4.3.2. The 120(h) clause found at paragraph E2.3.2. of Enclosure 2 entitled "Covenant Pursuant to Section 120(h)(4)(D)(i) of the Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (42 U.S.C. § 9620(h)(4)(D)(i))"; and,

5.5.2.4.3.3. The 120(h) clause found at paragraph E2.3.3. of Enclosure 2 entitled "Access Rights Pursuant to Section 120(h)(4)(D)(ii) of the Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (42 U.S.C. § 9620(h)(4)(D)(ii))".

5.5.2.5. If a hazardous substance was not stored for one year or more, known to have been released, or disposed of on the parcel, but a petroleum product or its derivative is known to have been released or disposed of on the property, none of the 120(h) clauses under Reference (s) shall be provided.

5.5.2.6. To the extent a deed contains separately identified parcels at least one each of which is subject to any two or more of paragraphs 120(h)(3), 120(h)(3) with deferral, and 120(h)(4) of Reference (s), the deed shall separately designate those parcels under each of those three categories and provide the applicable 120(h) clauses in Enclosure 2 for each of those groupings.

5.5.2.7. Users of the 120(h) clauses found at paragraphs E2.1.2. and E2.1.3. of Enclosure 2 should note that they include the possibility of voluminous attachments. Since the transferee will pay the cost of recording, the transferee should be consulted before voluminous but not necessarily required attachments are included with the deed.

5.6. Release of Leaseholds. Excess leaseholds, if transferable, should be made available to other DoD Components and the Coast Guard as soon as possible.

5.6.1. Immediately upon a determination that a DoD leasehold is no longer required by the DoD Component, the DoD Component concerned shall send a notice of availability to the appropriate offices of the other DoD Components and the Coast Guard, provided the leasehold terms would not prevent their use of the leasehold and there is a reasonable useful life remaining.

5.6.2. Such notices shall include a physical description of the property, terms of the lease, surrender date, and date of contract renewal.

5.6.3. The DoD Component or Coast Guard interested in acquiring such an excess DoD leasehold shall assume responsibility for continuing the leasehold interest, including payment of all rents.

5.6.4. If no DoD or Coast Guard interest is expressed, the DoD Component shall advise GSA of any excess leasehold which has at least 9 months of beneficial occupancy remaining to permit Federal screening.

5.6.5. For GSA leaseholds occupied by DoD Components, the DoD Component will inform GSA as soon as the DoD Component becomes aware that it will no longer require the use of the GSA leasehold.

5.7. Excess Family Housing Units. A Report of Excess Real Property (Standard Form 118) (Reference (t)) to GSA covering mortgaged or unencumbered family housing and related land and improvements or unimproved land acquired for family housing purposes shall include the statement: "Net proceeds from the sale of family housing, including related land and improvements, shall be deposited in the Family Housing Account of the appropriate Military Department."

5.8. Timberland

5.8.1. Under the authority of section 2665 of title 10, U.S.C. (Reference (u)), any forest products produced on land owned or leased by a Military Department may be sold without also selling the underlying land, provided, in the case of leased property, that the lease does not prohibit such sales. Since Reference (u) is used to dispose of the forest products, they are not declared excess under title 40, U.S.C., or its implementing regulations.

5.8.2. If forestlands are being considered for disposal, the forest resources should be evaluated to determine the feasibility of harvesting and sale of forest products before disposal of lands. This evaluation must consider the effects of harvesting on the future use and environmental quality of the property as well as its relative diminution of the property's fair market value. With respect to base realignment and closure property, the evaluation should also consider the impact of harvesting on the redevelopment plans of the local redevelopment authority. Planned harvesting may continue on land reported as excess until actual disposal or transfer, provided that the evaluation determines that harvesting and sale of forest products should proceed and any sales agreement does not provide otherwise.

5.9. Property with Military Munitions

5.9.1. Real property known to contain or suspected of containing explosive or chemical agent hazards shall not be transferred out of DoD control (other than to the Coast Guard) unless appropriate protective measures have been taken to ensure the recipient of the property is both fully informed of the actual and potential hazards relating to the presence or possible presence of explosives or chemical agents and restrictions or conditions have been placed on the use of the property to avoid harm to users due to the presence of explosives or chemical agents. Appropriate notice requirements and restrictions on use will be submitted by the disposing

Component to the Department of Defense Explosives Safety Board for its approval prior to transfer. An outgrant such as a lease or permit may constitute transfer out of DoD control if the DoD Component does not retain sufficient control over the property to adequately manage exposure to explosive or chemical agent hazards.

5.9.2. Real property being transferred out of DoD control after explosive and chemical agent hazards have been addressed, but which is adjacent to property where such hazards have not been addressed, will have appropriate restrictions and reservations included in the transfer documents to ensure the use of the transferred property does not obstruct addressing the hazards on the adjacent property. DUSD(I&E), after consultation with the Department of Defense Explosives Safety Board, will provide model language for this purpose.

5.10. Retention of Access Rights

5.10.1. Property disposed of but not subject to inclusion of clauses under Reference (s) or paragraph 5.5. should retain a right of entry onto the property for purposes of addressing the possibility of undiscovered contamination. For this purpose, the transfer document should contain a clause similar to or the same as the clause contained at paragraph E.2.3.3., although without including in the clause any reference to Reference (s).

5.10.2. Appropriate access rights should also be retained whenever other laws or provisions of the transfer document could generate an obligation or responsibility on the part of the United States requiring it to return to the property.

5.11. Indemnification Under Section 330 of the National Defense Authorization Act for Fiscal Year 1993 (Reference (v)), as amended. Reference (v) provides for indemnification of transferees of closing DoD properties under circumstances specified in that statute. The authority to implement this provision of law has been delegated by the Secretary of Defense to the General Counsel of the Department of Defense; therefore, this provision of law shall only be referred to or recited in any deed, sales agreement, bill of sale, lease, license, easement, right-of-way, transfer document for real or personal property, or cooperative agreement or grant after obtaining the written concurrence of the Deputy General Counsel (Environment and Installations), Office of the General Counsel, Department of Defense.

7. EFFECTIVE DATE


This Instruction is effective immediately.

8. RELEASABILITY

UNLIMITED. This Instruction is approved for public release. The DoD Components (to include the Combatant Commands), other Federal agencies, and the public may obtain copies of

DoDI 4165.72, December 21, 2007

this Instruction through the Internet from the DoD Issuances Web Site at
<http://www.dtic.mil/whs/directives>.



John J. Young, Jr.
Under Secretary of Defense for
Acquisition, Technology, and Logistics

Enclosures - 3

- E1. References, continued
- E2. CERCLA 120(h) Clauses
- E3. Table of CERCLA 120(h) Clauses

E1. ENCLOSURE 1

REFERENCES, continued

- (e) Joint Publication 1-02, "Department of Defense Dictionary of Military and Associated Terms," as amended
- (f) Section 101 of title 10, U.S.C.
- (g) DoD Instruction 4165.14, "Real Property Inventory and Forecasting," March 31, 2006
- (h) Section 2696 of title 10, U.S.C.
- (i) Title 40, CFR, Part 373, "Reporting Hazardous Substance Activity When Selling or Transferring Federal Real Property," current edition
- (j) Title 41, CFR, Part 102-75, "Federal Management Regulation," current edition
- (k) DoD 7000.14-R, "DoD Financial Management Regulations," current edition
- (l) Section 11411 of title 42, U.S.C., "McKinney Vento Homeless Assistance Act"
- (m) Section 2668a of title 10, U.S.C.
- (n) Section 470, et seq., of title 16, U.S.C., "The National Historic Preservation Act"
- (o) Title 43, CFR, Part 2720, "Conveyance of Federally-Owned Mineral Interests," current edition
- (p) DoD Instruction 4165.70, "Real Property Management," January 6, 2005
- (q) Executive Order 11988, "Floodplain Management," May 24, 1977
- (r) Executive Order 11990, "Protection of Wetlands," May 24, 1977
- (s) Section 120(h) of the Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (CERCLA) (Section 9620(h) of title 42, U.S.C.)
- (t) Report of Excess Real Property (Standard Form 118)
- (u) Section 2665 of title 10, U.S.C.
- (v) Section 330 of Public Law 102-484, "The National Defense Authorization Act for Fiscal Year 1993"

E2. ENCLOSURE 2

CERCLA 120(h) CLAUSES

**TEXT OF CLAUSES PROVIDED PURSUANT TO SECTION 120(h) OF CERCLA
(Reference (s))**

[USER NOTE: UPON USE, DELETE MATERIAL IN SQUARE BRACKETS. THE MATERIAL IN BOLD CURLY BRACKETS IS TO BE FILLED IN OR A SELECTION MADE.]

E2.1—DEPARTMENT OF DEFENSE UNIFORM NOTICE, DESCRIPTION, ACCESS RIGHTS, AND COVENANTS FOR SECTION 120(h)(3) OF THE COMPREHENSIVE ENVIRONMENTAL RESPONSE, COMPENSATION, AND LIABILITY ACT OF 1980 (42 U.S.C. § 9620(h)(3))

E2.1.1. “___ . Property Covered by Notice, Description, Access Rights, and Covenants Made Pursuant to Section 120(h)(3)(A) of the Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (42 U.S.C. § 9620(h)(3)(A)):”

[OPTION #1: FOR USE WHERE THE 120(h) CLAUSES ONLY APPLY TO CERTAIN PARCELS OF THE TOTAL PROPERTY.]

“For parcels _____ of the property, the Grantor provides the following notice, description, and covenants and retains the following access rights:”

[OPTION #2: FOR USE WHERE THE 120(h) CLAUSES APPLY TO THE ENTIRE PROPERTY.]

“For the property, the Grantor provides the following notice, description, and covenants and retains the following access rights:”

E2.1.2. “___ . Notices Pursuant to Section 120(h)(3)(A)(i)(I) and (II) of the Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (42 U.S.C. § 9620(h)(3)(A)(i)(I) and (II)):”

[OPTION #1: FOR LENGTHY NOTICES, SET FORTH THE DETAILED INFORMATION IN AN EXHIBIT TO THE DEED AND INCORPORATE IT BY THIS REFERENCE.]

“Pursuant to section 120(h)(3)(A)(i)(I) and (II) of the Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (42 U.S.C. § 9620(h)(3)(A)(i)(I) and (II)), available information regarding the type, quantity, and location of hazardous substances and the time at which such substances were stored, released, or disposed of, as defined in section 120(h), is provided in Exhibit ___, attached hereto and made a part hereof.”

[OPTION #2: FOR BRIEF NOTICES, SET FORTH THE DETAILED INFORMATION IN THE NOTICE ITSELF.]

“Pursuant to section 120(h)(3)(A)(i)(I) and (II) of the Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (42 U.S.C. § 9620(h)(3)(A)(i)(I) and (II)), notice is hereby provided that {INSERT DESCRIPTION OF TYPE, QUANTITY, AND LOCATION OF HAZARDOUS SUBSTANCES} {was/were} {stored/released/disposed of} on the property on or about {INSERT DATES IF KNOWN FOR SUCH STORAGE, RELEASE, OR DISPOSAL OF HAZARDOUS SUBSTANCES}.”

E2.1.3. “ ___. Description of Remedial Action Taken, if Any, Pursuant to Section 120(h)(3)(A)(i)(III) of the Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (42 U.S.C. § 9620(h)(3)(A)(i)(III)):”

[OPTION #1: FOR LENGTHY DESCRIPTIONS, SET FORTH THE DETAILED INFORMATION IN AN EXHIBIT TO THE DEED AND INCORPORATE IT BY THIS REFERENCE.]

“Pursuant to section 120(h)(3)(A)(i)(III) of the Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (42 U.S.C. § 9620(h)(3)(A)(i)(III)), a description of the remedial action taken, if any, on the property is provided in Exhibit ___, attached hereto and made a part hereof.”

[OPTION #2: FOR BRIEF DESCRIPTIONS, SET FORTH THE DETAILED INFORMATION IN THE NOTICE ITSELF.]

“Pursuant to section 120(h)(3)(A)(i)(III) of the Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (42 U.S.C. § 9620(h)(3)(A)(i)(III)), a remedial action consisting of {FILL IN DESCRIPTION OF THE REMEDIAL ACTION} has been taken on the property.”

E2.1.4. “ ___. Covenant Pursuant to Section 120(h)(3)(A)(ii) and (B) of the Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (42 U.S.C. § 9620(h)(3)(A)(ii) and (B)):

“Pursuant to section 120(h)(3)(A)(ii) and (B) of the Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (42 U.S.C. § 9620(h)(3)(A)(ii) and (B)), the United States warrants that—

“(a) all remedial action necessary to protect human health and the environment with respect to any hazardous substance identified pursuant to section 120(h)(3)(A)(i)(I) of the Comprehensive Environmental Response, Compensation, and Liability Act of 1980 remaining on the property has been taken before the date of this deed, and

“(b) any additional remedial action found to be necessary after the date of this deed shall be conducted by the United States.”

E2.1.5. “___ . Access Rights Pursuant to Section 120(h)(3)(A)(iii) of the Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (42 U.S.C. § 9620(h)(3)(A)(iii)):

“The United States retains and reserves a perpetual and assignable easement and right of access on, over, and through the property, to enter upon the property in any case in which a remedial action or corrective action is found to be necessary on the part of the United States, without regard to whether such remedial action or corrective action is on the property or on adjoining or nearby lands. Such easement and right of access includes, without limitation, the right to perform any environmental investigation, survey, monitoring, sampling, testing, drilling, boring, coring, testpitting, installing monitoring or pumping wells or other treatment facilities, response action, corrective action, or any other action necessary for the United States to meet its responsibilities under applicable laws and as provided for in this instrument. Such easement and right of access shall be binding on the grantee and its successors and assigns and shall run with the land.

“In exercising such easement and right of access, the United States shall provide the grantee or its successors or assigns, as the case may be, with reasonable notice of its intent to enter upon the property and exercise its rights under this clause, which notice may be severely curtailed or even eliminated in emergency situations. The United States shall use reasonable means to avoid and to minimize interference with the grantee’s and the grantee’s successors’ and assigns’ quiet enjoyment of the property. At the completion of work, the work site shall be reasonably restored. Such easement and right of access includes the right to obtain and use utility services, including water, gas, electricity, sewer, and communications services available on the property at a reasonable charge to the United States. Excluding the reasonable charges for such utility services, no fee, charge, or compensation will be due the grantee, nor its successors and assigns, for the exercise of the easement and right of access hereby retained and reserved by the United States.

“In exercising such easement and right of access, neither the grantee nor its successors and assigns, as the case may be, shall have any claim at law or equity against the United States or any officer or employee of the United States based on actions taken by the United States or its officers, employees, agents, contractors of any tier, or servants pursuant to and in accordance with this clause: Provided, however, that nothing in this paragraph shall be considered as a waiver by the grantee and its successors and assigns of any remedy available to them under the Federal Tort Claims Act.”

E2.2—DEPARTMENT OF DEFENSE UNIFORM 120(h) CLAUSES FOR SECTION 120(h)(3)(C)(iii) OF THE COMPREHENSIVE ENVIRONMENTAL RESPONSE, COMPENSATION, AND LIABILITY ACT OF 1980 (42 U.S.C. § 9620(h)(3)(C)(iii))

E2.2.1. “___ . Property Covered by Notice, Description, Assurances, Access Rights, and Covenants Made Pursuant to Section 120(h)(3)(A) of the Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (42 U.S.C. § 9620(h)(3)(A)):”

[OPTION #1: FOR USE WHERE THE 120(h) CLAUSES ONLY APPLY TO CERTAIN PARCELS OF THE TOTAL PROPERTY.]

“For parcels _____ of the property, the Grantor provides the following notice, description, assurances, and covenants and retains the following access rights:”

[OPTION #2: FOR USE WHERE THE 120(h) CLAUSES APPLY TO THE ENTIRE PROPERTY.]

“For the property, the Grantor provides the following notice, description, assurances, and covenants and retains the following access rights:”

E2.2.2. “___ . Covenant Pursuant to Section 120(h)(3)(A)(ii)(II) and (B) of the Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (42 U.S.C. § 9620(h)(3)(A)(ii)(II) and (B)):

“Pursuant to section 120(h)(3)(A)(ii)(II) and (B) of the Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (42 U.S.C. § 9620(h)(3)(A)(ii)(II) and (B)), the United States warrants that any additional remedial action found to be necessary after the date of this deed shall be conducted by the United States.”

E2.2.3. “___ . Assurances Pursuant to Section 120(h)(3)(C)(ii) of the Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (42 U.S.C. § 9620(h)(3)(C)(ii)):

“Pursuant to section 120(h)(3)(C)(ii) of the Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (42 U.S.C. § 9620(h)(3)(C)(ii)), the United States provides the following response action assurances:

{(1) INSERT DESCRIPTION AND ASSURANCE OF ANY NECESSARY RESTRICTIONS ON THE USE OF THE PROPERTY TO ENSURE THE PROTECTION OF HUMAN HEALTH AND THE ENVIRONMENT;

(2) INSERT DESCRIPTION AND ASSURANCE OF ANY RESTRICTIONS ON USE NECESSARY TO ENSURE THAT REQUIRED REMEDIAL INVESTIGATIONS, RESPONSE ACTION, AND OVERSIGHT ACTIVITIES WILL NOT BE DISRUPTED;

(3) INSERT ASSURANCE THAT ALL NECESSARY RESPONSE ACTION WILL BE TAKEN AND IDENTIFY THE SCHEDULES FOR INVESTIGATION AND COMPLETION OF ALL NECESSARY RESPONSE ACTION AS APPROVED BY THE APPROPRIATE REGULATORY AGENCY; AND

(4) INSERT ASSURANCE THAT THE DoD COMPONENT WILL SUBMIT A BUDGET REQUEST TO THE DIRECTOR OF THE OFFICE OF MANAGEMENT AND BUDGET THAT ADEQUATELY ADDRESSES SCHEDULES FOR INVESTIGATION AND COMPLETION OF ALL NECESSARY RESPONSE ACTION, SUBJECT TO CONGRESSIONAL AUTHORIZATIONS AND APPROPRIATIONS.}”

[USER NOTE: THE FOLLOWING 120(h) CLAUSE GRANTED PURSUANT TO SECTION 120(h)(3)(C)(iii) IS GRANTED WHEN ALL RESPONSE ACTION NECESSARY TO PROTECT HUMAN HEALTH AND THE ENVIRONMENT WITH RESPECT TO ANY SUBSTANCE REMAINING ON THE PROPERTY ON THE DATE OF TRANSFER HAS BEEN TAKEN:]

E2.2.4. “___ . Warranty Pursuant to Section 120(h)(3)(C)(iii) of the Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (42 U.S.C. § 9620(h)(3)(C)(iii)):

“Pursuant to section 120(h)(3)(C)(iii) of the Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (42 U.S.C. § 9620(h)(3)(C)(iii)), the United States warrants that all response action necessary to protect human health and the environment with respect to any substance remaining on the property on the date of transfer has been taken.”

E2.3—DEPARTMENT OF DEFENSE UNIFORM 120(h) CLAUSES FOR SECTION 120(h)(4) OF THE COMPREHENSIVE ENVIRONMENTAL RESPONSE, COMPENSATION, AND LIABILITY ACT OF 1980 (42 U.S.C. § 9620(h)(4))

E2.3.1. “___ . Property Covered by Covenant and Access Rights Made Pursuant to Section 120(h)(4)(D) of the Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (42 U.S.C. § 9620(h)(4)(D)):”

[OPTION #1: FOR USE WHERE THE 120(h) CLAUSES ONLY APPLY TO CERTAIN PARCELS OF THE TOTAL PROPERTY.]

“For parcels _____ of the property, the Grantor provides the following covenants and retains the following access rights:”

[OPTION #2: FOR USE WHERE THE 120(h) CLAUSES APPLY TO THE ENTIRE PROPERTY.]

“For the property, the Grantor provides the following covenants and retains the following access rights:”

E2.3.2. “___ . Covenant Pursuant to Section 120(h)(4)(D)(i) of the Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (42 U.S.C. § 9620(h)(4)(D)(i)):

“Pursuant to section 120(h)(4)(D)(i) of the Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (42 U.S.C. § 9620(h)(4)(D)(i)), the United States warrants that any response action or corrective action found to be necessary after the date of this deed for contamination existing on the property prior to the date of this deed shall be conducted by the United States.”

E2.3.3. “ ___ . Access Rights Pursuant to Section 120(h)(4)(D)(ii) of the Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (42 U.S.C. § 9620(h)(4)(D)(ii)):

“The United States retains and reserves a perpetual and assignable easement and right of access on, over, and through the property, to enter upon the property in any case in which an environmental response or corrective action is found to be necessary on the part of the United States, without regard to whether such environmental response or corrective action is on the property or on adjoining or nearby lands. Such easement and right of access includes, without limitation, the right to perform any environmental investigation, survey, monitoring, sampling, testing, drilling, boring, coring, testpitting, installing monitoring or pumping wells or other treatment facilities, response action, corrective action, or any other action necessary for the United States to meet its responsibilities under applicable laws and as provided for in this instrument. Such easement and right of access shall be binding on the grantee and its successors and assigns and shall run with the land.

“In exercising such easement and right of access, the United States shall provide the grantee or its successors or assigns, as the case may be, with reasonable notice of its intent to enter upon the property and exercise its rights under this clause, which notice may be severely curtailed or even eliminated in emergency situations. The United States shall use reasonable means to avoid and to minimize interference with the grantee’s and the grantee’s successors’ and assigns’ quiet enjoyment of the property. At the completion of work, the work site shall be reasonably restored. Such easement and right of access includes the right to obtain and use utility services, including water, gas, electricity, sewer, and communications services available on the property at a reasonable charge to the United States. Excluding the reasonable charges for such utility services, no fee, charge, or compensation will be due the grantee, nor its successors and assigns, for the exercise of the easement and right of access hereby retained and reserved by the United States.

“In exercising such easement and right of access, neither the grantee nor its successors and assigns, as the case may be, shall have any claim at law or equity against the United States or any officer, employee, agent, contractor of any tier, or servant of the United States based on actions taken by the United States or its officers, employees, agents, contractors of any tier, or servants pursuant to and in accordance with this clause: Provided, however, that nothing in this paragraph shall be considered as a waiver by the grantee and its successors and assigns of any remedy available to them under the Federal Tort Claims Act.”

E3. ENCLOSURE 3

Table of CERCLA 120(h) Clauses

| Categories of CERCLA 120(h) clause requirements: | | |
|--|--|-----------|
| 120(h)(3) ¹ | 120(h)(3)(C) | 120(h)(4) |
| Applicable clauses for each category: | | |
| E2.1.1. | E2.2.1. | E2.3.1. |
| E2.1.2. | E2.1.2. | E2.3.2. |
| E2.1.3. | E2.1.3. | E2.3.3. |
| E2.1.4. ² | E2.2.2. ² | |
| E2.1.5. | E2.2.3. | |
| | E2.1.5. | |
| | After all response actions have been taken: | |
| | E2.2.1. ² | |
| | E2.2.4. ² | |

¹ But excluding those properties subject to deferral under paragraph 120(h)(3)(C).

² These clauses shall not be provided in any case in which the person or entity to whom the real property is transferred is a potentially responsible party with respect to such property.